



## **ITEM #1**

## SUBDIVISION COMMITTEE PRELIMINARY REPORT

**DATE:** May 5, 2021

**TO:** OC Subdivision Committee

FROM: OC Development Services / Land Development Division

**SUBJECT:** "B" Vesting Tentative Tract Map 19025 within Planning Area 3, Subarea 3.1, Ranch

Plan Planned Community

PROPOSAL: Applicant Rancho Mission Viejo requests approval of "B" Vesting Tentative Tract

Map 19025 (VTTM 19025) to subdivide a 8.16-acre site within Subarea 3.1 of the Ranch Plan Planned Community into 104 legal lots: 73 numbered lots for planned concept single-family detached dwellings, 8 numbered lots for pocket parks and landscaping, 1 lettered lot for a public street, 12 lettered lots for private streets and

alleys, and 10 lettered lots for landscaped open space areas.

**ZONING:** Ranch Plan Planned Community

**GENERAL** 6 "Urban Activity Center"

PLAN:

LOCATION: The project site is located in southeastern unincorporated Orange County, in

Subarea 3.1, Lots 1 through 11 and 74 of "A" Tract Map 17931, of the Ranch Plan

Planned Community, in the Fifth (5th) Supervisorial District.

**OWNER** RI

/SUBDIVIDER:

RMV PA3 Development, LLC ('RMV')

It should be noted that the current landownership is RMV, but the transfer of

ownership to Pulte Homes will begin upon final recordation.

**APPLICANT:** Rancho Mission Viejo

Jay Bullock, Vice President, Planning and Entitlement

STAFF Robert Zegarra, Contract Planner, Land Development Division

**CONTACT:** Phone: (714) 667-8893 FAX: (714) 667-7560

Email: robert.zegarra@ocpw.ocgov.com

### **RECOMMENDED ACTION(S):**

Land Development recommends that the Subdivision Committee:

- 1. Receive and review staff report;
- 2. Find that Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 2006; Addendum 1.1 (PA110003-06) approved February 24, 2011; the Planning Area 2 Addendum (PA130001-06) approved March 27, 2013; and Addendum 3.1 (PA140072-81) approved February 25, 2015; reflect the independent judgment of the County and are adequate to satisfy the requirements of CEQA for approval of Vesting Tentative Tract Map (VTTM) 19025, which is a necessarily included element contemplated as part of the whole of the action considered in Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1.
  - a. The circumstances of the project are substantially the same as described in Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1 which adequately addressed the effects of the project proposed in VTTM19025. No substantial changes have been made in the project that involve new significant environmental effects or a substantial increase in the severity of previously identified significant effects; no substantial changes have occurred in the circumstances under which the project is being undertaken, that involve new significant environmental effects or a substantial increase in the severity of previously identified environmental effects; and no new information of substantial importance to the project which was not known or could not have been known when Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, Addendum 3.1 were certified and approved has become known; therefore, no further environmental review is required.
  - b. Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1 are adequate to satisfy the requirements of CEQA for VTTM19025.
  - c. All mitigation measures are fully enforceable pursuant to Public Resources Code section 21081.6(b) and have either been adopted as conditions, incorporated as part of the project design, or included in the procedures of project implementation.
- 3. Approve VTTM19025, subject to the attached Findings and Conditions of Approval.

NOTE: Per State Law, for any improvements required prior to the recordation of a final map, the developer may instead enter into an agreement with the County of Orange guaranteeing all required improvements. Said agreement shall be accompanied by financial security.

#### **BACKGROUND AND EXISTING CONDITIONS:**

In November 2004, the County of Orange approved the Ranch Plan Planned Community, which encompasses approximately 22,815 acres located east of I-5, north and south of Ortega Highway at Antonio Parkway/La Pata Avenue, within the Fifth Supervisorial District. As approved, the Ranch Plan Planned Community comprises 75 percent permanent open space and allows for the development of 14,000 dwelling units and 5,200,000 square feet (SF) of non-residential uses in the remaining 25 percent. It is regulated by the Ranch Plan PC Program Text which addresses the unique characteristics of the property and a development plan for the transition to suburban/urban uses occurring over a 25- to 30-year period.

The Master Area Plan and Subarea Plans for Planning Areas 3 and 4 were originally approved on February 25, 2015 by the Planning Commission (PA140072-PA140081) and revised administratively on May 22, 2017 (PA150047). On September 11, 2019, the Planning Commission approved amendments and revisions to the Master Area Plans and Subarea Plans for Planning Areas 3 and 4 (PA180030) which reflect

the applicant's plan to develop Planning Area 3 in smaller phases. Final Tract Map 17931 for Subarea 3.1 was approved on December 8, 2020 by the County of Orange Board of Supervisors and was recorded on December 18, 2020. Currently, Subarea 3.1 is being graded under issued permit GRD19-0175 and supporting infrastructure (streets and storm Drains, etc.) is in various stages of construction.

## **Proposed Project**


The applicant, Rancho Mission Viejo, requests approval of "B" Vesting Tentative Tract Map 19025 (VTTM 19025) to subdivide a 8.16-acre site within Subarea 3.1 of the Ranch Plan Planned Community into 104 legal lots; 73 numbered lots for planned concept single-family detached dwellings, 8 numbered lots for pocket parks and landscaping, 1 lettered lot for a public street, 12 lettered lots for private streets and alleys, and 10 lettered lots for landscaped open space areas. This VTTM is one of multiple "B" maps proposed in Planning Area 3, Subarea 3.1 of the Ranch Plan. Further discussion is provided in the Discussion/Analysis section.

#### **SURROUNDING LAND USE:**

Land uses immediately surrounding the project site include the following:

- North: Future Subarea 3.2 development
- South: Saddle Way, Future Tract 19026 – TRIPointe single-family homes
- East: Future Subarea 3.2 development
- West: Ranch Canyon Road, Future Ranch Camp Recreation Facility

Please refer to The Ranch Plan General Vicinity Map, Exhibit 1, and the PA 3.1 Builder Map, Exhibit 2.



**Exhibit 1 - General Vicinity Map** 



Exhibit 2 – PA 3.1 Builder Map

## **DISCUSSION/ANALYSIS:**

## **General Description**

The proposed "B" VTTM 19025 is a subdivision of a 8.16-acre site within Subarea 3.1 of the Ranch Plan Planned Community into 104 legal lots; 73 numbered lots for planned concept single-family detached dwellings, 8 numbered lots for pocket parks and landscaping, 1 lettered lot for a public street, 12 lettered lots for private streets and alleys, and 10 lettered lots for landscaped open space areas with general access to the tract provided from Saddle Way. A model complex is proposed for Lots 52 through 58. The tract map has been designed to create individual planned concept detached lots oriented around private alleys. Main access is provided via a new in-tract public street (Ivy Way) which provides access to a private loop street and 11 alleys throughout the tract. The private loop street and 11 alleys provide direct access to the individual units and have been designated as Lots M and Lots A through K, respectively. Lettered Lots N through W have been designated for landscaped open space and Lots 74 through 81 have been designated for pocket parks and landscaping.

# Consistency Analysis:

Proposed "B" VTTM 19025 is consistent with:

- a. State Subdivision Map Act and County of Orange Subdivision Code and Manual
- b. General Plan, Land Use Element: 6 Urban Activity Center. The proposed map is consistent with the 6 Urban Activity Center designation
- Zoning: Planned Community. The proposed map is in conformance with the County of Orange Planned Community District regulations as regulated by the Ranch Plan Planned Community Text, statistical summary, and development maps

- d. Area Plans. The proposed map is consistent with the PA3 Master Area Plan, Subarea Plan 3.1, and the PA3 Master Area and Subarea Plan Amendments (PA180030)
- e. CEQA: The proposed map is consistent with Program EIR 589, which was certified on November 8, 2004; Addendum 1.0, approved on July 26, 2006; Addendum 1.1, approved on February 24, 2011; the Planning Area 2 Addendum, approved on March 27, 2013; and Addendum 3.1 approved February 25, 2015
- f. Alternative Development Standards: All previously approved Alternative Development Standards that are to be incorporated into the development of Subarea 3.1 are listed on the cover page of proposed VTTM 19025
- g. Regulation Compliance Matrix: Clearance of all applicable conditions of approval have been confirmed per the Ranch Plan Regulation Compliance Matrix

## **Estimated Earthwork**

The estimated grading quantities for this map are substantially consistent with or less than the earthwork quantities described under previous approvals (i.e. Master Area Plan (PA3), Subarea Plan 3.1, Tract 17931) and related grading permit GRD19-0175. The proposed grading on this map has been addressed per CEQA document FEIR 589, together with Addendum 3.1.

## **Drainage:**

The subject property is in the Ranch Plan Planned Community Runoff Management Plan (ROMP) Area. A Master Plan of Drainage (MPD) consistent with the PA3 and 4 ROMP has been established for the project site (Subarea 3.1). VTTM 19025 is consistent with this MPD, however no MPD fees are required.

#### Recreation and Open Space:

The proposed map is not required to provide any improvements or dedications associated with the County Master Plan of Regional Recreation Facilities; Master Plan of Regional Riding and Hiking Trails; Resources Element (Open Space Component); or the County Bikeway Plan.

- Master Plan of Regional Recreation Facilities There are no regional park dedication requirements of the subject map.
- Master Plan of Regional Riding and Hiking Trails There are no riding and hiking trail requirements of the subject map.
- Master Plan of Local Parks (Local Park Code) The proposed map is required to provide park land in accordance with the Master Plan of Local Parks (Local Park Code). The Local Park Code requirement for the subject map VTTM 19025 is 0.44 net usable acres of park land based upon a proposal to build 73 dwelling units at a gross residential density of 9.0 du/ac (73 du x .006 ac/du). Said requirement can be satisfied by an allocation of parkland credit from Park Modification PM07-01, the Local Park Implementation Plan (LPIP) for the Ranch Plan P.C. originally approved March 14, 2007, 1st Amendment approved in June 2012, 2nd Amendment approved on July 16, 2014, and 3rd Amendment approved on November 20, 2019.

Per the Ranch Plan LPIP, the total parkland acreage requirement for the entire Ranch Plan Planned Community is 94 acres, based on 14,000 approved dwelling units and the anticipated proportion

of single-family and multi-family units. The Ranch Plan LPIP (PM07-01) indicates that far more acres of total community-wide parkland will be implemented in Planning Area 3&4 than would be required per County Standards, based on the 7,500 dwelling units entitled by the PA3 and 4 Master Area Plan PA180030, per the parkland generation factor for each unit (greater than 6.5 du/ac requires 0.006 acres and less than 6.5 du/ac requires 0.008 acres). Final Map 17931 for Subarea 3.1 will include 6.6 acres of recreation facilities (Ranch Camp).

- Resources Element Open Space Component There are no open space dedication requirements applicable to the subject map.
- County Bikeway Plan There are no bikeways identified within the area of this map.

## Public Services & Utilities

- Schools This property is within the boundaries of the Capistrano Unified School District. The developer is subject to the provisions of Assembly Bill AB 2926, or other mitigating measures designed to provide for school facilities and/or funding, such as community facilities districts, as outlined by Mitigation Measure 4.15-5 of FEIR 589.
- Facilities Fees Programs This project area is included within the Ranch Plan Planned Community
  Development Facility Agreement area which phases development commensurate with public
  services and facilities.
- Water/Sewer This project is within the boundaries of the Santa Margarita Water District ("District"). The District stated in their Preliminary Water Sewer Letter dated December 17, 2020 that the District can and will provide water and sewage disposal service to this development.
- Water Quality Control This project will be required to operate in accordance with requirements prescribed by the California Regional Water Quality Control Board, San Diego Region, as outlined by Standard Conditions 4.5-3 thru 4.5-11 of FEIR 589.
- Fire Protection and Safety Existing and proposed fire protection services are capable of providing an adequate level of fire protection services to this development. This property is within the area covered by the Ranch Plan Fire Protection Program (RPFPP) and a project specific Fire Master Plan (SR# 292620) has been approved in compliance with all applicable regulations.
- County Service Area (CSA) This property is within the boundaries of County Service Area No. 26.

## Traffic/Circulation

- Scenic Highway Corridors There are no Scenic Highways applicable to this map.
- Access/Highways/Streets/Roads Access to the site is provided from Ivy Way via Saddle Way.
   Internal tract access will be provided by a system of private streets and alleys.
- Major Thoroughfare and Bridge Fee Program This project lies within the area of benefit of the Foothill/Eastern Transportation Corridor. The developer is required to pay Foothill/Eastern Major Thoroughfare and Bridge fees in accordance with the adopted program.
- Off-Site Fee Program The project lies within the area of benefit of the South County Roadway Improvement Road Fee Program (SCRIP). The developer is required to pay SCRIP fees in accordance with the adopted program.

To ensure that necessary ingress and egress easements are provided along the proposed motor courts/alleyways with the Final Map, Condition of Approval #7 requires the developer to demonstrate on the Final Map, subject to the satisfaction of the Deputy Director, OC Development Services, that improvements will not be constructed within the ingress and egress easements, which could interfere with the use and/or maintenance of the easement.

#### Fire Master Plan

The applicant has provided a copy of the Orange County Fire Authority (OCFA) Fire Master Plan, Service Request number 292620, approved on April 21, 2021. OCFA has reviewed the proposed project and has concurred with the proposal. OCFA and Land Development will continue to coordinate necessary plan check reviews during the permitting and construction process to ensure establishment of VTTM 19025 in compliance with associated fire safety and fire protection requirements.

## **ALTERNATIVE DEVELOPMENT STANDARDS:**

As allowed by General Regulation #25 of the Ranch Plan Planned Community Program Text, proposed Alternative Development Standards are intended to be incorporated into the development as listed within the "Notes" portion of the cover page of VTTM 19025. The following approved Ranch PC Alternative Development Standards (approved September 26, 2018) are proposed as part of VTTM 19025:

- A-1 36-foot Double Loaded Streets (up to 800 ADT)
- A-5 Residential Parkways
- A-9 Tapered Street Double Loaded
- A-19 Cul-De-Sacs with Raised Landscape Median
- A-20 Alternative Neighborhood Sidewalk Detail-Curb Separated Walkway
- A-36 Ribbon Curb
- B-9 Modified Color of Curb Ramp Detectable Warning Surface
- D-8 Planned Concept Residential Lots Greater Than 3,000 Square Feet
- D-17 Credit Toward Usable Private Open Space
- G-3a Private Alley Drive Allowing Emergency Vehicle Access
- G-3b Private Alley Drive with No Requirement for Emergency Vehicle Access
- G-7 Reduced Local Depression on Private Streets
- G-9 Rolled Curb on Private Streets

#### REFERRAL FOR COMMENT AND PUBLIC NOTICE:

Copies of the tentative map application submittal package were distributed for review and comment to County staff and consultants, including Land Development, Traffic & Development, Inspection Services, Operations & Maintenance, Building & Safety, OC Survey, and the Orange County Fire Authority. Through a collaborative effort with County staff, the applicant adequately addressed all comments. As of the writing of this staff report, no further comments have been received by any County divisions.

A Notice of Public Meeting was mailed to all property owners of record within 300 feet of the subject site on April 23, 2021. Additionally, notices were posted at the site, at the Orange County Hall of Administration, and at the County Administration South (CAS) Building, as required by established public meeting posting procedures. No public comments have been received to date.

### CEQA COMPLIANCE:

The proposed project is covered by previous CEQA documentation, which includes Final Program EIR 589, which was certified on November 8, 2004; Addendum 1.0, approved on July 26, 2006; Addendum 1.1, approved on February 24, 2011; the Planning Area 2 Addendum, approved on March 27, 2013; and Addendum 3.1, approved February 25, 2015. This finding is appropriate and complies with the intent of CEQA, pursuant to the Orange County 2020 Local CEQA Procedures Manual, Section 13.1 for projects where a previous environmental document (i.e. Program EIR 589) is already in place. Further CEQA evaluation and clearances are not required for proposed "B" VTTM 19025.

#### CONCLUSION:

Based upon the review of the subject submittal, staff supports approval of the applicant's proposed Vesting Tentative Tract Map 19025 (VTTM 19025) pursuant to the Orange County Subdivision Code, Orange County Codified Ordinances (OCCO), Subarticle 5 (Processing Procedures for Tentative Maps).

Submitted by:

Bea Bea Jiménez, Division Manager, Land Development, OC Development Services Amanda Carr, Deputy Director
OC Public Works, OC Development Services

imender (an

## **CERTIFICATION:**

I hereby certify that the Tentative Tract Map 19025 was approved by the Orange County Subdivision Committee on May 5, 2021, per the findings in Appendix A and the conditions in Appendix B.

Laree Alonso, Subdivision Committee Chairperson

#### **APPENDICES:**

- A. Recommended Findings
- B. Recommended Conditions of Approval
- C. Ranch Plan Regulation Compliance Matrix "B" Map Items

#### **ATTACHMENTS:**

- 1. Applicant's Letter of Proposal
- 2. Will Serve Letter
- 3. Project Plans and Fire Master Plan

#### APPEAL PROCEDURE:

Any interested person may appeal the decision of the Subdivision Committee on this application to the Orange County Planning Commission within 10 calendar days of the decision upon submittal of required documents and a filing fee of \$500.00 filed at 601 N. Ross St., Santa Ana. If you challenge the action taken on this proposal in court, you may be limited to raising only those issues you or someone else raised in written correspondence delivered to OC Development Services.

# **APPENDIX A**



## Appendix A Findings VTTM 19025

1 EIR AND ADDENDUM VTTM 19025

That the decision-maker has considered Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 2006; Addendum 1.1 (PA110002-PA110006) approved February 24, 2011; the Planning Area 2 Addendum (PA130001-PA130004 and PA130006) approved on March 27, 2013; and Addendum 3.1 (PA140072-81) approved February 25, 2015 prior to project approval. The addendums are approved for the proposed project based upon the following findings:

- a. Together, these documents are adequate to satisfy the requirements of CEQA by the decision-maker;
- b. The additions, clarifications and/or changes to the original document caused by the Addendums, do not raise new significant issues which were not addressed by the EIR and none of the conditions described in CEQA Guidelines Section 15162 applies; and
- c. The consideration of the EIR and approval of the Addendums for the proposed project reflect the independent judgment of the Lead Agency.

#### ENVIRONMENTAL MONITORING VTTM 1902

That the monitoring requirements of Public Resources Code Section 21081.6 (AB 3180) will be considered as having been met in that the design of the subject project, the satisfaction of the requirements of the County's building, grading, fire, and other codes and ordinances and the satisfaction of the conditions of approval applied to the project will implement the mitigation measures contained in EIR No. 589, Addendum 1 (PA06-0023), Addendum 1.1 (PA110003-0006), the Planning Area 2 Addendum (PA130001-0004 and PA130006), and Addendum 3.1 (PA140072-81).

GENERAL PLAN CONSISTENCY VTTM 19025

That the proposed map is consistent with the Orange County General Plan.

4 DESIGN & IMPROVEMENT VTTM 19025

That the design and improvement of the proposed subdivision are consistent with the Orange County General Plan.

5 DEVELOPMENT TYPE VTTM 19025

That the proposed site is physically suitable for the proposed type of development.

6 DEVELOPMENT DENSITY VTTM 19025

That the proposed site is physically suitable for the proposed density of development.

7 ENVIRONMENTAL DAMAGE VTTM 19025

That the design of the subdivision or the proposed improvements are not likely to cause substantial environmental damage or substantial and avoidable injury to fish or wildlife or their habitat.

8 PUBLIC HEALTH VTTM 19025

That the design of the subdivision and the type of improvements proposed are not likely to cause serious public health problems.

9 PUBLIC EASEMENTS VTTM 19025

That the design of the subdivision and the type of improvements proposed will not conflict with easements of record or established by court judgment acquired by the public-at-large for access through or use of property within the proposed subdivision.

10 SUBDIVISION / ZONING CODE CONSISTENCY VTTM 19025

That the proposed subdivision complies with the requirements set forth in the Orange County Subdivision Code and the Orange County Zoning Code.

11 ZONING CONSISTENCY VTTM 19025

That the design and improvement of the proposed subdivision are suitable for the uses proposed, and the subdivision can be developed in compliance with applicable zoning regulations pursuant to Section 7-9-254 of the Subdivision Code.

12 SEWER SYSTEM VTTM 19025

That the discharge of waste from the proposed subdivision into the existing sewer system of the Water District will not result in violations of existing requirements prescribed by the California Regional Water Quality Control Board, San Diego Region.

13 NATURAL HEATING AND COOLING VTTM 19025

That the design of the subdivision and its improvements do provide, to the extent feasible, for future passive or natural heating or cooling opportunities as specified in Section 66473.1 of the Government Code (Subdivision Map Act).

14 FEE PROGRAMS VTTM 19025

That the following determinations apply to fees required by Sections 7-9-700 through 713, Codified Ordinances of Orange County:

- A. Purpose of fees: Fire protection, paramedic, law enforcement, library, and general County services.
- B. Use of fees: Construction of new fire station, sheriff substation, library, and general County facilities in newly developing areas which have inadequate service.
- C. Relationship between use of fees and type of development: Dwelling units and commercial/industrial structures and their occupants require fire protection, paramedic, law enforcement, library, and general County services.
- D. Relationship between need for facilities and type of project: Project is located in newly developing area which has inadequate fire protection, paramedic, library services, and sheriff substation and general County facilities.
- E. Relationship between amount of fees and cost of the portion of the facilities attributable to the development: Fees represent project's pro rata share of the cost of the fire station, sheriff substation, library, and general County facilities.

15 EXPIRATION OF MAPS VTTM 19025

That because of participation in fee programs for off-site improvements, this project will qualify for consideration under Section 66452.6 of the Subdivision Map Act.

16 LOCAL PARK CODE VTTM 19025

That the Local Park Code requirement can be met by an allocation of park lands credit from PM 07-01, the park implementation plan for the Ranch Plan Planned Community.

17 DEVELOPMENT AGREEMENT VTTM 19025

That the Development Agreement contains provisions requiring developer participation in fee programs, facility construction and development phasing and is therefore in compliance with the adopted Growth Management Element in terms of public services and facilities being made available to accommodate development.

18 APPEAL OF EXACTIONS VTTM 19025

That the applicant is hereby provided notice that the fees, dedications, reservations or other exactions imposed on this project are as described in this approval as well as the reports and actions accompanying this approval and that the 90-day approval period in which the applicant may protest pursuant to Government Code Section 66020 has begun.

# **APPENDIX B**



## **Appendix B Conditions of Approval**

VTTM 19025

#### RANCH PLAN REGULATION COMPLIANCE MATRIX VTTM 19025

The applicant shall comply with all applicable requirements of the Ranch Plan Regulation Compliance Matrix: to the satisfaction of the appropriate decision maker listed in each applicable Regulation Compliance Matrix item. The applicable requirements are listed below and attached as Appendix C:

```
139: EIR 589 Mitigation Measure 4.9-27 - Invasive Plants CC&R Prohibition
524: EIR 589 Stand. Cond. 4.4-3 (G04) - Off-site Letter of Consent (if necessary)
527 & 527.1: EIR 589 Standard Condition 4.5-1 (D01a) - Drainage Study
528 & 528.1: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements
528: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements
529: EIR 589 Standard Condition 4.5-4 (D02b) – Drainage Improvements
532: EIR 589 Standard Condition 4.5-5 (D06b) – Subordination of Easements
533: EIR 589 Standard Condition 4.5-5 (D06b) – Subordination of Easements
534: EIR 589 Standard Condition 4.5-5 (D06b) – SMWD Easements
535: EIR 589 Standard Condition 4.5-6 (D07b) – Regional Facility Improvements
537 & 537.1: EIR 589 St. Cond. 4.5-8 (WQQ1) – Water Quality Management Plan (WQMP)
538: EIR 589 St. Cond. 4.5-8 (WQ03) – Water Quality Management Plan (WQMP) 544: EIR 589 Standard Condition 4.6-2 (T01) – Vehicular Access Rights 545: EIR 589 Standard Condition 4.6-3 (T02) – Private Street Improvements
546: 546.1: 546.2 & 546.3: SC 4.6-4: (T04) - Street Improvements
549: EIR 589 Standard Condition 4.6-7 (T08) - Traffic Signal Conduit
550, 550.1, 550.2 & 550.3: EIR 589 Stand. Cond. 4.6-8 (T12) - Internal Circulation
551: EIR 589 Standard Condition 4.6-9 (T13b) - Traffic Signal Maintenance Easement
 552: EIR 589 Standard Condition 4.6-10 (T14b) - Traffic Signal Installation
 559 & 559.1: EIR 589 Standard Condition 4.8-3 (N01) - Sound Attenuation
 589.1: EIR 589 Standard Condition 4.15-1 - Water Improvement Plans
597: EIR 589 Standard Condition 4.15-9 - Capistrano Unified School District fees
619: Ranch Plan Fire Prot. Program Cond. 4 - OCFA Administrative Approval
b. Prior to Approval of Site Development Permit
109: EIR 589 Mitigation Measure 4.7-3 – Shade Trees in Parking Lot Design
110: EIR 589 Mitigation Measure 4.7-3 - Use of Light-Colored Roof Materials
c. Prior to Issuance of Grading Permits
521: EIR 589 Standard Condition 4.4-1 (G01) – Geotechnical report
522: EIR 589 Standard Condition 4.4-2 (G02) - Conformance with TT Map 523: EIR 589 Standard Condition 4.4-2 (G02) - Revised TT Map (if necessary)
524: EIR 589 Stand. Cond. 4.4-3 (G04) - Off-site Letter of Consent (if necessary)
 525: EIR 589 Standard Condition 4.4-4 (G09) - Consistency with Planning Approval
527 & 527.1: EIR 589 Standard Condition 4.5-1 (D01a) - Drainage Study
 528 & 528.1: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements
520 & 520. 1. EIR 569 Standard Condition 4.5-2 (D02a) – Drainage Improvements 530 & 530.1: EIR 589 Standard Condition 4.5-3 (D02b) – Drainage Improvements 537 & 537.1: EIR 589 St. Cond. 4.5-8 (WQ01) – Water Quality Management Plan (WQMP) 538: EIR 589 St. Cond. 4.5-8 (WQ03) – Water Quality Management Plan (WQMP) 540: EIR 589 St. Cond. 4.5-10 (WQ04) – Stormwater Pollution Prevention (SWPPP) 541: EIR 589 St. Cond. 4.5-11 (WQ05) – Erosion and Sediment Control Plan 548: EIR 589 Standard Condition 4.6-6 (T07) – Sight Distance
548: EIR 589 Standard Condition 4.6-6 (T07) – Sight Distance
555, 555.1 through 555.5: EIR 589 Standard Condition 4.7-1 – Fugitive Dust
556, 556.1, 556.2 & 556.3: EIR 589 Standard Condition 4.7-2 – Emission Control
557: EIR 589 Standard Condition 4.8-1 (N10) – Hours of Construction 558, 558.1, 558.2, 558.3 & 558.4: EIR 589 St. Condition. 4.8-2 (N10) – Construction Noise
559 & 559.1: EIR 589 Standard Condition 4.8-3 (N01) - Sound Attenuation
567: EIR 589 Standard Condition 4.10-2 (LA02b) - Private Area Landscaping
571: EIR 589 Standard Condition 4.11-1 (A04) - Archaeology Grading Observation and Salvage
574: EIR 589 Standard Condition 4.11-2 (A07) – Paleontology Resource Surveillance 589: EIR 589 Standard Condition 4.14-2 – Hazardous Materials
616: Ranch Plan Fire Prot. Program Cond. 3.d. - Precise Fuel Modification Plan
d. Prior to Precise Fuel Modification Plans:
138: EIR 589 Mitigation Measure 4.9-27 - Invasive Plants and Fuel Modification
e. Prior to Issuance of Building Permit:
111: EIR 589 Mitigation Measure 4.7-3 – Use of Light-Colored Roof Materials 140: EIR 589 Mitigation Measure 4.9-28 – Open Space habitat, light shields 206: EIR 589 Mitigation Measure 4.15-5 – Capistrano Unified School District fees
526: EIR 589 Standard Condition 4.4-5 - Compliance with Code
537 & 537.1: EIR 589 St. Cond. 4.5-8 (WQ01) – Water Quality Management Plan (WQMP) 538: EIR 589 St. Cond. 4.5-8 (WQ03) – Water Quality Management Plan (WQMP) 540: EIR 589 St. Cond. 4.5-10 (WQ04) – Stormwater Pollution Prevention (SWPPP)
541: EIR 589 St. Cond. 4.5-11 (WQ05) - Erosion and Sediment Control Plan
547: EIR 589 Standard Condition 4.6-5 (T05) – Major Thoroughfare & Bridge Fees 550, 550.1, 550.2 & 550.4: EIR 589 Standard Condition 4.6-8 (T12) – Internal Circulation
 559.2 & 559.3: EIR 589 Standard Condition 4.8-3 (N01) - Sound Attenuation
564 & 564.1: EIR 589 Standard Condition 4.10-1 (LA01b) - Public Area Landscaping
570: EIR 589 Standard Condition 4.10-3 (LG01) - Light and Glare
```

589: EIR 589 Standard Condition 4.14-2 – Hazardous Materials 617: Ranch Plan Fire Prot. Program Cond. 3.e. – Vegetation Clearance f. Prior to Combustible Construction:

609: Ranch Plan Fire Prot. Program Cond. 2.d. - Emergency Access & Water Supply

#### g. During Construction:

197: EIR 589 Mitigation Measure 4.14-13 - ESA Remedial Measures

h. Prior to Certificates of Occupancy: 529: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements

531: EIR 589 Standard Condition 4.5-3 (D02b) - Drainage Improvements

539, 539.1 & 539.2: EIR 589 Standard Condition 4.5-9 (WQ03) - Compliance with Water Quality Management Plan (WQMP)

560: EIR 589 Standard Condition 4.8-4 (N09) – Multi-Family Residential Development 563: EIR 589 Standard Condition 4.8-7 (N12) – Transportation Corridor Notification

565 & 566: EIR 589 Standard Condition 4.10-1 (LA01b) - Public Area Landscaping

568 & 569: EIR 589 Standard Condition 4.10-2 (LA02b) - Private Area Landscaping

618: Ranch Plan Fire Prot. Program Cond. 3.f. - Fuel Modification Zones

i. Prior to Release of Grading Bond:

572 & 573: EIR 589 Standard Condition 4.11-1 (A04) – Archaeology Grading Observation and Salvage 575 & 576: EIR 589 Standard Condition 4.11-2 (A07) – Paleontology Resource Surveillance

#### WATER QUALITY MANAGEMENT PLAN VTTM 19025

Prior to the issuance of any grading or building permits, the applicant shall submit for review and approval by the Manager, Permit Services, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. The applicant shall utilize the Orange County Drainage Area Management Plan (DAMP), Model WQMP, and Technical Guidance Manual for reference, and the County's WQMP template for submittal. This WQMP shall include the following:

- Detailed site and project description
- Potential stormwater pollutants
- Post-development drainage characteristics
- Low Impact Development (LID) BMP selection and analysis
- Structural and Non-Structural source control BMPs
- Site design and drainage plan (BMP Exhibit)
- GIS coordinates for all LID and Treatment Control BMPs
- Operation and Maintenance (O&M) Plan that (1) describes the long-term operation and maintenance requirements for BMPs identified in the BMP Exhibit; (2) identifies the entity that will be responsible for long-term operation and maintenance of the referenced BMPs; and (3) describes the mechanism for funding the long-term operation and maintenance of the referenced BMPs

The BMP Exhibit from the approved WQMP shall be included as a sheet in all plan sets submitted for plan check and all BMPs shall be depicted on these plans. Grading and building plans must be consistent with the approved BMP exhibit.

#### **BEST MANAGEMENT PRACTICES** VTTM 19025

Prior to issuance of a building permit, the off-site regional Best Management Practices (BMPs) relied upon by this project (e.g., basins, swales, etc.) must be built and/or installed, and operational. The location and operation of these regional BMPs must be in compliance with the Final Project-Specific WQMP for the regional BMP(s). The location and operation of the regional BMP(s) must be demonstrated to the satisfaction of the Manager, Grading and Building Plan Check.

## COMPLIANCE WITH THE NPDES IMPLEMENTATION PROGRAM VTTM 19025

Prior to the issuance of a certificate of use and occupancy, the applicant shall demonstrate compliance with the County's NPDES Implementation Program in a manner meeting the satisfaction of the Manager, OC Inspection, including:

- Demonstrate that all structural Best Management Practices (BMPs) described in the BMP Exhibit from the project's approved WQMP have been implemented, constructed and installed in conformance with approved plans and specifications
- Demonstrate that the applicant has complied with all non-structural BMPs described in the project's WQMP
- Submit for review and approval an Operations and Maintenance (O&M) Plan for all structural BMPs (the O&M Plan shall become an attachment to the WQMP:
- Demonstrate that copies of the project's approved WQMP (with attached O&M Plan) are available for each of the initial occupants;
- Agree to pay for a Special Investigation from the County of Orange for a date twelve (12) months after the issuance of a Certificate of Use and Occupancy for the project to verify compliance with the approved WQMP and O&M Plan
- Demonstrate that the applicant has RECORDED one of the following:
- 1. The CC&R's (that must include the approved WQMP and O&M Plan) for the project's Homeowner's Association;
- 2. A water quality implementation agreement that has the approved WQMP and O&M Plan attached; or
- 3. The final approved Water Quality Management Plan (WQMP) and Operations and Maintenance (O&M) Plan.

(Appendix C - Items 539, 539.1, 539.2)

#### INDEMNIFICATION VTTM 19025

Applicant shall defend with counsel approved by the County of Orange in writing, indemnify and hold harmless the County of Orange, its officers, agents and employees from any claim, action or proceeding against the County, its officers, agents or employees to attack, set aside, void, or annul any approval of the application or related decision, or the adoption of any environmental documents, findings or other environmental determination, by the County of Orange, its Board of Supervisors, Planning Commission, Zoning Administrator, Director of OC Public Works, or Director of Planning concerning this application. The County may, at its sole discretion, participate in the defense of any action, but such participation shall not relieve applicant of his/her obligations under this condition. Applicant shall reimburse the County for any court costs and attorney's fees that the County may be required to pay as a result of such action. The County shall promptly notify the applicant of any such claim, action or proceeding.

#### **BUYER NOTIFICATION MAP** VTTM 19025

Prior to the issuance of any building permits for residential construction, the developer RMV Community Development, LLC, shall prepare a map denoting the existing and proposed land uses, arterial highways, and public facilities within the surrounding area for the approval of the Manager, OC Planning. The map content, display, and distribution shall be in accordance with the Buyer Notification Program guidelines listed in Board of Supervisors Resolution 82-1368 and as amended.

#### MANEUVERABILITY EASEMENT VTTM 19025

Prior to recordation of the final tract map, the subdivider shall demonstrate that all necessary ingress/egress easements for vehicle maneuverability within motor courts/alleyways are identified on the final map subject to the satisfaction of the Manager, Land Development. The easement shall prohibit property owners from installing any improvements within the easement area or interfering with the use or maintenance of the easement.

## 8 LOTS 74 THROUGH 81 VTTM 19025

Prior to recordation of the final tract map, a note shall be provided on the map indicating that Lots 74 through 81 shall be developed exclusively as recreation/open and landscape area as shown on VTTM 19025, and that Lots 74 through 81 shall not be developed as residential lots or for any other use, subject to the satisfaction of the Manager, Land Development.

# **APPENDIX C**

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
a.	Prior to	Reco	rdation									
139	137-138 (EIR 589, MM 4.9-27)	EIR 589	MM 4.9-27 (cont.)	Prior to the recordation of a map for tract adjacent to the RMV Open Space	Biological Resources	CC&Rs, California Exotic Pest Plant Council	Invasive Plants CC&R Prohibition	b. Prior to the recordation of a map for a tract adjacent to the RMV Open Space, the County of Orange shall verify that the CC&Rs contain language prohibiting the planting of plants identified by the California Exotic Pest Plant Council as an invasive risk in Southern California in private landscaped areas.	Director, PDS Director, OC Planning	Provide letter stating that CC&Rs contain language prohibiting the planting of plants on most current California Invasive Plant Inventory	To be cleared for entire Planned Community, upon providing RMV CC&R summarv letter [Hyperlink #13] stating CC&Rs contain language prohibiting the planting of plants on most current California Invasive Plant Inventory (www.cal-ipc.org) in private landscape areas. Only applies to recordation of tract maps that include lots located inmediately adjacent to RMV Open Space	Each PA
524		EIR 589		Prior to the recordation of a subdivision map or prior to issuance of a Grading Permit, whichever comes first	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to the recordation of a subdivision map or prior to the issuance of any grading permit, whichever comes first, and if determined necessary by the County of Orange Manager, Subdivision and Grading, the applicant shall record a letter of consent from the affected property owners permitting off-site grading, cross lot drainage, drainage diversions and/or unnatural concentrations. The applicant shall obtain approval of the form of the letter of consent from the Manager, Subdivision and Grading Services before recordation of the letter. (County Standard Condition G04)	Director-of- Planning & Development- Services- Director, OC Planning	Recordation of a letter of consent from affected property owners if determined necessary by County of Orange Director of Planning & Development Services		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
527		EIR 589	SC 4.5-1	Prior to recordation of a Subdivision Map or issuance of a Grading Permit, whichever comes first	Drainage Study:		Drainage Study:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the following drainage studies shall be submitted to and approved by the Manager, Subdivision and Grading: (County Standard Condition D01a)		Submittal of satisfactory of drainage study		Each PA
527.1		EIR 589	SC 4.5-1 (cont.)	See above	Drainage Study (cont.):		Drainage Study (cont.):	A. A drainage study of the project including diversions, off-site areas that drain onto and/or through the project, and justification of any diversions; and B. When applicable, a drainage study evidencing that proposed drainage patterns will not overload existing storm drains; and C. Detailed drainage studies indicating how the project grading, in conjunction with the drainage conveyance systems including applicable swales, channels, street flows, catch basins, storm drains, and flood water retarding, will allow building pads to be safe from inundation from rainfall runoff which may be expected from all storms up to and including the theoretical 100-year flood. (County Standard Condition D01a)	See above	See above		Each PA
528		EIR 589	SC 4.5-2	Prior to recordation of a Subdivision Map or Issuance of a Grading Permit, whichever comes first	Drainage Improvements:		Drainage Improvements:	A. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the applicant shall in a manner meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition D02a)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Approval of storm drain drainage plans and offer(s) of dedication, if necessary		Each PA
528.1		EIR 589	SC 4.5-2 (cont.)	See above	Drainage Improvements (cont.):		Drainage Improvements (cont.):	Design provisions for surface drainage;     Design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and     Dedicate the associated easements to the County of Orange, if determined necessary.  (County Standard Condition D02a)	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
529		EIR 589	SC 4.5-2 (cont.)	Prior to recordation of a Subdivision Map or Issuance of a Certificate of Use and Occupancy, whichever comes first	Drainage Improvements (cont.):		Drainage Improvements (cont.):	B. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any certificates of use and occupancy, whichever occurs first, said improvements shall be constructed in a manner meeting the approval of the Manager, Construction. (County Standard Condition D02a)	County of Orange Manager of Inspection, Manager, OC Inspection Division	Verification of construction of drainage improvement		Each PA
532		EIR 589	SC 4.5-4	Prior to the	Master Plan of Drainage:		Master Plan of Drainage:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only), the subdivider shall	Director of Planning &	Verification of participation in Master Plan of Drainage (fees and/or improvements)	See guidance above related to Item No. 30.	Each PA
533		EIR 589	SC 4.5-5	Prior to the recordation of a Subdivision Map	Subordination of Easements:		Subordination of Easements:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only), the subdivider shall not grant any easements over any property subject to a requirement of dedication or irrevocable offer to the County of Orange or the Orange County Flood Control District, unless such easements are expressly made	Director of Planning & Development Services Director, OC Planning	that any granted	Except in those cases where the County of Orange and the public entity grantee have previously mutually agreed upon conditions to coexist within the easement area.	Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
534		EIR 589	SC 4.5-5 (cont.)	See above	Subordination of Easements (cont.):		Subordination of Easements (cont.):	of facilities located within the easement; however, in no event shall Santa Margarita Water District be responsible for the cost of relocating its facilities in event of conflicts	County of Orange- Director of- Planning &- Development- Services- Director, OC Planning (Orange County Flood Control District and Santa Margarita Water District)		Except in those cases where the County of Orange and the public entity grantee have previously mutually agreed upon conditions to coexist within the easement area.	Each PA
535		EIR 589		Prior to County of Orange acceptance of improvements as identified by separate agreement thereordation of a Subdivision-Map	Regional Facility Improvements:		Regional Facility Improvements:	agreement the recordation of a subdivision map, the applicant shall improve Regional Facility by the construction (or evidence of financial security, such as bonding) of an IOD shall be recorded offering said improvements and dedicate right-of-way to the Orange County Flood Control District in a manner meeting the approval of the Manager, Subdivision	Planning & Development Services	Verification of construction and/or offer(s) of dedication for flood control improvements		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
537		EIR 589		Prior to the recordation of a Subdivision Map or the issuance of any Grading or Building Permit, whichever comes first	Water Quality Management Plan:		Water Quality Management Plan:	Prior to the recordation of any final subdivision map (except those maps for financing or conveyance purposes only) or the issuance of any grading or building permit (whichever comes first), the applicant shall submit for review and approval by the Manager, Inspection Services Division, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. This WQMP shall identify, at a minimum, the routine structural and non-structural measures specified in the current Drainage Area Management Plan (DAMP). The WQMP may include one or more of the following: (County Standard Condition WQO11)	Planning & Development	Submittal of satisfactory Water Quality Management Plan		Each PA
537.1		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Discuss regional water quality and/or watershed programs (if available for the project);     Address Site Design BMPs (as applicable) such as minimizing impervious areas, maximizing permeability, minimizing directly connected impervious areas, creating reduced or "zero discharge" areas, and conserving natural areas;     Include the applicable Routine Source Control BMPs as defined in the DAMP. (County Standard Condition WQ01)	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
538		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate how surface runoff and subsurface drainage shall be managed and directed to the nearest acceptable drainage facility (as applicable), via sump pumps if necessary. (Standard Condition of Approval, WQ03)	See above	See above		Each PA
544		EIR 589	SC 4.6-2	Prior to the recordation of a Subdivision Map	Vehicular Access Rights:		Vehicular Access Rights:	final map which release and relinquish vehicular access rights to all arterial highways to the County of Orange, except for access locations approved by the	Planning & Development- Services, Director, OC	Verification of notes on the final map which release and relinquish vehicular access rights to all arterial highways to the County of Orange except for access locations approved by the County of Orange of Corange except for access locations approved by the County of Orange except for access locations approved by the County of Orange except for access locations approved by the County of Orange except for access locations approved by the County of Orange except for access locations are supported by the county of Orange except for access locations are supported by the County of Orange except for access locations are supported by the county of Orange except for access location for access for access location for access fo	Note shall state: "Rancho Mission Viejo or assigns hereby release and relinquish vehicular access rights to all arterial highways to the County of Orange, except for access locations approved by the County of Orange"	Each PA
545		EIR 589	SC 4.6-3	Prior to the recordation of a Subdivision Map	Private_Street Improvements:		Private Street Improvements:	Prior to the recordation of a subdivision map, the subdivider shall place a note on the map, in a manner that meets the approval of the Manager, Subdivision and Grading Services, that states: "The private streets constructed within this map shall be owned, operated and maintained by the developer, successors or assigns. The County of Orange shall have no responsibility therefore unless pursuant to appropriate sections of the Streets and Highways Code of the State of California, the said private streets have been accepted into the County Road System by appropriate resolution of the Orange County Board of Supervisors. (County Standard Condition TD2)	Gounty of Orange Director of- Planning & Development Services, Director, OC Planning	Verification of a note on the Subdivision Map	Note shall make statement listed in quotations in condition.	Each PA
546		EIR 589	SC 4.6-4	Prior to the recordation of a Subdivision Map	Street Improvements (cont.):		Street Improvements (cont.):	Prior to the recordation of a subdivision map, the subdivider shall design and construct (or provide evidence of financial security, such as bonding) the following improvements in accordance with plans and specifications meeting the approval of the	County of Orange Director of Planning & Development Services, Director, OC Planning	Submittal of satisfactory improvements and utility plans with verification of subsequent construction/in stallation of improvements	If applicable, bonding may substitute for construction of each of the required improvements.	Each PA
546.1		EIR 589	SC 4.6-4 (cont.)	See above	Street Improvements (cont.):		Street Improvements (cont.):	A. Streets, bus stops, on-road bicycle trails, street names, signs, striping and stenciling. (County Standard Condition T04)	See above	See above	See above	Each PA
546.2		EIR 589	SC 4.6-4 (cont.)	See above	Street Improvements (cont.):		Street Improvements (cont.):	B. The water distribution system and appurtenances shall also conform to the applicable laws and adopted regulations enforced by the County Fire Chief. (County Standard Condition T04)	See above	See above	See above	Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
546.3		EIR 589	SC 4.6-4 (cont.)	See above	Street Improvements (cont.):		Street Improvements (cont.):	C. Underground utilities (including gas, cable, electrical and telephone), streetlights, and mailboxes. (County Standard Condition T04)	See above	See above	See above	Each PA
549		EIR 589	SC 4.6-7	Prior to the recordation of a Subdivision Map	Traffic Signal Conduit:		Traffic Signal Conduit:	Prior to the recordation of a subdivision map, the subdivider shall install (or provide evidence of financial security, such as bonding, that) all underground traffic signal conduits (e.g., signals, phones, power, loop detectors, etc.) and other appurtenances (e.g., pull boxes, etc.) needed for future traffic signal construction, and for future interconnection with adjacent intersections, all in accordance with plans and specifications meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T08)	County of Orange Director of Planning & Development Services, Director, OC Planning	Approved traffic signal plans with verification of subsequent installation	If applicable, bonding may substitute for construction of each of the required improvements.	Each PA
550		EIR 589	SC 4.6-8	Prior to the recordation of a Subdivision Map or prior to the issuance of Building Permits, whichever occurs first	Internal Circulation:		Internal Circulation:	A. Prior to the recordation of a subdivision map or the issuance of any building permits, whichever occurs first, the subdivider shall provide plans and specifications meeting the approval of the Manager, Subdivision and Grading, for the design of the following improvements: (County Standard Condition T12)	County of Orange Director of Planning & Development Services,	Submittal of satisfactory street improvement plans		Each PA
550.1		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation (cont.):		Internal Circulation (cont.):	Internal street common private drive system. (County Standard Condition T12)	See above	See above		Each PA
550.2		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation (cont.):		Internal Circulation (cont.):	2) Entrance to the site to emphasize that the development is private by use of signs and other features. (Standard Condition of Approval T12)	See above	See above		Each PA
550.3		EIR 589	SC 4.6-8 (cont.)	Prior to the recordation of Subdivision Map.	Internal Circulation (cont.):		Internal Circulation (cont.):	B. Prior to the recordation of a subdivision map, the applicant shall construct (or provide evidence of financial security, such as bonding) the above improvements in a manner meeting the approval of the Manager, Construction. (County Standard Condition T12)	County of Orange Manager of- Inspection, Manager, OC Inspection Division	Verification of improvements' construction in SC 4.6-8A	If applicable, bonding may substitute for construction of each of the required improvements.	Each PA
551		EIR 589	SC 4.6-9	Prior to the recordation of a Subdivision Map	Traffic Signal Maintenance Easement:		Traffic Signal Maintenance Easement:	Prior to the recordation of a subdivision map, the subdivider shall dedicate a signal maintenance easement to the County of Orange at the project site access, in a manner meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T13b)	County of Orange Director of- Planning &- Development- Services, Director, OC Planning	Submittal of offer(s) of dedication for signal maintenance easement(s)		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
552		EIR 589	SC 4.6-10	Prior to the recordation of a Subdivision Map	Traffic Signal Installation:		Traffic Signal Installation:	Prior to the recordation of a subdivision map, the subdivider shall design and construct/provide a cash deposit of% of the cost of / /enter into an agreement with the County of Orange, accompanied by financial security, for the cost of% of) a traffic signal at the intersection of and, in a manner meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T14b)	County of Orange- Director-of- Planning &- Development- Services, Director, OC Planning	Verification of approved street improvement plans with subsequent installation of improvements or enter into agreement with County for construction (with appropriate financial security)	If applicable, bonding may substitute for construction of each of the required improvements.	Each PA
559		EIR 589	SC 4.8-3	See below	Sound Attenuation:		Sound Attenuation:	The applicant shall sound attenuate all residential lots and dwellings against present and projected noise (which shall be the sum of all noise impacting the project) so that the composite interior standard of 45 dBA CNEL for habitable rooms and a source specific exterior standard of 65 dBA CNEL for outdoor living areas is not exceeded. The applicant shall provide a report prepared by a County-certified acoustical consultant, which demonstrates that these standards will be satisfied in a manner consistent with Zoning Code Section 7-9-137.5, as follows: (County Standard Condition, NO1)	County of Orange- Director of- Planning &- Development- Services and- County of Orange- Manager of- Building Permits- Services, Director, OC Planning and Manager, Permit Services (Building Plan	Submittal of satisfactory acoustical analysis	Staff may determine that no attenuation is necessary, and no action is required (as occurred in PA1). In such a case a "not applicable" memo is to be prepared. Applicant and County staff to address AC units in side yards as soon as possible.	Each PA
559.1		EIR 589	SC 4.8-3 (cont.)	Prior to the recordation of a subdivision map or prior to the issuance of grading permits	Sound Attenuation (cont.):		Sound Attenuation (cont.):	Standard Condition N011 a. Prior to the recordation of a subdivision map or prior to the issuance of grading permits, as determined by the Manager, Building Permits Services, the applicant shall submit an acoustical analysis report to the Manager, Building Permits Services, for approval. The report shall describe in detail the exterior noise environment and preliminary mitigation measures. Acoustical design features to achieve interior noise standards may be included in the report in which case it may also satisfy Condition B below. (County Standard Condition N01)	Check) See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
589.1		EIR 589	SC 4.15-1	Prior to recordation of final tract a-subdivision-maps (alternatively subdivider may enter into a subdivision improvement agreement with the County	Water Improvement Plans:			Prior to the recordation of a subdivision map, the subdivider shall design and construct (or provide evidence of financial security, such as bonding) water distribution system and appurtenances that conform to the applicable laws and adopted regulations enforced by the County Fire Chief, in accordance with plans and specifications meeting the approval of the Manager, Subdivision and Grading. (Added per MMRP attached to 11/8/06 CEQA Resolution 04-290)	County of Orange- Director of- Planning &- Development Services- Director, OC Planning (OCFA)	water improvement plans with subsequent construction of	Applicant must submit one of the following: (1) approved improvement plan consisted with referenced Plan of Works, (2) letters from both SMWD and OCFA indicating sufficient water supply and pressure for Map area, or (3) subdivision improvement agreement with County	Each PA
597		EIR 589	SC 4.15-9		CUSD Fees:			Prior to the recordation of final tract map, the project applicant shall provide for the payment of fees pursuant to California Government Code Section 65995, unless other provision are required of the applicant through the agreement with CUSD (see Mitigation Measure 4.15-5).	N/A	Compliance with CUSD agreement	Payment of school fees per CUSD/RMV Agreement	PC- Wide
619		Fire Prot. Prog.	Cond. 4	Prior to recordation of each Tract Map	Administrative Approval of Tract Maps		Tract Maps	Prior to recordation of each Tract Map, the applicant shall submit a copy of the proposed Tract map to OCFA for administrative approval (verifying that the map remains consistent with previous approvals), and for OCFA's record keeping purposes.	Planning	Submit a copy of the proposed Tract map to OCFA for administrative approval		
COA #7		PA2.3 Builer "B" Map COAs	Cond. #7	Prior to recordation of the final tract map			MANEUVERAB ILITY EASEMENT	Prior to recordation of the final tract map, the subdivider shall demonstrate that all necessary ingress/egress easements for vehicle maneuverability within motor courts/alleyways are identified on the final map subject to the satisfaction of the Planning Manager. The easement shall prohibit property owners from installing any improvements within the easement area or interfering with the use or maintenance of the easement.	Planning	Submit a copy of the proposed Tract map to OCFA for administrative approval		

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
b.	Prior to	Appro	oval of S	ite Developi	ment Permit							
109				Prior to approval of Master Area- Plan or Subarea- Plan Site Development Permit	,	Shade trees, evaporative emissions	Design	With the submittal of each Master Area Plan, the project applicant shall identify how shade trees can be incorporated into parking lot designs (to reduce evaporative emissions from parked vehicles); where shade trees can be sited (to reduce summer cooling needs); and how shade trees would be incorporated into bicycle and pedestrian path design. [Note: for the purposes of clarification, the timing of this requirement should be interpreted to read as follows: Prior to approval of each applicable Site Development permit, the project applicant shall. 1	Planning	Submittal of satisfactory landscape plans (precise, not general landscape plan at SDP level		Each PA
110	111 (MM 4.7-3)	EIR 589	MM 4.7-3 (cont.)	Prior to approval of Master Area- Plan or Subarea- Plan Site Development Permit	Air Quality	Light-colored roof materials	Use Light- Colored Roof Materials to Reflect Heat (Item Nos. 110- 111)	As a part of each Master Area Plan, the applicant shall identify how the use of light-colored roof materials and paint to reflect heat to the extent feasible has been incorporated into the design plans. [Note: for the purposes of clarification, the timing of this requirement should be interpreted to read as follows: Prior to approval of each applicable Site Development permit, the project applicant shall]	Director, PDS Director, OC Planning	Issuance of Building Permit (Evidence of reflection of materials)		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
C.	Prior to	Issua	nce of G	rading Pern	nits							
521			SC 4.4-1		Geology and Soils:		Geology and Soils:	Prior to the issuance of a grading permit, the applicant shall submit a geotechnical report to the Manager of Subdivision-Manager OC Planned Communities and Grading, for approval. The report shall meet the requirements outlined in the County of Orange Grading Code and Manual. (County Standard Condition G01)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Submittal of satisfactory geotechnical report		Each PA
522		EIR 589	SC 4.4-2	Prior to the issuance of a grading permit	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to the issuance of any grading permits, the Manager of Subdivision and Grading shall review the grading plan for conformance with the grading shown on the approved tentative map. If the applicant submits a grading plan which the Manager-of-Subdivision and Grading Manager OC Planned Communities determines to show a significant deviation from the grading shown on the approved tentative map, specifically with regard to slope heights, slope ratios, pad elevations or configurations, the Subdivision Committee shall review the plan for a finding of substantial conformance. (County Standard Condition G02)	Services, Director, OC Planning	Approval of grading plan demonstrating submittal conformance with the grading shown on the approved TTM		Each PA
523		EIR 589	(cont.)	Prior to the issuance of a grading permit	Geology and Soils (cont.):		Geology and Soils (cont.):	If the Subdivision Committee fails to make such a finding, the applicant shall process a revised tentative map; or, if a final map has been recorded, the applicant shall process a new tentative map or a site development permit application per Orange County Zoning Code Sections 7-9-139 and 7-9-150. Additionally, the applicant shall process a new environmental assessment for determination by the decision making entity. (County Standard Condition G02)	Subdivision Committee review for substantial conformance, if required	Process new subdivision, if necessary		Each PA
524		EIR 589	SC 4.4-3	Prior to the recordation of a subdivision map or prior to issuance of a Grading Permit, whichever comes first	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to the recordation of a subdivision map or prior to the issuance of any grading permit, whichever comes first, and if determined necessary by the County of Orange Manager, Subdivision and Grading, the applicant shall record a letter of consent from the affected property owners permitting off-site grading, cross lot drainage, drainage diversions and/or unnatural concentrations. The applicant shall obtain approval of the form of the letter of consent from the Manager, Subdivision and Grading Services before recordation of the letter. (County Standard Condition G04)	Director-of- Planning & Development- Services- Director, OC Planning	Recordation of a letter of consent from affected property owners if determined necessary by County of Orange Director of Planning & Development Services		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
525		EIR 589		Prior to the issuance of grading permits	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to issuance of grading permits, the Manager of Subdivision and Grading- Manager OC Planned Communities shall determine that the proposed grading is consistent with the grading depicted within the approved planning application. (County Standard Condition G09)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Approval of grading plan		Each PA
527		EIR 589	SC 4.5-1	Prior to recordation of a Subdivision Map or issuance of a Grading Permit, whichever comes first	Drainage Study:		Drainage Study:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the following drainage studies shall be submitted to and approved by the Manager, Subdivision and Grading: (County Standard Condition D01a)	Director of Planning &- Development Services,	Submittal of satisfactory of drainage study		Each PA
527.1		EIR 589	SC 4.5-1 (cont.)	See above	Drainage Study (cont.):		Drainage Study (cont.):	A. A drainage study of the project including diversions, off-site areas that drain onto and/or through the project, and justification of any diversions; and B. When applicable, a drainage study evidencing that proposed drainage patterns will not overload existing storm drains; and C. Detailed drainage studies indicating how the project grading, in conjunction with the drainage conveyance systems including applicable swales, channels, street flows, catch basins, storm drains, and flood water retarding, will allow building pads to be safe from inundation from rainfall runoff which may be expected from all storms up to and including the theoretical 100-year flood. (County Standard Condition D01a)	See above	See above		Each PA
528		EIR 589	SC 4.5-2	Prior to recordation of a Subdivision Map or Issuance of a Grading Permit, whichever comes first	Drainage Improvements:		Drainage Improvements:	A. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the applicant shall in a manner meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition D02a)	Director of Planning & Development Services, Director, OC	Approval of storm drain drainage plans and offer(s) of dedication, if necessary		Each PA
528.1		EIR 589	SC 4.5-2 (cont.)	See above	Drainage Improvements (cont.):		Drainage Improvements (cont.):	Design provisions for surface drainage;     Design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and     Dedicate the associated easements to the County of Orange, if determined necessary.  (County Standard Condition D02a)	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
530		EIR 589	SC 4.5-3	Prior to the issuance of Grading Permits	Drainage Improvements (cont.):		Drainage Improvements (cont.):	A. Prior to the issuance of any grading permits, the applicant shall in a manner meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition D02b)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Submittal of satisfactory drainage plans		Each PA
530.1		EIR 589	SC 4.5-3 (cont.)	See above	Drainage Improvements (cont.):		Drainage Improvements (cont.):	Design provisions for surface drainage; and     Design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and     Dedicate the associated easements to the County of Orange, if determined necessary.  (County Standard Condition D02b)	See above	See above		Each PA
537		EIR 589		Prior to the recordation of a Subdivision Map or the issuance of any Grading or Building Permit, whichever comes first	Water Quality Management Plan:		Water Quality Management Plan:	Prior to the recordation of any final subdivision map (except those maps for financing or conveyance purposes only) or the issuance of any grading or building permit (whichever comes first), the applicant shall submit for review and approval by the Manager, Inspection Services Division, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. This WQMP shall identify, at a minimum, the routine structural and non-structural measures specified in the current Drainage Area Management Plan (DAMP). The WQMP may include one or more of the following: (County Standard Condition MVCO11)	Development-	Submittal of satisfactory Water Quality Management Plan		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
537.1		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Discuss regional water quality and/or watershed programs (if available for the project);     Address Site Design BMPs (as applicable) such as minimizing impervious areas, maximizing permeability, minimizing directly connected impervious areas, creating reduced or "zero discharge" areas, and conserving natural areas;     Include the applicable Routine Source Control BMPs as defined in the DAMP. (County Standard Condition WQ01)	See above	See above		Each PA
538		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate how surface runoff and subsurface drainage shall be managed and directed to the nearest acceptable drainage facility (as applicable), via sump pumps if necessary. (Standard Condition of Approval. WQ03)	See above	See above		Each PA
540		EIR 589		Prior to the issuance of any Grading or Building Permits	Stormwater Pollution Prevention Plan.		Stormwater Pollution Prevention Plan.	Prior to the issuance of any grading or building permits, the applicant shall demonstrate compliance under California's General Permit for Stormwater Discharges Associated with Construction Activity by providing a copy of the Notice of Intent (NOI) submitted to the State Water	Building- Inspection— Manager, OC Inspection Division (Regional Water Quality Control Board)	Provision of Notice of Intent and verification of a copy of the Storm Water Pollution Prevention Plan (SWPPP); at the project site		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
541		EIR 589	SC 4.5-11	Prior to the issuance of any Grading or Building Permits	Erosion and Sediment Control Plan.		Erosion and Sediment Control Plan.	Prior to the issuance of any grading or building permit, the applicant shall submit a Erosion and Sediment Control Plan (ESCP) in a manner meeting approval of the Manager, Building Permit Services, to demonstrate compliance with local and state water quality regulations for grading and construction activities. The ESCP shall identify how all construction materials, wastes, grading or demolition debris, and stockpiles of soil, aggregates, soil amendments, etc. shall be properly covered, stored, and secured to prevent transport into local drainages or coastal waters by wind, rain, tracking, tidal erosion or dispersion. The ESCP shall also describe how the applicant will ensure that all BMPs will be maintained during construction of any future public right-of-ways. A copy of the current ESCP shall be kept at the project site and be available for County review on request. (County	Manager of Building Permits, Manager, Permit Services (Building Plan Check)	Submittal of satisfactory Erosion and Sediment Control Plan (ESCP); verification of copy of ESCP at project site		Each PA
548		EIR 589	SC 4.6-6	Prior to the issuance of Grading Permits	Sight Distance:		Sight Distance:	Prior to the issuance of any grading permits, the applicant shall provide adequate sight distance per Standard Plan 1117 at all street intersections, in a manner meeting the approval of the Manager, Subdivision and Grading. The applicant shall make all necessary revisions to the plan to meet the sight distance requirement such as removing slopes or other encroachments from the limited use area in a manner meeting the approval of the Manager, Subdivision and Grading Services. (Standard Condition of Approval T07)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Approved grading plans verifying adequate sight distance		Each PA
555		EIR 589	SC 4.7-1	Prior to the issuance of a grading permit	Fugitive Dust:		Fugitive Dust:	All construction contractors shall comply with South Coast Air Quality Management District (SCAQMD) regulations, including Rule 403, Fugitive Dust, and Rule 402, Nuisance. All grading (regardless of acreage) shall apply best available control measures for fugitive dust in accordance with Rule 403. To ensure that the project is in full compliance with applicable SCAQMD dust regulations and that there is no nuisance impact off the site, the contractor would implement each of the following:	County of Orange Director of Planning & Development Services, Director, OC Planning	Verification of compliance with Rule 403 and Rule 402		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
555.1		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	Moisten soil not more than 15 minutes prior to moving soil or conduct whatever watering is necessary to prevent visible dust emissions from traveling more than 100 feet in any direction.	See above	See above		Each PA
555.2		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	b. Apply chemical stabilizers to disturbed surface areas (i.e., completed grading areas) within five days of completing grading or apply dust suppressants or vegetation sufficient to maintain a stabilized surface.	See above	See above		Each PA
555.3		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	c. Water excavated soil piles hourly or cover with temporary coverings.	See above	See above		Each PA
555.4		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	d. Water exposed surfaces at least twice a day under calm conditions. Water as often as needed on windy days when winds are less than 25 miles per day or during very dry weather in order to maintain a surface crust and prevent the release of visible emissions from the construction site.	See above	See above		Each PA
555.5		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	e. Wash mud-covered tires and under- carriages of trucks leaving construction sites.	See above	See above		Each PA
555.5		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	f. Provide for street sweeping, as needed, on adjacent roadways to remove dirt dropped by construction vehicles or mud, which would otherwise be carried off by trucks departing from project sites.	See above	See above		Each PA
556		EIR 589	SC 4.7-2	Prior to issuance of a grading permit	Construction - ROC and NOX Emissions:		Construction - ROC and NOX Emissions:	The applicant shall comply with the following measures, as feasible, to reduce NO <sub>X</sub> and ROC from heavy equipment.	County of Orange Director of- Planning & Development- Services, Director, OC Planning	Place as general notes on approved grading plan		Each PA
556.1		EIR 589	(cont.)	See above	Construction Emissions:		Construction Emissions:	Turn equipment off when not in use for more than five minutes.	See above	See above		Each PA
556.2		EIR 589	SC 4.7-2 (cont.)	See above	Construction Emissions (cont.):		Construction Emissions (cont.):	b. Maintain equipment engines in good condition and in proper tune as per manufacturers' specifications.	See above	See above		Each PA
556.3		EIR 589	SC 4.7-2 (cont.)	See above	Construction Emissions (cont.):		Construction Emissions (cont.):	c. Lengthen the construction period during smog season (May through October) to minimize the number of vehicles and equipment operating at the same time.	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
557		EIR 589	SC 4.8-1	Prior to the issuance of grading permits	Hours of Construction:		Hours of Construction:	During construction, the project applicant shall ensure that all noise generating activities be limited to the hours of 7 a.m. to 8 p.m. on weekdays and Saturdays. No noise generating activities shall occur on Sundays and holidays in accordance with the County of Orange Noise Ordinance.	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	General note on approved grading plan		Each PA
558		EIR 589	SC 4.8-2	Prior to the issuance of grading permits	Construction Noise:		Construction Noise:	A. Prior to the issuance of any grading permits, the project proponent shall produce evidence acceptable to the Manager, Building Permits Services, that: (County Standard Condition N10)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	General note on approved grading plan		Each PA
558.1		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	(1) All construction vehicles or equipment, fixed or mobile, operated within 1,000' of a dwelling shall be equipped with properly operating and maintained mufflers. (County Standard Condition N10)	See above	See above		Each PA
558.2		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	(2) All operations shall comply with Orange County Codified Ordinance Division 6 (Noise Control). (County Standard Condition N10)	See above	See above		Each PA
558.3		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	(3) Stockpiling and/or vehicle staging areas shall be located as far as practicable from dwellings. (County Standard Condition N10)	See above	See above		Each PA
558.4		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	B. Notations in the above format, appropriately numbered and included with other notations on the front sheet of the project's permitted grading plans, will be considered as adequate evidence of compliance with this condition. (County Standard Condition N10)	See above	See above		Each PA
559		EIR 589	SC 4.8-3	See below	Sound Attenuation:		Sound Attenuation:	The applicant shall sound attenuate all residential lots and dwellings against present and projected noise (which shall be the sum of all noise impacting the project) so that the composite interior standard of 45 dBA CNEL for habitable rooms and a source specific exterior standard of 65 dBA CNEL for outdoor living areas is not exceeded. The applicant shall provide a report prepared by a County-certified acoustical consultant, which demonstrates that these standards will be satisfied in a manner consistent with Zoning Code Section 7-9-137.5, as follows: (County Standard Condition. NO1)	County of Orange- Director of- Planning &- Development- Services and- County of Orange- Manager of- Building Permits- Services, Director, OC Planning and Manager, Permit Services (Building Plan Chack)	Submittal of satisfactory acoustical analysis	Staff may determine that no attenuation is necessary, and no action is required (as occurred in PA1). In such a case a "not applicable" memo is to be prepared. Applicant and County staff to address AC units in side yards as soon as possible.	Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
559.1		EIR 589	SC 4.8-3 (cont.)	Prior to the recordation of a subdivision map or prior to the issuance of grading permits	Sound Attenuation (cont.):		Sound Attenuation (cont.):	a. Prior to the recordation of a subdivision map or prior to the issuance of grading permits, as determined by the Manager, Building Permits Services, the applicant shall submit an acoustical analysis report to the Manager, Building Permits Services, for approval. The report shall describe in detail the exterior noise environment and preliminary mitigation measures. Acoustical design features to achieve interior noise standards may be included in the report in which case it may also satisfy Condition B below. (County Standard Condition N01)	See above	See above		Each PA
567			SC 4.10-2	Prior to the issuance of precise grading permits	Private Area Landscaping:		Private Area Landscaping:	a. Prior to the issuance of precise grading permits, the applicant shall prepare a detailed landscape plan for privately maintained common areas which shall be reviewed and approved by the Manager, Subdivision and Grading. The plan shall be certified by a licensed landscape architect or a licensed landscape contractor, as required, as taking into account the approved preliminary landscape plan (if any), County Standard Plans for landscape areas, adopted plant palette guides, applicable scenic and specific plan requirements, Water Conservation Measures contained in Board Resolution 90-487 (Water Conservation Measures), and Board Resolution 90-1341 (Water Conservation Implementation Plan). (County Standard Condition I AQ2h)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Approved detailed landscape plan for privately maintained common areas		Each PA
571	172-176 (MM 4.11-3)	EIR 589	SC 4.11-1	Prior to the issuance of any grading permits	Archaeology Grading Observation and Salvage:		Archaeology Grading Observation and Salvage:	Prior to the issuance of any grading permit, the applicant shall provide written evidence to the County of Orange Manager, Subdivision and Grading, that applicant has retained a County-certified archaeologist to observe grading activities and salvage and catalogue archaeological resources as necessary. The archaeologist shall be present at the pre-grade conference; shall establish procedures for archaeological resource surveillance; and shall establish, in cooperation with the applicant, procedures for temporarily halting or redirecting work to permit the sampling, identification, and evaluation of the artifacts as appropriate. If the archaeological resources are found to be significant, the archaeological observer shall determine appropriate actions, in cooperation with the project applicant, for exploration and/or salvage. (County Standard Condition A04)	Gounty of Orange Manager, Harbors, Beaches & Parks. HBP/Coastal and-Historical Facilities OC Public Works/OC Planning*	evidence that	If prior to rough grade (GA permit) applicant has obtained archaeological clearance, no additional review or clearance required if precise grading (GB) permit is in compliance with GA permit.	Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
574		EIR 589	SC 4.11-2	Prior to the issuance of any grading permits	Paleontology Resource Surveillance:		Paleontology Resource Surveillance:	Prior to the issuance of any grading permit, the project contractor shall provide written evidence to the Manager, Subdivision and Grading, that contractor has retained a County certified paleontologist to observe grading activities and salvage and catalogue fossils as necessary. The paleontologist shall be present at the pregrade conference, shall establish procedures for paleontological resources surveillance, and shall establish, in cooperation with the contractor, procedures for temporarily halting or redirecting work to permit sampling, identification, and evaluation of the fossils. If the paleontological resources are found to be significant, the paleontologist shall determine appropriate actions, in cooperation with the contractor, which ensure proper exploration and/or salvage.	OC Public Works/OC Planning*	evidence that		Each PA
589		EIR 589	SC 4.14-2	Prior to issuance of a grading and/or building permit	Hazardous Materials:		Hazardous Materials:	Prior to the issuance of a grading or building permit, the contractor shall submit to the	Director of Planning & Development Services	Submittal of Hazardous Materials Assessment and Disclosure Statement		Each PA
616		Fire Prot. Prog.		Prior to the issuance of a GB precise grading permit	Precise Fuel Mod:		Precise Fuel Mod:	d) Prior to the issuance of a GB precise grading permit, the applicant shall provide the Manager, PDS Subdivision and Infrastructure Manager OC Planned Communities, with a clearance from OCFA indicating their review and approval of a Precise Fuel Modification Plan per RPFPP Section C.3.	Planning	Provide the Manager, PDS-Subdivision-and-Infrastructure-Manager OC Planned Communities with a clearance from OCFA demonstrating approval of a Conceptual Fuel Modification Plan		

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
COA# 2		PA2.3 Builer "B" Map COAs		Prior to the issuance of any grading or building permits	WQMP			Prior to the issuance of any grading or building permits, the applicant shall submit for review and approval by the Manager, Permit Services, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. The applicant shall utilize the Orange County Drainage Area Management Plan (DAMP), Model WQMP, and Technical Guidance Manual for reference, and the County's WQMP template for submittal.	County of Orange- Manager, Building- Inspection- Services, Manager, OC Inspection Division			Each PA
COA# 2 (cont.)		PA2.2 Builer "B" Map COAs		See above	WQMP			This WQMP shall include the following:     Detailed site and project description     Potential stormwater pollutants     Post-development drainage characteristics     Low Impact Development (LID) BMP     selection and analysis     - Structural and Non-Structural source     control BMPs     - Site design and drainage plan (BMP     Exhibit)     - GIS coordinates for all LID and Treatment     Control BMPs     - Operation and Maintenance (O&M) Plan     that (1) describes the long-term operation     and maintenance requirements for BMPs     identified in the BMP Exhibit; (2) identifies     the entity that will be responsible for long- term operation and maintenance of the     referenced BMPs; and (3) describes the     mechanism for funding the long-term     operation and maintenance of the     referenced BMPs  The BMP Exhibit from the approved WQMP     shall be depicted on these plans. Grading and     building plans must be consistent with the     approved BMP exhibit.	County of Orange- Manager, Building- Inspection- Services, Manager, OC Inspection Division			Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
d.	Prior to	Preci	se Fuel I	Modification	Plans							
138	137 and 139 (EIR 589, MM 4.9-27) 514 (ROSA Exhibit G)	EIR 589	MM 4.9-27 (cont.)	Prior to the approval of Precise Fuel Modification Plans	Biological Resources	California Exotic Pest Plant Council, OCFA Fuel Modification Plant List	Invasive Plants and Fuel Modification	a. Prior to issuance of fuel modification plan approvals, the County of Orange shall verify that: 1) plants identified by the California Exotic Pest Plant Council as an invasive risk in Southern California are not included in plans for fuel management zones adjacent to the RMV Open Space and, 2) the plant palette for fuel management zones adjacent to RMV Open Space is limited to those species listed on the Orange County Fire Authority Fuel Modification Plant List.	Director, PDS- Director, OC Planning (OCFA)	Verification of authorized plant materials	Signature of Landscape Architect on approved Precise Fuel Modification Plan certifying plant palette: (a) complies with current OCFA plant list, and (b) does not include plants listed on the current invasive species list.	Each PA
e.	Prior to	Issua	nce of B	uilding Pern	nit						ISDECIES IIST.	
111	110 (MM 4.7-3)			Prior to issuance of building permits		Light-colored roof materials	Use Light- Colored Roof Materials to Reflect Heat (Item Nos. 110- 111)	Prior to issuance of building permits, the applicant shall identify how the use of light-colored roof materials and paint to reflect heat to the extent feasible has been incorporated into the design plans.	Director, PDS Director, OC Planning	Issuance of Building Permit (Evidence of reflection of heat through home design)	Sustainability Issue	Each PA
140	141 (MM 4.9-28) 515 (ROSA Exhibit G)	EIR 589	MM 4.9-28	Prior to the issuance of Building permits on streets for tracts with public street lighting adjacent to RMV Open Space habitat areas	Biological Resources	Open Space habitat, light shields	Streetlight Shielding Adjacent to Open Space	Lighting shall be shielded or directed away from RMV Open Space habitat areas through the use of low-sodium or similar intensity lights, light shields, native shrubs, berms or other shielding methods.	Director, PDS Director, OC Planning	Preparation of a lighting plan	Preparation of street improvement plans for public streets that detail how street lighting is to be directed away from RMV Open Space areas	Each Applica ble PA
206				Prior to issuance of residential building permits (excluding age- qualified units)	and Facilities	California Government Code Section 65995	CUSD Agreement	Prior to issuance of any residential building permit, excluding senior housing, the applicant shall enter into an agreement with CUSD regarding the development of future facilities and payment of costs. The agreement shall, at a minimum, provide for the payment of fees pursuant to California Government Code Section 65995. If fees are paid, the amount of fees to be paid will be determined based on the established State formula for determining construction costs. Applicable fees shall be paid prior to the issuance of each building permit.	, ,	Negotiate and execute Mitigation Agreement regarding future school facilities and payment of costs		PC- Wide
526		EIR 589		Prior to the issuance of building permits	Geology and Soils (cont.):		Geology and Soils (cont.):	The proposed development shall be designed in compliance with the Uniform Building Code (UBC), accepted industry standards, and the County's earthquake safety Municipal Code requirements.	County of Orange- Director of- Planning & Development- Services, Director, OC Planning	Verification of design development compliance with the UBC and Municipal Code requirements		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
537		EIR 589		Prior to the recordation of a Subdivision Map or the issuance of any Grading or Building Permit, whichever comes first	Water Quality Management Plan:		Water Quality Management Plan:	Prior to the recordation of any final subdivision map (except those maps for financing or conveyance purposes only) or the issuance of any grading or building permit (whichever comes first), the applicant shall submit for review and approval by the Manager, Inspection Services Division, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. This WQMP shall identify, at a minimum, the routine structural and non-structural measures specified in the current Drainage Area Management Plan (DAMP). The WQMP may include one or more of the following: (County Standard Condition WQ011)	County of Orange- Director of- Planning &- Development- Services, Director, OC Planning	Submittal of satisfactory Water Quality Management Plan		Each PA
537.1		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Discuss regional water quality and/or watershed programs (if available for the project);  Address Site Design BMPs (as applicable) such as minimizing impervious areas, maximizing permeability, minimizing directly connected impervious areas, creating reduced or "zero discharge" areas, and conserving natural areas; Include the applicable Routine Source Control BMPs as defined in the DAMP. (County Standard Condition WQ01)	See above	See above		Each PA
538		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate how surface runoff and subsurface drainage shall be managed and directed to the nearest acceptable drainage facility (as applicable), via sump pumps if necessary. (Standard Condition of Approval, WQ03)	See above	See above		Each PA
540		EIR 589	SC 4.5-10	Prior to the issuance of any Grading or Building Permits	Stormwater Pollution Prevention Plan.		Stormwater Pollution Prevention Plan.	Prior to the issuance of any grading or building permits, the applicant shall demonstrate compliance under California's General Permit for Stormwater Discharges Associated with Construction Activity by providing a copy of the Notice of Intent (NOI) submitted to the State Water Resources Control Board and a copy of the subsequent notification of the issuance of a Waste Discharge Identification (WDID) Number or other proof of filing in a manner meeting the satisfaction of the Manager, Building Permit Services. Projects subject to this requirement shall prepare and implement a Stormwater Pollution Prevention Plan (SWPPP). A copy of the current SWPPP shall be kept at the project site and be available for County review on request. (County Standard Condition	Gounty of Orange Manager of Building Inspection— Manager, OC Inspection Division (Regional Water Quality Control Board)	Provision of Notice of Intent and verification of a copy of the Storm Water Pollution Prevention Plan (SWPPP); at the project site		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
541		EIR 589	SC 4.5-11	Prior to the issuance of any Grading or Building Permits	Erosion and Sediment Control Plan.		Erosion and Sediment Control Plan.	Prior to the issuance of any grading or building permit, the applicant shall submit a Erosion and Sediment Control Plan (ESCP) in a manner meeting approval of the Manager, Building Permit Services, to demonstrate compliance with local and state water quality regulations for grading and construction activities. The ESCP shall identify how all construction materials, wastes, grading or demolition debris, and stockpiles of soil, aggregates, soil amendments, etc. shall be properly covered, stored, and secured to prevent transport into local drainages or coastal waters by wind, rain, tracking, tidal erosion or dispersion. The ESCP shall also describe how the applicant will ensure that all BMPs will be maintained during construction of any future public right-ofways. A copy of the current ESCP shall be kept at the project site and be available for County review on request. (County	County of Orange Manager of Building Permits, Manager, Permit Services (Building Plan Check)	Submittal of satisfactory Erosion and Sediment Control Plan (ESCP); verification of copy of ESCP at project site		Each PA
547		EIR 589	SC 4.6-5	Prior to the issuance of Building Permits	Major Thoroughfare and Bridge Fee Programs:		Major Thoroughfare and Bridge Fee Programs:	Prior to the issuance of building permits, the applicant shall pay fees for the Major Thoroughfare and Bridge Fee Program for	Director of Planning &	Verification of payment of fees for the Major Thoroughfare and Bridge Fee Program		Each PA
550		EIR 589	SC 4.6-8	Prior to the recordation of a Subdivision Map or prior to the issuance of Building Permits, whichever occurs first	Internal Circulation:		Internal Circulation:	A. Prior to the recordation of a subdivision	County of Orange	Submittal of satisfactory street improvement plans		Each PA
550.1		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation		Internal Circulation	Internal street common private drive system. (County Standard Condition T12)	See above	See above		Each PA
550.2		EIR 589	SC 4.6-8 (cont.)	See above	(cont.): Internal Circulation (cont.):		(cont.): Internal Circulation (cont.):	Entrance to the site to emphasize that the development is private by use of signs and other features. (Standard Condition of Approval T12)	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
550.4		EIR 589	SC 4.6-8 (cont.)	Prior to the issuance of Building Permits	Internal Circulation (cont.):		Internal Circulation (cont.):	C. Prior to the issuance of any building permits, the subdivider shall provide plans meeting the approval of the Manager, Subdivision & Grading, for the design of the internal pedestrian circulation system within the development. (County Standard Condition T12)	Services, Director, OC Planning	Submittal of satisfactory internal pedestrians circulation plans		Each PA
559.2		EIR 589	SC 4.8-3 (cont.)	Prior to the issuance of any building permits for residential construction	Sound Attenuation (cont.):		Sound Attenuation (cont.):	b. Prior to the issuance of any building permits for residential construction, the applicant shall submit an acoustical analysis report describing the acoustical design features of the structures required to satisfy the exterior and interior noise standards to the Manager, Building Permits Services, for approval along with satisfactory evidence which indicates that the sound attenuation measures specified in the approved acoustical report have been incorporated into the design of the project. (County Standard Condition N01)	Development- Services and- County of Orange- Manager of- Building Permits- Services, Director, OC Planning and Manager, Permit Services (Building Plan Check)	Submittal of satisfactory acoustical analysis		Each PA
559.3		EIR 589	SC 4.8-3 (cont.)	See above	Sound Attenuation (cont.):		Sound Attenuation (cont.):	c. Prior to the issuance of any building permits, the applicant shall show all freestanding acoustical barriers on the project's plot plan illustrating height, location and construction in a manner meeting the approval of the Manager, Building Permits Services. (County Standard Condition N01)	See above	See above		Each PA
564		EIR 589	SC 4.10-1	Prior to the issuance of building permits	Public Area Landscaping:		Public Area Landscaping:	The applicant shall install landscaping, equip for irrigation, and improvements on lots in accordance with an approved plan as stated below: (County Standard Condition LA01b)	Director of	Approved landscaping plan and irrigation plan		Each PA
564.1		EIR 589	SC 4.10-1 (cont.)	See above	Public Area Landscaping:		Public Area Landscaping:	a. Detailed Plan-Prior to the issuance of any building permit(s), the applicant shall submit a detailed landscape plan showing the detailed irrigation and landscaping design to the Manager, Subdivision and Grading for approval, in consultation with the Manager HBP/Program Management. Detailed plans shall show the detailed irrigation and landscaping design and shall take into account the previously approved landscape plan for the Ranch Plan project, the County Standard Plans for landscape areas, adopted plant palette guides, applicable scenic and specific plan requirements, Water Conservation Measures contained in Board Resolution 90-487 (Water Conservation Measures), and Board Resolution 90-1341 (Water Conservation Implementation Plan).	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
570		EIR 589	SC 4.10-3	Prior to the issuance of building permits	Light and Glare:			Prior to issuance of any building permit, the applicant shall demonstrate that all exterior lighting has been designed and located so that all direct rays are confined to the property in a manner meeting the approval of the Manager, Building Permit. (County Standard Condition LG01)	County of Orange Manager of Building Permits, Manager, Permit Services (Building Plan Check)	Approved lighting study/plan	Low voltage lighting: landscape architect is the designer can sign off on the lighting. High voltage lighting: electrical engineer stamp required.	Each PA
589		EIR 589		Prior to issuance of a grading and/or building permit	Hazardous Materials:		Materials:	Prior to the issuance of a grading or building permit, the contractor shall submit to the Fire Chief a list of all hazardous, flammable and combustible liquids, solids or gases to be stored, used or handled on site. These materials shall be classified according to the Uniform Fire Code and a document submitted to the Fire Chief with a summary sheet listing the totals for storage and use for each hazard class. (County Standard Condition FPC11A)	Director of Planning & Development Services	Hazardous Materials Assessment and Disclosure Statement	100000	Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
617		Fire Prot. Prog.	Cond. 3.e.	Prior to the issuance of a building permit for construction phases of Vesting Tentative Tract Maps adjoining fuel modification areas, and prior to the County of Orange allowing fuel tanks, generators and/or Lumber Drops	Vegetation Clearance:		Clearance:	e) Prior to the issuance of a building permit for construction phases of Vesting Tentative Tract Maps adjoining fuel modification areas, and prior to the County of Orange allowing fuel tanks, generators and/or Lumber Drops (see Section E, Definitions) within the project site, the applicant shall provide the Manager, Building & Safety, with a clearance from OCFA indicating that vegetation has been cleared and maintained at a height of 8 inches or less, or that the appropriate fuel modification thinning and removal of plants from the OCFA Undesirable Plant List has been implemented.	Director, PDS, Director, OC Planning	Provide the Manager, Building & Safety, with a clearance from OCFA indicating that vegetation has been cleared and maintained		
COA# 3		PA2.3 Builer "B" Map COAs	Cond. #3	Prior to the issuance of a building permit			MANAGEMENT PRACTICES	Prior to issuance of a building permit, the off- site regional Best Management Practices (BMPs) relied upon by this project (e.g., basins, swales, etc.) must be built and/or installed, and operational. The location and operation of these regional BMPs must be in compliance with the Final Project-Specific WQMP for the regional BMP(s). The location and operation of the regional BMP(s) must be demonstrated to the satisfaction of the Manager, Grading and Building Plan Check.	Manager, Permit Services (Building Plan Check)			
COA# 6		PA2.3 Builer "B" Map COAs	Cond. #6	Prior to the issuance of a building permit			NOTIFICATION MAP	Prior to the issuance of any building permits for residential construction, the developer RMV Community Development, LLC, shall prepare a map denoting the existing and proposed land uses, arterial highways, and public facilities within the surrounding area for the approval of the Manager, OC Planning. The map content, display, and distribution shall be in accordance with the Buyer Notification Program guidelines listed in Board of Supervisors Resolution 82-1368 and as amended.	Director, PDS, Director, OC Planning			

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
f.	Prior to	Comb	ustible (	Construction								
609			Cond. 2.d.	Prior to initiation of combustible construction	A Map Fire Master Plan (cont.):		A Map Fire Master Plan (cont.):	d) Prior to initiation of combustible construction the following fire master plan improvements shall be verified by site inspection:  • Emergency access  • Water Supply	Director, PDS, Director, OC Planning	Site inspection		
a.	During	Const	ruction						<u> </u>			
197				During construction	Hazards and Hazardous Materials	Remedial measures	ESA Remedial Measures	If soil is encountered during site development that is suspected of being impacted by hazardous materials, work will be halted and site conditions will be evaluated by a qualified environmental professional. If requested by the qualified environmental professional, the results of the evaluation will be submitted to OCHCA and/or RWQCB, and the appropriate remedial measures will be implemented, as directed by OCHCA, RWQCB, or other applicable oversight agency, until all specified requirements of the oversight agencies are satisfied and a no-further-action status is attained	Director, PDS- Director, OC Planning (Orange County Health Care Agency)	Stop work upon encountering condition; prepare evaluation and submit to OCHCA and/or RWQCB (as directed)		Each PA
h.	Prior to	Issua	nce of C	ertificates o	f Occupanc	V		laction status is attained.				
529		EIR 589		Prior to recordation of a	Drainage Improvements (cont.):		Drainage Improvements (cont.):	B. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any certificates of use and occupancy, whichever occurs first, said improvements shall be constructed in a manner meeting the approval of the Manager, Construction. (County Standard Condition D02a)	County of Orange Manager of Inspection, Manager, OC Inspection Division	Verification of construction of drainage improvement		Each PA
531		EIR 589	SC 4.5-3 (cont.)	Prior to the issuance of Certificates of Use and Occupancy	Drainage Improvements (cont.):		Drainage Improvements (cont.):	B. Prior to the issuance of any certificates of use and occupancy, said improvements shall be constructed in a manner meeting the approval of the Manager, Construction. (County Standard Condition D02b)	County of Orange Manager of Inspection, Manager, OC Inspection	Verification of installation of drainage improvement		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
539		EIR 589	SC 4.5-9	Prior to the issuance of a Certificate of Use and Occupancy	Compliance with the WQMP:		Compliance with the WQMP:	Prior to the issuance of a certificate of use and occupancy, the applicant shall demonstrate compliance with the WQMP in a manner meeting the satisfaction of the Manager, Inspection Services Division, including:  • Demonstrate that all structural Best Management Practices (BMPs) described in the project's WQMP have been implemented, constructed and installed in conformance with approved plans and specifications;  • Demonstrate that the applicant has complied with all non-structural BMPs described in the project's WQMP;  • Submit for review and approval an Operations and Maintenance (O&M) Plan for all structural BMPs for attachment to the WOMP.	Inspection, Manager, OC Inspection Division	Verification of compliance with Water Quality Management Plan		Each PA
539.1		EIR 589	SC 4.5-9 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate that copies of the project's approved WQMP (with attached O&M Plan) are available for each of the incoming occupants;     Agree to pay for a Special Investigation from the County of Orange for a date (12) twelve months after the issuance of a Certificate of Use and Occupancy for the project to verify compliance with the approved WQMP and O&M Plan; and (County Standard Condition WQ03)	See above	See above		Each PA
539.2		EIR 589	SC 4.5-9 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate that the applicant has agreed to and recorded one of the following: 1) the CC&R's (that must include the approved WQMP and O&M Plan) for the project Home Owner's Association; 2) a water quality implementation agreement that has the approved WQMP and O&M Plan attached; or 3) the final approved Water Quality Management Plan (WQMP) and Operations and Maintenance (O&M) Plan. (County Standard Condition WQ03)	See above	See above		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
560		EIR 589	SC 4.8-4	Prior to the issuance of certificates of use and occupancy	Multi-Family Residential Development:		Multi-Family Residential Development:	Prior to the issuance of any certificates of use and occupancy, the applicant shall perform field testing in accordance with Title 24 Regulations to verify compliance with FSTC and FIIC standards if determined necessary by the Manager, Building Inspection Services. In the event such a test was previously performed, the applicant shall provide satisfactory evidence and a copy of the report to the Manager, Building Inspection Services, as a supplement to the previously required acoustical analysis report. (County Standard Condition N09)		Verification of field testing in accordance with Title 24 Regulations to verify compliance with FSTC and FIIC standards or a copy of a previous test		Each PA
563		EIR 589	SC 4.8-7	Prior to the issuance of certificates of use and occupancy	Transportation Corridor Notification:		Transportation Corridor Notification:	Prior to the issuance of certificates of use and occupancy, the developer shall produce evidence to the Manager, Building Inspection Services, that the Department of Real Estate has been notified that the project area is adjacent to a regional transportation corridor. The corridor is expected to be a high capacity, high-speed, limited-access facility for motor vehicles, and will have provisions for bus lanes and other mass transit type facilities. (County Standard Condition N12)	County of Orange- Manager of- Building- Inspection- Services, Manager, OC Inspection Division	Submission of evidence that County of Orange Dept. of Real Estate has been notified the project area is adjacent to a regional transportation corridor		Each PA
565		EIR 589	SC 4.10-1 (cont.)	Prior to the issuance of final certificates of use and occupancy and the release of financial security	Public Area Landscaping (cont.):		Public Area Landscaping (cont.):	b. Installation Certification: Prior to the issuance of final certificates of use and occupancy and the release of financial security, if any, guaranteeing the landscape improvements, said improvements shall be installed and shall be certified by a licensed landscape architect or licensed landscape contractor, as having been installed in accordance with the approved detailed plans. (County Standard Condition LA01b)	County of Orange Director of Planning & Development Services & Manager HBP, Director, OC Planning	Landscaping and irrigation plan certification from landscape architect		Each PA
566		EIR 589	SC 4.10-1 (cont.)	Prior to the issuance of final certificates of use and occupancy and the release of financial security	Public Area Landscaping (cont.):		Public Area Landscaping (cont.):	b. Installation Certification (cont): The applicant shall furnish said certification, including an irrigation management report for each landscape irrigation system, and any other required implementation report determined applicable, to the Manager, Construction, and the Manager, Building Inspection Services, prior to the issuance of any certificates of use and occupancy. (County Standard Condition LA01b)	County of Orange Manager, Construction and Manager, Building Inspection Services, Manager, OC Inspection Division	irrigation management		Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
568		EIR 589	SC 4.10-2 (cont.)	Prior to the issuance of certificates of use and occupancy	Private Area Landscaping (cont.):		Private Area Landscaping (cont.):	b. Prior to the issuance of certificates of use and occupancy, applicant shall install said landscaping and irrigation system and shall have a licensed landscape architect or licensed landscape contractor, certify that it was installed in accordance with the approved plan. (County Standard Condition LA02b)	Director of Planning & Development Services, Director, OC Planning	Certification from landscape architect that landscaping and irrigation system in accordance with the approved plan		Each PA
569		EIR 589	SC 4.10-2 (cont.)	Prior to the issuance of certificates of use and occupancy	Private Area Landscaping (cont.):		Private Area Landscaping (cont.):	c. Prior to the issuance of any certificates of use and occupancy, the applicant shall furnish said installation certification, including an irrigation management report for each landscape irrigation system, and any other implementation report determined applicable, to the Manager, Building Inspection Services. (County Standard Condition LA02b)	Manager, Building Inspection Services,	Approved irrigation management report for each landscape irrigation system		Each PA
618		Fire Prot. Prog.		Prior to the issuance of any certificate of use and occupancy adjoining fuel modification areas	Occupancy Requirements:		Occupancy Requirements:	f) Prior to the issuance of any certificate of use and occupancy, the applicant shall provide the Manager, Building & Safety, with a clearance from OCFA indicating that: 1. Approved "A" Zone planting has been installed and approved irrigation has been activated.  2. Approved fuel modification zone markers have been installed.  3. Accessways every 500 feet (or as approved) have been installed.  4. Approved thinning of the "B" and "C" Zones and removal of plants from the OCFA Undesirable Plant List have been completed.  5. CC&Rs or other approved documents contain provisions for maintaining the fuel modification zones.	Planning	Provide the Manager, Building & Safety, with a clearance from OCFA indicating installation and thinning		

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
	Prior to			ading Bond								
572			SC 4.11-1 (cont.)	release of the grading bond	Archaeology Grading Observation and Salvage (cont.):		Archaeology Grading Observation and Salvage (cont.):	Prior to the release of the grading bond, the applicant shall obtain approval of the archaeologist's follow-up report from the Manager, Harbors, Beaches & Parks HBP/Coastal and Historical Facilities. The report shall include the period of inspection, an analysis of any artifacts found and the present repository of the artifacts. Applicant shall prepare excavated material to the point of identification. Applicant shall offer excavated finds for curatorial purposes to the County of Orange, or its designee, on a first refusal basis. (County Standard Condition A04)	County of Orange- Manager,- Harbors, Beaches & Parks- HBP/Coastal and- Historical- Facilities— OC Public Works/OC Planning*	archaeologist's follow-up report		Each PA
573		EIR 589	SC 4.11-1 (cont.)	Prior to the release of the grading bond	Archaeology Grading Observation and Salvage (cont.):		Archaeology Grading Observation and Salvage (cont.):	These actions, as well as final mitigation and disposition of the resources shall be subject to the approval of the Manager, HBP/Coastal and Historical Facilities. Applicant shall pay curatorial fees if an applicable fee program has been adopted by the Board of Supervisor, and such fee program is in effect at the time of presentation of the materials to the County of Orange or its designee, all in a manner meeting the approval of the Manager, HBP/Coastal and Historical Facilities. (County Standard Condition A04)	County of Orange Manager, Harbors, Beaches & Parks HBP/Coastal and Historical Facilities OC Public Works/OC Planning*	Verification of payment of curatorial fee if an applicable fee program has been adopted by the Board of Supervisor at the time of presentation		Each PA
575		EIR 589	SC 4.11-2 (cont.)	Prior to the release of the grading bond	Paleontology Resource Surveillance (cont.):		Paleontology Resource Surveillance (cont.):	Prior to the release of any grading bond, the contractor shall submit the paleontologist's follow up report for approval by the County Manager, HBP/Coastal and Historical Facilities. The report shall include the period of inspection, a catalogue and analysis of the fossils found, and the present repository of the fossils. The contractor shall prepare excavated material to the point of identification. The contractor shall offer excavated finds for curatorial purposes to the County of Orange, or its designee, on a first-refusal basis. (County Standard Condition A07)	Gounty of Orange Manager, Harbors, Beaches & Parks HBP/Coastal and Historical Facilities OC Public Works/OC Planning*	Approval of the paleontologist' s follow-up report		Each PA
576		EIR 589	SC 4.11-2 (cont.)	Prior to the release of the grading bond	Paleontology Resource Surveillance (cont.):		Paleontology Resource Surveillance (cont.):	These actions, as well as final mitigation and disposition of the resources, shall be subject to approval by the HBP/Coastal and Historical Facilities. The contractor shall pay curatorial fees if an applicable fee program has been adopted by the Board of Supervisors, and such fee program is in effect at the time of presentation of the materials to the County of Orange or its designee, all in a manner meeting the approval of the County Manager, HBP/Coastal and Historical Facilities. (County Standard Condition A07)	County of Orange Manager, Harbors, Beaches & Parks HBP/Ceastal and Historical Facilities OC Public Works/OC Planning*	Verification of payment of curatorial fee if an applicable fee program has been adopted by the Board of Supervisor at the time of presentation		Each PA

# **ATTACHMENT 1**



October 7, 2020

Bea Bea Jiménez Division Manager Land Development OC Public Works 601 North Ross Street Santa Ana, CA 92701

#### SUBJECT:

Application for "B" Vesting Tentative Tract Maps 190025 within Rancho Mission Viejo (Ranch Plan) Planning Area 3, Subarea 3.1 for the MR37 project (Pulte Group)

Dear Ms. Jiménez,

#### PROPOSAL:

Rancho Mission Viejo requests Subdivision Committee approval of Vesting Tentative Tract Map 19025 within Rancho Mission Viejo (Ranch Plan) Planning Area 3, Subarea 3.1 for the MR37 project to allow 73 Planned Concept Detached Dwellings on 73 numbered residential lots and 8 numbered and 22 lettered lots for landscaped open space, private motor courts and alley purposes. Site Development Permit PA20-0048 is being processed concurrently.

#### ZONING:

Ranch Plan Planned Community (PC) – Subarea Plan 3.1 Planned Concept Detached Dwellings (PC Text Section III.A.2)

#### LOCATION:

The MR37 project site is located within the Ranch Plan Planned Community - Planning Area 3 (PA3), Subarea 3.1 and Tract Map 17931, Lots 1-11 and 74 in unincorporated Orange County, California. The site is surrounded by Ranch Canyon road to the west, Saddle Way to the south, future Subarea 3.2 residential and recreational area to the north and east.

#### LANDOWNER/SUBDIVIDER:

The specific land ownership entity for the proposed project site is RMV PA3 Development LLC (referred to as Rancho Mission Viejo, or "RMV"). The site will eventually be owned by, and homes built by, The Pulte Group.

### **BACKGROUND AND EXISTING CONDITIONS:**

In November 2004, the County of Orange approved the Ranch Plan Planned Community, which encompasses approximately 22,815 acres located east of I-5, north and south of Ortega Highway, within the Fifth Supervisorial District. As approved, the Ranch Plan Planned Community encompasses 75 percent permanent open space, with development of 14,000 dwelling units and 5,200,000 square feet (SF) of non-residential uses allowed within the

remaining 25 percent. It is regulated by the Ranch Plan PC Program Text which addresses the unique characteristics of the property and a development plan for the transition to suburban/urban uses occurring over a 25- to 30-year period.

The Master Area Plan and Subarea Plans for Planning Area 3 were approved on September 11, 2019 including Subarea Plan 3.1 (PA180030). VTTM 17931 for Subarea Plan 3.1 was approved by the Subdivision Committee on November 20, 2019. Currently, Subarea 3.1 is currently being graded per issued Mass Grading Permit GRD19-0108. 3rd plan-check review of Rough Grading Permit GRD 19-0175 is currently in process.

#### **PROPOSED PROJECT:**

The applicants, RMV and The Pulte Group, request approval of Vesting Tentative Tract Map 19025 to allow 73 Planned Concept Detached Dwellings on 73 Planned Concept Detached Dwellings on 73 numbered residential lots and 8 numbered and 22 lettered lots for landscaped open space, private motor courts and alley purposes, all within the proposed 8.14-acre project site. The project will also include street and infrastructure improvements, landscaping, and minor precise grading. A model home complex is proposed within Lots 1-3 of TT19025.

The 73 numbered lots range in size from 2,253 square feet up to 4,538 square feet. The site has a net residential acreage of 2.21 du/ac (excluding streets, motorcourts, alleys and HOA slopes) for a net residential density of 12.9 dwelling units per acre. As permitted by Ranch Plan Alternative Development Standard (ADS) D-8, Planned Concept Single-Family Detached Dwellings are permitted on lots in excess of 3,000 square feet, provided a minimum net residential density of 8 dwelling units per acre is maintained.

The project proposes a site design with motor court layout with dwellings having garages accessible via private alleys and motor courts. All private alleys and motor courts will take access off public street lvy Way.

#### **SURROUNDING LAND USE:**

Land uses immediately surrounding the project site include the following:

- Westerly: Ranch Canyon and permanent Open Space
- Southerly: Saddle Way and future residential (TRI-Pointe MR13)
- Northerly and Easterly: Subarea 3.1 future residential and recreational

#### REFERRAL FOR COMMENT AND PUBLIC NOTICE:

The applicant understands that the tentative map application submittal will be distributed for review and comment to County staff and consultants, including Land Development, OC Infrastructure Programs, Inspection Services, Building & Safety OC Survey, and Orange County Fire Authority. We also understand that the VTTM must be approved by the OC Subdivision Committee at a Public Meeting with a public notice mailed to all property owners of record within 300 feet of the subject, and posted at the site, at the Orange County Hall of Administration, and at 601 N. Ross Street, as required by established public meeting posting procedures.

#### **CEQA COMPLIANCE:**

Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 26, 2006; Addendum 1.1 (PA110003-06) approved February 24, 2011; the Planning Area 2 Addendum (PA130001-06) approved March 27, 2013; and Addendum 3.1 (PA140072-81) approved February 25, 2015. Further CEQA evaluation and clearances are not required for this proposed SDP or VTTM.

#### **CONSISTENCY ANALYSIS:**

The proposed SDP and VTTM are consistent with the Ranch Plan PC Program Text Use Regulations & Development Standards (PC Program Text, Section III), as described below:

- a. General Plan The OC General Plan Land Use Element designates Subarea 3.1 of Ranch Plan as "1B, Suburban Residential (0.5 to 18 du/ac)", per GPA 01-01. The proposed SDP and VTTM are consistent with the 1B "Suburban Residential designation.
- b. Zoning The proposed SDP and VTTM are consistent with the Ranch Plan Planned Community zoning, including all applicable requirements of the PC Program Text Use Regulations & Development Standards (PC Section III).
- c. State Subdivision Map Act and County of Orange Subdivision Code and Manual In Compliance.
- d. Area Plans The proposed SDP and VTTM are consistent with land uses and other details of PA3&4 Master Area Plan and Subarea Plan 3.1 (PA190030).
- e. CEQA The proposed SDP and VTTM are consistent with Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 26, 2006; Addendum 1.1 (PA110003-06) approved February 24, 2011; the Planning Area 2 Addendum (PA130001-06) approved March 27, 2013; and Addendum 3.1 (PA140072-81) approved February 25, 2015.
- f. Alternative Development Standards All Alternative Development Standards incorporated into this project have been previously approved by the appropriate decision maker per the Ranch Plan Planned Community Program Text, General Regulation 25.
- g. Regulation Compliance Matrix Clearance of all applicable conditions of approval have been confirmed per the Ranch Plan Regulation Compliance Matrix.

#### **Estimated Earthwork**

The proposed estimated grading quantities for this map are substantially consistent with or less than the earthwork quantities described under previous approvals (i.e. Master Area Plan (PA3&4), Subarea Plan 3.1, VTTM 17931, and Subarea 3.1 Mass Grading Permit GRD19-0108. Subarea 3.1 is currently being graded per issued Rough Grading Permit GRD 19-0175, and Revision 1 to GRD 19-0175 currently in process. The proposed grading on this map has been addressed per CEQA document FEIR 589, together with Addendum 3.1 (PA140072-81) approved February 25, 2015.

#### Drainage:

The subject property is in the Ranch Plan Planned Community Runoff Management Plan Area. No Master Plan of Drainage (MPD) facilities have been identified or approved within the site and no MPD fees are required.

#### Recreation and Open Space:

The proposed map is not required to provide any improvements or dedications associated with the County Master Plan of Regional Recreation Facilities; Master Plan of Regional Riding and Hiking Trails; Resources Element (Open Space Component); or OCTA Strategic Plan for Bikeways.

- Master Plan of Regional Recreation Facilities There are no regional park dedication requirements of the subject map.
- Master Plan of Regional Riding and Hiking Trails There are no riding and hiking trail requirements of the subject map.

- Master Plan of Local Parks (Local Park Code) The proposed map is required to provide park land in accordance with the Master Plan of Local Parks (Local Park Code). The Local Park Code requirement for the subject map VTTM 19025 is 0.438 net usable acres of park land based upon a proposal to build 73 dwelling units at a gross residential density of 8.97 du/ac (73 du x .006 ac/du). Said requirement can be satisfied by an allocation of parkland credit from Park Modification PM07-01, the Local Park Implementation Plan (LPIP) for the Ranch Plan P.C. originally approved March 14, 2007, 1st Amendment approved in June 2012, 2<sup>nd</sup> Amendment approved on July 16, 2014, and 3<sup>rd</sup> Amendment approved November 7, 2019. Per the Ranch Plan LPIP, the total parkland acreage requirement for the entire Ranch Plan Planned Community is 94.0 acres, based on 14,000 approved dwelling units and the anticipated proportion of singlefamily and multi-family units. The Ranch Plan LPIP (PM07-01) indicates that far more acres of total community-wide parkland will be implemented in Planning Area 3&4 than would be required per County standards, based on the 7,500 dwelling units entitled by the PA3&4 Master Area Plan PA180030, per the parkland generation factor for each unit (greater than 6.5 du/ac requires 0.006 acres and less than 6.5 du/ac requires 0.008 acres). Rancho Mission Viejo's Final Tract Map 17931 for Subarea 3.1, will include 6.6 acres of recreation facilities (Ranch Camp).
- Resources Element Open Space Component There are no open space dedication requirements of the subject map.
- OCTA Strategic Plan for Bikeways There are no County-wide bikeways identified within the area of this map.

#### Public Services & Utilities

- Schools This property is within the boundaries of the Capistrano Unified School District.
  The developer is subject to the provisions of Assembly Bill AB 2926, or other mitigating
  measures designed to provide for school facilities and/or funding, such as community
  facilities districts. No school facilities are proposed within Subarea 3.1.
- Facilities Fees Programs This project area is included within the Ranch Plan Planned Community Development Facility Agreement area which phases development commensurate with public services and facilities.
- Water/Sewer This project is within the boundaries of the Santa Margarita Water District. The District stated in their "will-serve" letter dated ##/##/2020, that the District will be capable of providing water and sewage disposal service to this development.
- Water Quality Control This project will be required to operate in accordance with requirements prescribed by the California Regional Water Quality Control Board, San Diego Region.
- Fire Protection and Safety Existing and proposed fire protection services will be
  providing an adequate level of fire protection services to this development, per the
  TT19025 Fire Master Plan approved by OCFA ##/##/2020. Additionally, this property is
  within the area covered by the approved Ranch Plan Fire Protection Program, which
  includes all applicable conditions of approval and regulations.
- County Service Area (CSA) This property is within the boundaries of County Service Area No. 26.

#### Traffic/Circulation

- Scenic Highway Corridors There are no Scenic Highways applicable to this map
- Access/Highways/Streets/Roads Access to the site is Cherry Court. Internal tract access will be provided by internal private alleys and motor courts.

- Major Thoroughfare and Bridge Fee Program This project lies within the area of benefit of the Foothill/Eastern Transportation Corridor. The developer is required to pay Foothill/Eastern Major Thoroughfare and Bridge fees in accordance with the adopted program.
- Off-Site Fee Program The project lies within the area of benefit of the South County Roadway Improvement Road Fee Program (SCRIP). The developer is required to pay SCRIP fees in accordance with the adopted program.

#### Multiple Final Map Phasing

As indicated in the notes for TT190025, the option of multiple final maps phasing has been requested as part of the approval of this Vesting Tentative Tract Map.

#### **DEVIATIONS FROM STANDARDS OF DESIGN:**

The developer may request deviations from County standard design criteria in accordance with Subdivision Code section 7-9-291. In the absence of any specifically approved deviation request, the County-approved standard design criteria will prevail. No deviations are requested with this map.

#### **ALTERNATIVE DEVELOPMENT STANDARDS:**

As indicated in the notes for TT190025, as allowed by General Regulation #25 of the Ranch Plan Planned Community Program Text, proposed Alternative Development Standards are intended to be incorporated into the development.

Upon review of this application our hope is that staff supports OC Subdivision Committee approval of the "B" tentative tract map. Please contact me with any questions, or if you or your staff need any further information.

Sincerely,

Jay Bullock

Vice President, Planning and Entitlement

Rancho Mission Viejo

## **ATTACHMENT 2**

#### **BOARD OF DIRECTORS**

BETTY H. OLSON, PH.D FRANK URY

CHARLES T. GIBSON SAUNDRA F. JACOBS
JUSTIN McCUSKER

DANIEL R. FERONS GENERAL MANAGER



### Santa Margarita Water District

January 26, 2021

County of Orange OC Public Works OC Development Services 601 N. Ross Street Santa Ana, California 92703

Subject: Preliminary Water and Sewer Letter for PulteGroup Inc., VTTM 19025, Rancho Mission

Viejo, in Improvement District No. 5

Greetings:

This letter is in response to a request by PulteGroup Inc. (Developer) for a preliminary water and sewer letter for the subject tract.

The Santa Margarita Water District (District) supplies all of its current customers with domestic water purchased from the Metropolitan Water District of Southern California (Metropolitan) through the Municipal Water District of Orange County (MWDOC), which acts as a wholesaler to its member agencies. It is anticipated the subject tract would also be supplied with available domestic water purchased from Metropolitan through MWDOC. Supplemental water for this development, if required, will be provided via the implementation of an agreement between SMWD and Cucamonga County Water District (now called Cucamonga Valley Water District) that has been executed for the specific purpose of providing supplemental water in support of the "Ranch Plan". Subject to the Developer's successful completion of the construction of the in-tract water facilities, the District can and will provide domestic and non-domestic water service to each and every building parcel in the subject tract.

Furthermore, and subject to the Developer's successful completion of the in-tract sewer facilities and the District's construction of off-site sewer facilities, the District can and will provide sewer service to each and every building lot within the subject tract without exception.

At this time, the Developer has not provided surety to guarantee the construction of the in-tract water and sewer facilities. A final will-serve will be issued upon your request when (1) the Developer has guaranteed the construction of the in-tract facilities and (2) construction of the District's water and sewer facilities is assured.

Should you have any questions or desire additional information, please call Karla Houlihan at (949) 459-6581.

Sincerely,

SANTA MARGARITA WATER DISTRICT


Patricia A Butler Chief Engineer


Patricia Butler


S:\ENGINEERING\PRELIMINARY WILL SERVE\2021\Will Serve VTTM 19025 - PulteGroup.doc


# **ATTACHMENT 3**


#### SUMMARY VESTING TENTATIVE TRACT MAP 19025 NUMBERED | LOT SQUARE | LOT SQUAR EXISTING LAND USE: PREVIOUSLY ROUGH GRADED PER GRD19-0175 FOOTAGE PROPOSED LAND USE: RESIDENTIAL - 73 SINGLE-FAMILY DETACHED UNITS 2 | 3,575.9 0.08 THE PLANNING AREA 3 MASTER AREA PLAN AND SUB-AREA PLAN 3.1 (PA180030) P.A. 3.1 - PULTE MR37 DESIGNATE THE EXISTING ZONING AREA: MR37 IS LOCATED WITHIN RANCH PLAN PLANNED 3 4,286.5 0.10 COMMUNITY PLANNING AREA 3.1, IS ZONED AS A DEVELOPMENT AREA BY THE RANCH 2,929.1 0.07 5 2,562.1 0.06 THE PLANNING AREA 3 MASTER AREA PLAN AND SUB-AREA PLAN 3.1 (PA180030) LEGAL DESCRIPTION 6 2,987.2 0.07 DESIGNATE PROJECT SITE AS RESIDENTIAL. THIS VESTING TENTATIVE TRACT MAP MORE 2,942.2 0.07 SPECIFICALLY IDENTIFIES THIS SITE DESIGNATION AS PLANNED CONCEPT DETACHED LOTS 1-11 INCLUSIVE & LOT 74 OF FINAL MAP, "A" TRACT NO. 17931 DWELLING, PER PC TEXT SECTION III.A.2, CONSISTENT WITH THE REFERENCED RANCH 8 2,427.7 0.06 PLAN PC TEXT SITE DEVELOPMENT STANDARD. 9 2,980.4 0.07 LAND USES IMMEDIATELY SURROUNDING THE PROJECT SITE INCLUDES THE FOLLOWING: 2,877.1 0.07 WESTERLY: RANCH CANYON AND PERMANENT OPEN SPACE 2,441.8 SOUTHERLY: SADDLE WAY AND FUTURE RESIDENTIAL (TRI-POINTE MR13) 0.06 NORTHERLY: FUTURE SUBAREA 3.2 RESIDENTIAL 2,891.5 0.07 EASTERLY: FUTURE SUBAREA 3.2 PARK 3,267.8 0.08 SANITARY SEWER PROVIDED BY: SANTA MARGARITA WATER DISTRICT 2,900.8 0.07 DOMESTIC WATER PROVIDED BY: SANTA MARGARITA WATER DISTRICT 3,469.9 0.08 NON-DOMESTIC WATER PROVIDED BY: SANTA MARGARITA WATER DISTRICT 3,486.4 0.08 ALL PROPOSED UTILITIES ARE TO BE UNDERGROUND. PROPOSED UTILITY LOCATIONS 17 2,746.0 0.06 SHOWN ON THE MAP ARE APPROXIMATE. ACTUAL LOCATIONS AND EASEMENT WIDTHS 2,774.3 0.06 **VICINITY MAP** WILL BE REFLECTED ON FINAL TRACT MAP(S). 4,772.0 0.11 SOUTHERN CALIFORNIA GAS COMPANY 3,337.0 20 0.08 SAN DIEGO GAS AND ELECTRIC 3,413.6 0.08 3,319.8 0.08 TELEPHONE: AT&T AND COX COMMUNICATIONS 3,482.7 0.08 CABLE TELEVISION: COX COMMUNICATIONS 2,252.7 0.05 ). PROJECT SITE IS LOCATED WITHIN THE CAPISTRANO UNIFIED SCHOOL DISTRICT. 2,550.6 0.06 2,839.2 0.07 STORM FLOWS TRIBUTARY TO THE SITE SHALL BE INTERCEPTED AND CONVEYED AROUND 26 THE SITE VIA THE STORM DRAIN SYSTEMS SHOWN HEREON. ALL PROPOSED STORM 2,257.9 0.05 DRAINS SHOWN HEREON ARE PRELIMINARY. STORM DRAIN PLANS WILL BE PREPARED 3,301.9 0.08 PRIOR TO RECORDATION OF THE FINAL MAP. 29 | 3,693.8 0.08 PUBLIC EASEMENTS (IF NECESSARY) FOR SIDEWALK PURPOSES WILL BE REFLECTED ON 2,740.8 0.06 31 2,748.0 0.06 . THE APPLICANT REQUESTS THE OPTION OF RECORDING MULTIPLE FINAL MAPS FROM THIS 32 2,921.2 0.07 VESTING TENTATIVE TRACT MAP PER SECTION 66456.1 OF THE STATE OF CALIFORNIA 2,737.8 GOVERNMENT CODE (SUBDIVISION MAP ACT) AS AMENDED JANUARY, 2020. 0.06 3,012.8 0.07 . VTTM 19025 IS NOT LOCATED WITHIN A SPECIAL FLOOD HAZARD ZONE PER THE CONDITIONAL LETTER OF MAP REVISION (CLOMR) APPROVED BY FEMA AND THE COUNTY 2,970.2 0.07 35 2,666.0 0.06 5. AN EASEMENT FOR EMERGENCY VEHICLE ACCESS SHALL BE DEDICATED TO THE COUNTY 2,666.0 0.06 2% MIN.**∮** OF ORANGE ON THE FINAL MAP OVER ALL PRIVATE STREETS. 38 2,972.2 0.07 PER THE RANCH PLAN PLANNED COMMUNITY—WIDE ALTERNATIVE DEVELOPMENT 39 2,779.9 0.06 STANDARDS (APPROVED MARCH 14, 2007 AND MOST RECENTLY AMENDED SEPTEMBER 26, 40 2,712.4 0.06 2018: SUBSEQUENT REVISIONS OR ADDITIONS MAY ALSO BE APPROVED), AND AS 2,876.0 0.07 ALLOWED BY RANCH PLAN PC TEXT (GENERAL REGULATION 25) THE FOLLOWING 3,069.9 ALTERNATIVE DEVELOPMENT STANDARDS (ADS) ARE PROPOSED: 0.07 **SECTION A-A** 4,056.9 0.09 • A-1 36-FOOT DOUBLE LOADED STREETS (UP TO 800 ADT) 47.9' 3,342.3 0.08 A-5 RESIDENTIAL PARKWAYS 2,677.8 0.06 • A-9 TAPERED STREETS DOUBLE LOADED 2,385.0 0.05 A-19 CUL-DE-SACS WITH RAISED LANDSCAPE MEDIAN 3,189.0 0.07 • A-20 ALTERNATIVE NEIGHBORHOOD SIDEWALK DETAIL-CURB SEPARATED WALKWAY 3,322.3 0.08 A-36 RIBBON CURB 3,076.1 0.07 • B-9 MODIFIED COLOR OF CURB RAMP DETECTABLE WARNING SURFACE 3,180.7 0.07 D-8 PLANNED CONCEPT RESIDENTIAL LOTS GREAT THAN 3,000 SQUARE FEET 2,816.3 SECTION B-B D−17 CREDIT TOWARD USABLE PRIVATE OPEN SPACE 3,902.3 0.09 3,816.6 • G-3g PRIVATE ALLEY DRIVE ALLOWING EMERGENCY VEHICLE ACCESS 2,739.3 0.06 G-3b PRIVATE ALLEY DRIVE WITH NO REQUIREMENT FOR EMERGENCY VEHICLE ACCESS PAD=366.4 C 3,284.7 55 0.08 G-7 REDUCED LOCAL DEPRESSION ON PRIVATE STREETS ' (SEE NOTE #4. STD. PLAN 1320) 3,185.2 0.07 BOUNDARY • G-9 ROLLED CURB ON PRIVATE STREETS 2,739.3 0.06 7. GRADING: 6" MIN. ABOVE PAD 3,642.5 0.08 a. GRADING PLANS MAY BE PROCESSED CONCURRENTLY WITH TENTATIVE TRACT MAPS. PER 3,668.3 0.08 BLDG. PAD ELEV! A CONCURRENT PROCESSING REQUEST LETTER. PLAN CHECKING OF GA OR GB PLANS 60 2,827.7 0.06 PAD=365.1 DOMESTIC WATER MAIN MAY PROCEED, BUT APPROVAL OF THE GRADING PLAN MUST FOLLOW VTTM APPROVAL. 61 3,360.3 0.08 POINT OF CONNECTION ESTIMATED EARTHWORK — PROPOSED GRADING OF 2,000 CUBIC YARDS IS CONSISTENT 2,919.1 0.07 CAPITAL WATER IMPROVEMENT PLANS WITH THE PA3 MASTER AREA PLAN, SUBAREA PLAN 3.1 (PA180030), VESTING 2,342.7 0.05 FOOTING REQUIRED TO BLDG. PAD ELEV. OR HIGHER TENTATIVE TRACT MAP 19025 AND RELATED GRADING PERMITS. 64 3,246.3 0.07 PAD=365.0 SECTION C-C 3,365.9 0.08 ENVIRONMENTAL - PROPOSED GRADING HAS BEEN ADDRESSED PER FINAL PROGRAM EIR 2,312.9 0.05 589, ADDENDUMS 1.0, 1.1, AND 3.1, AND PLANNING AREA 3 ADDENDUM. 67 2,846.8 0.07 8. IN THE DESIGN OF THIS MAP, THE SOLAR ACCESS GUIDELINES ADOPTED BY THE BOARD TYPICAL PAD GRADING DETAIL 2,701.3 0.06 OF SUPERVISORS WERE CONSIDERED. 2,314.4 0.05 PER COUNTY OF ORANGE STANDARD PLAN 1320 . THE EXPIRATION DATE OF THIS TENTATIVE MAP SHALL RUN CONCURRENT WITH (AND NOT 70 | 3,677.5 0.08 NOT TO SCALE TERMINATE PRIOR TO THE EXPIRATION OF) THE DEVELOPMENT AGREEMENT, EVEN IF THAT 71 4,717.4 TIME FRAME EXCEEDS TEN YEARS, BASED ON GOVERNMENT CODE SECTION 0.11 66452.6(a)(1) AND RANCHO MISSION VIEJO DEVELOPMENT AGREEMENT 04-01 SECTIONS 2,839.3 0.07 73 | 3,172.4 0.07 O. ALL PROPOSED SEWER & WATER SHALL BE DEDICATED TO SANTA MARGARITA WATER 1,162.5 0.03 DISTRICT AS PUBLIC UTILITIES. 3,129.5 0.07 ALL UNITS ARE TO BE SPRINKLERED PER RANCH FIRE PROTECTION PROGRAM AND OCFA 76\* 728.2 0.02 REQUIREMENTS. 77\* 7,025.7 0.16 22. ALL INFRASTRUCTURE IMPROVEMENTS WITHIN THE TENTATIVE TRACT MAP ARE PROVIDED 1,255.7 0.03 BY BUILDER. 79\* 1,345.5 0.03 3. ALL CONNECTIONS TO PUBLIC ROADWAYS WILL REQUIRE A PUBLIC PROPERTY PERMIT. 80\* 1,122.6 0.03 4. THE NOTES, DEVIATIONS, ALTERNATIVE DEVELOPMENT STANDARDS STATED ON VESTING PAD=362.4 81\* 671.5 0.02 TENTATIVE MAP NO. 17931 R-1 ARE INCLUDED IN THIS MAP BY REFERENCE. NUMBERED 241,691.3 5.55 TRACT BOUNDARY 5. COUNTY PROCESSING STEPS AND PROCEDURES FOR THIS VESTING TENTATIVE TRACT MAP ARE MADE IN ACCORDANCE WITH THE RANCH PLAN SUBDIVISION FLOWCHART AND PROPOSED PROPERTY LINE CHECKLIST AVAILABLE ON-LINE. TRACT 17931 LETTERED | LOT SQUARE | LOT SQUAR 6. DRAINAGE SYSTEM WILL BE DEVELOPED IN ACCORDANCE WITH THE O.C. PUBLIC WORKS BOUNDARY ————— EASEMENTS FOOTAGE ACRAGE AND COUNTY OF ORANGE FLOOD CONTROL DISTRICT STANDARDS IN ACCORDANCE WITH 3,486.5 0.08 THE APPLICABLE "MASTER PLAN OF DRAINAGE" FOR TRACT 17931 PREPARED BY ----- WALL В 2,854.7 0.07 MICHAEL BAKER INTERNATIONAL AND THE RUNOFF MANAGEMENT PLAN (ROMP) PA3 AND 250 GRADING CONTOUR 3,406.0 0.08 4 APPROVED ON 11/12/2019. 2,971.1 0.07 7. STREET IMPROVEMENTS SHOWN HEREON SHALL MEET THE REQUIREMENTS OF THE COUNTY LOT NUMBER/LETTER E 3,159.0 0.07 OF ORANGE OR COUNTY-APPROVED RANCH PLAN ALTERNATIVE DEVELOPMENT STANDARDS, 10T "N1" EXCEPT FOR DEVIATIONS AS LISTED HEREON. 7,460.8 0.17 8. ALL SLOPES SHALL BE CONSTRUCTED AT A MAXIMUM SLOPE RATIO OF 2:1 UNLESS 1,900.1 0.04 APPROVED BY THE COUNTY. 2,988.5 0.07 DOMESTIC WATER POINT 9. FLOW TRIBUTARIES TO THE SITE SHALL BE INTERCEPTED AND CONVEYED AROUND AND ı 3,038.5 0.07 THROUGH THE SITE VIA THE PROPOSED STORM DRAIN SYSTEMS SHOWN HEREON. 3,075.7 0.07 O. ACCESS TO THE SITE IS PROPOSED VIA "SADDLE WAY". STREETS ARE PUBLIC AND 3,158.3 0.07 DRY UTILITY POINT OF ALLEYS ARE PRIVATE. L 51,719.7 1.19 . THIS MAP IS AN APPLICATION FOR A DEVELOPMENT PERMIT PURSUANT TO SECTION 17,849.9 0.41 65943 OF THE CALIFORNIA GOVERNMENT CODE. 449.7 0.01 2. PROPOSED UTILITIES AND EASEMENTS, INCLUDING BUT NOT LIMITED TO PUBLIC UTILITIES, 514.5 0.01 OCS BM "AP-02-00" (NAVD88) ELEVATION: 238.11' FIRE ACCESS. PRIVATE ACCESS. PRIVATE UTILITIES AND ACCESS ARE APPROXIMATE. P\* 515.5 0.01 ACTUAL UTILITY AND TRAIL LOCATIONS AND EASEMENT WIDTHS WILL BE REFLECTED ON FOUND 3-3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "AP-02-99," SET IN THE FINAL MAPS, OR BY SEPARATE EASEMENT DOCUMENTS SUBSEQUENT TO FINAL MAP 103.8 0.002 THE NORTHEASTERLY CORNER OF A CONCRETE BRIDGE DECK. MONUMENT IS 0.002 108.0 LOCATED IN THE NORTHEASTERLY CORNER OF ANTONIO PARKWAY AND ITS 3. THE COUNTY OF ORANGE WILL NOT BE RESPONSIBLE FOR MAINTENANCE OF PRIVATE 76.6 0.002 OVERCROSSING OF SAN JUAN CREEK. STREETS/EASEMENTS 0.042 1,836.0 103.5 0.002 **ENGINEERS STATEMENT:** 65.0 1,965.5 0.045 STATISTICAL SUMMARY: I HEREBY STATE THAT THIS MAP WAS PREPARED UNDER MY SUPERVISION AND THAT THE OWNER OF RECORD HAS KNOWLEDGE OF AND CONSENTS TO THE 112,552.60 LOTS FILING OF THIS MAP LOT NUMBERS | TOTAL LOTS | AREA (AC) | GROSS % | NET % | PROPOSED LAND USE RMV PA3 DEVELOPMENT LLC COMMENTS \*OPEN SPACE AREAS 50' 0' 25' 50' SAN JUAN CAPISTRANO, CA \_\_\_\_ DATE: \_\_\_\_\_\_ 92675 1-73 73 63.48 5.18 TREVOR DODSON, P.E. 42029 **SLOPE DESIGNATIONS:** (949)240-3363 **RAW EARTHWORK QUANTITIES:** SCALE: 1" = 50'POCKET PARK (OPEN ALL MANUFACTURED SLOPES TO HAVE TERRACE AND DOWN DRAINS AS REQUIRED BY THE CONVEY TO HOA (MR-37)74-81 0.39 4.78 6.89 DATE: March 23, 2021 COUNTY OF ORANGE GRADING CODE REQUIREMENTS. SPACE) RAW CUT: 1,825 CY STATEMENT OF OWNERSHIP: RAW FILL: 1,825 CY PULTE GROUP, INC. IS THE OWNER OF THAT PORTION OF PA3 COVERED BY TRACT -----1.19 14.58 PUBLIC STREET (IVY WAY) CONVEY TO OC A MAINTAINED BY PUBLIC AGENCY (NONE) PREPARED BY: NET: 0 CY 17931 AND AUTHORIZED TO EXECUTE AND DELIVER ALL DOCUMENTS THAT ARE MAINTAINED BY THE HOA. (MR-37) NECESSARY AND APPROPRIATE FOR PROCESSING AND IMPLEMENTING THE PA3 CONVEY TO SUB-ASSOCIATION PRIVATE STREET DEVELOPMENT PROGRAM. SAID AUTHORIZATION INCLUDES, BUT IS NOT LIMITED TO 0.41 5.03 MAINTAINED BY INDIVIDUAL LOT OWNER. (LONGHORN WAY) (MR - 37)EXECUTION AND DELIVERY OF SUCH APPLICATIONS, AGREEMENTS AND OTHER DOCUMENTS AS ARE REQUIRED BY THE COUNTY OF ORANGE IN CONNECTION WITH THE MAINTAINED BY MASTER HOA CONVEY TO HOA (MR-37) 11.03 PRIVATE MOTOR COURT 11 0.90 NO. DATE PROCESSING AND DEVELOPMENT OF PA3. REVISIONS APP'D NO. C42029 EXP. 03/21/2022 10 0.09 1.10 |LANDSCAPE (OPEN SPACE)| CONVEY TO HOA (MR-37) **EASEMENT NOTE:** 16795 Von Karman, Suite 100 DATED THIS:\_\_\_\_\_ DAY OF \_\_\_\_\_ 100% TOTALS 104 8.16 100% (A) PROPOSED EASEMENT TO SMWD FOR SEWER, WATER AND ACCESS PURPOSES Irvine, California 92606 ALL LOTS 1-73, tel 949.474.1960 fax 949.474.5315 (B) EASEMENT FOR EMERGENCY ACCESS AND PUBLIC SECURITY VEHICLE INGRESS DEVELOPMENT AREA GROSS 9.0 DU/AC 8.16 www.fuscoe.com AND EGRESS PURPOSES RECIPROCAL INGRESS/EGRESS AND DRIVEWAY MANEUVERABILITY ACCESS DEVELOPMENT AREA NET 12.90 DU/AC EASEMENT FOR THE BENEFIT OF ALL LOTS IN TRACT NO. 19025 STREET/ALLEY F:\PROJECTS\176\017\PLANS\ENTITLEMENTS\TENTATIVE TRACT MAP\176-017-TTM.DWG (03-23-21 5:34:07PM) Plotted by: Victor Pham












SECTION 6-6

MOTOR COURT
WITH PARALLEL PARKING (ONE SIDE)

(PRIVATE)
(ALLEY 'F')

CURB & GUTTER

CURB & GUTTER —



PROPOSED AREA
DRAIN COLLECTOR D=360.9

PAD=361.3

PROPOSED 8" DOMESTIC WATER LINE

TYPICAL ALLEY WAY UTILITY PLAN

SCALE: 1" = 20'

PROPOSED JOINT TRENCH


PAD=360.1

PROPOSED 8" SEWER LINE

PAD=360.4

PROPOSED AREA 
DRAIN COLLECTOR

9









PA20-0048

F:\PROJECTS\176\017\PLANS\ENTITLEMENTS\TENTATIVE TRACT MAP\176-017-TTM.DWG (03-23-21 5:34:28PM) Plotted by: Victor Pham

