



---

**ITEM #2**

**SUBDIVISION COMMITTEE PRELIMINARY REPORT**

**DATE:** October 1, 2025

**TO:** Orange County Subdivision Committee

**FROM:** OC Development Services / Land Development Division

**SUBJECT:** "B" Vesting Tentative Tract Map 19322 within Planning Area 3, Subarea 3.5, Ranch Plan Planned Community

**PROPOSAL:** The applicant, Rancho Mission Viejo (RMV), requests approval of "B" Vesting Tentative Tract Map 19322 (VTTM 19322) to subdivide a 12.94-acre site into 49 numbered lots for conventional single-family detached dwellings, 1 lettered lot for a private drive, 2 lettered lots for landscaping, and 11 lettered lots for slope/landscape areas.

**ZONING:** Ranch Plan Planned Community

**GENERAL PLAN:** 1B "Suburban Residential"

**LOCATION:** The project site is located in the southeastern portion of unincorporated Orange County, within Subarea 3.5, Lots 26 through 32, and Lots U, W, Y, Z, CC, DD, EE, FF and II of Tract Map 17935 in the Ranch Plan Planned Community. The project site is located east of Ranch Canyon and north of Cow Camp Road, north of the intersection of Legado Road and Lamkin Lane, within the Fifth (5th) Supervisorial District.

**OWNER/  
SUBDIVIDER:** RMV PA3 Development, LLC (RMV)

It is noted that the current landownership is RMV, but the transfer of ownership to Lennar Homes will begin upon recordation of the Final Tract Map.

**APPLICANT:** Rancho Mission Viejo  
Richard Vuong, Project Director, Planning and Entitlement

**STAFF  
CONTACT:** Robert Zegarra, Contract Planner, Land Development Division  
Phone: (714) 667-8893  
Email: [Robert.Zegarra@ocpw.ocgov.com](mailto:Robert.Zegarra@ocpw.ocgov.com)

**RECOMMENDED ACTION(S):**

Land Development recommends that the Subdivision Committee:

- 1) Receive staff report and public testimony as appropriate.
- 2) Find that Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 2006, Addendum 1.1 (PA110003-06) approved February 24, 2011, the Planning Area 2 Addendum (PA130001-06) approved March 27, 2013, and Addendum 3.1 (PA140072-81) approved February 25, 2015 reflect the independent judgment of the County and are adequate to satisfy the requirements of CEQA for approval of Vesting Tentative Tract Map (VTTM) 19322, which is a necessarily included element contemplated as part of the whole of the action considered in Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1.
  - a. The circumstances of the project are substantially the same as described in Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1, which adequately addressed the effects of the project proposed in VTTM 19322. No substantial changes have been made in the project that involve new significant environmental effects or a substantial increase in the severity of previously identified significant effects; no substantial changes have occurred in the circumstances under which the project is being undertaken, that involve new significant environmental effects or a substantial increase in the severity of previously identified environmental effects; and no new information of substantial importance to the project which was not known or could not have been known when Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1 were certified and approved has become known; therefore, no further environmental review is required.
  - b. Final EIR 589, Addendum 1.0, Addendum 1.1, the Planning Area 2 Addendum, and Addendum 3.1, are adequate to satisfy the requirements of CEQA for VTTM 19322.
  - c. All mitigation measures are fully enforceable pursuant to Public Resources Code section 21081.6(b) and have either been adopted as conditions, incorporated as part of the project design or included in the procedures of project implementation.
- 3) Approve VTTM 19322, subject to the attached Findings and Conditions of Approval (Appendices A to C).

NOTE: Per State Law, for any improvements required prior to the recordation of a final map, the developer may instead enter into an agreement with the County of Orange guaranteeing all required improvements. Said agreement shall be accompanied by financial security.

**BACKGROUND AND EXISTING CONDITIONS:**

In November 2004, the County of Orange approved the Ranch Plan Planned Community, which encompasses approximately 22,815 acres located east of I-5, north and south of Ortega Highway at Antonio Parkway/La Pata Avenue, within the Fifth Supervisorial District. As approved, the Ranch Plan Planned Community comprises 75 percent permanent open space and allows for the development of 14,000 dwelling units and 5,200,000 square feet (SF) of non-residential uses in the remaining 25 percent. It is regulated by the Ranch Plan PC Program Text which addresses the unique characteristics of the property and a development plan for the transition to suburban uses occurring over a 25- to 30-year period.

The Master Area Plan and Subarea Plans for Planning Areas 3 and 4 were originally approved on February 25, 2015, by the Planning Commission (PA140072-PA140081) and revised administratively on May 22, 2017 (PA150047). On September 11, 2019, the Planning Commission approved amendments and revisions

## Subdivision Committee Draft Report – October 1, 2025

VTTM 19322 – RMV Subarea 3.5

Page 3 of 9

to the Master Area Plans and Subarea Plans for Planning Areas 3 and 4 (PA180030) which reflect the applicant's plan to develop Planning Area 3 in smaller phases. Administrative revisions to the Master Area Plan and Subarea Plans for Planning Areas 3 and 4 were approved in October 2022 (PA22-0067), October 2024 (PA24-0104) and most recently in May 2025 (MB24-0070), to adjust residential dwelling unit counts, non-residential square footage, and the locations of community facilities.

"A" Vesting Tentative Tract Map 17935 for Subarea Plan 3.5 was approved by the Subdivision Committee on October 16, 2024. The Final Tract Map 17935 was subsequently approved by the County of Orange Board of Supervisors on August 26, 2025, and recorded by the County Clerk-Recorder on September 11, 2025. Subarea 3.5 is currently being graded under issued permit GRD24-0045 and the street and storm drain improvement plan (STP25-0005) is under review by the County.

### Proposed Project


The applicant, Rancho Mission Viejo, is requesting approval of "B" Vesting Tentative Tract Map 19322 (VTTM 19322) to subdivide a 12.94-acre site within Planning Area 3.5 of the Ranch Plan Planned Community into 49 numbered lots for conventional single-family detached dwellings, 1 lettered lot for a private drive, 2 lettered lots for landscaping, and 11 lettered lots for sloped landscape areas. VTTM 19322 is one of seven "B" maps proposed for Planning Area 3, Subarea 3.5 of the Ranch Plan. The approval of the "A" Map – Final Map 17935 has established the outer boundaries for these B Maps, which further subdivide the land into smaller lots for the construction of housing, open space, streets, and other supporting facilities. Additional details of the proposed "B" map (Exhibit 2) are provided in the Discussion/Analysis section.


### **SURROUNDING LAND USE:**

Land uses immediately surrounding the project site include the following:

- North: Future Subarea 3.8
- South: Lamkin Lane, Existing Residential Tract 19152
- East: Future Residential Tracts 19321 & 19324
- West: Ranch Canyon/Lamkin Lane/Open Space/ Future Residential Tracts 19325 & 19326

Please refer to the General Vicinity Map (Exhibit 1) and the Project Site Map (Exhibit B on the following page).





**Exhibit 2 – Tentative Tract Map 19322**

## DISCUSSION/ANALYSIS:

### General Description

The proposed “B” VTTM 19322 subdivides a 12.94-acre site within Planning Area 3.5 of the Ranch Plan Planned Community into 49 numbered lots for conventional single-family detached dwellings and 14 lettered lots designated for a private drive, landscaping, and slope/landscape areas. General access to the tract will be provided via Gavilan Ridge, a public street, with secondary access provided via Radiant Way, a public street. The tract map has been designed to create individual residential lots fronting the internal main public residential street, Sunlit Way. The proposed residential lots will range in size from 6,165 to 8,643 square feet, and the tract will have a net density of 6.16 dwellings per acre.

The lettered lots will serve various uses. Lot A is designated for a private drive to provide access to Lots 48 and 49, Lots B and C are reserved for landscape lots, and Lots D through N are designated for slope and landscaping areas.

### Consistency Analysis:

Proposed “B” VTTM 19322 is consistent with:

- State Subdivision Map Act and County of Orange Subdivision Code and Manual.
- General Plan, Land Use Element: Suburban Residential. The proposed map is consistent with the Suburban Residential designation.



**Subdivision Committee Draft Report – October 1, 2025**

VTTM 19322 – RMV Subarea 3.5

Page 5 of 9

- c. Zoning: Planned Community. The proposed map is in conformance with the County of Orange Planned Community District regulations as regulated by the Ranch Plan Planned Community Text, statistical summary, and development maps.
- d. Area Plans: The proposed map is consistent with the PA3 Master Area Plan, Subarea Plan 3.5, and the PA3 & 4 Master Area and Subarea Plan Amendment and Addendum (PA180030). Additional administrative revisions affecting PA3 and Subareas were approved in 2022 (PA22-0067), 2024 (PA24-0104), and 2025 (PA24-0181 & MB24-0070).
- e. CEQA: The proposed map is consistent with Program EIR 589, which was certified on November 8, 2004; Addendum 1.0, approved on July 26, 2006; Addendum 1.1, approved on February 24, 2011; the Planning Area 2 Addendum, approved on March 27, 2013; and Addendum 3.1 approved on February 25, 2015.
- f. Alternative Development Standards: All previously approved Alternative Development Standards that are to be incorporated into the development of Subarea 3.5 are listed within the Note #30 on Sheet 1 of the proposed VTTM 19322.
- g. Regulation Compliance Matrix: Clearance of all applicable conditions of approval have been confirmed per the Ranch Plan Regulation Compliance Matrix.

Estimated Earthwork

The proposed estimated grading quantities for this map are substantially consistent with or less than the earthwork quantities described under previous approvals (i.e., Master Area Plan (PA3), Subarea Plan 3.5, Tract 17935, and related grading permit (GRD22-0016 and GRD24-0045). The proposed grading on this map has been addressed per CEQA document FEIR 589, together with Addendum 3.1.

Drainage:

The subject property is in the Ranch Plan Planned Community Runoff Management Plan (ROMP) Area. A Master Plan of Drainage (MPD) consistent with the latest version of the PA 3 and 4 ROMP has been established for the project site (Subarea 3.5). VTTM 19322 is located in Subarea 3.5 and is consistent with this MPD, however no MPD fees are required.

Recreation and Open Space:

The proposed map is not required to provide any improvements or dedications associated with the County Master Plan of Regional Recreation Facilities; Master Plan of Regional Riding and Hiking Trails; Resources Element (Open Space Component); or OCTA Strategic Plan for Bikeways.

- Master Plan of Regional Recreation Facilities - There are no regional park dedication requirements of the subject map.
- Master Plan of Regional Riding and Hiking Trails - There are no riding and hiking trail requirements of the subject map.
- Master Plan of Local Parks (Local Park Code) - The proposed map is required to provide park land in accordance with the Master Plan of Local Parks (Local Park Code). The Local Park Code requirement for the subject map VTTM 19322 is 0.39 net usable acres (0.008 ac/unit) of park land based upon a proposal to build 49 dwelling units at a gross residential density of 3.79 du/ac (49 du/12.94 ac). Said requirement can be satisfied by an allocation of parkland credit from Park Modification PM07-01, the Local Park Implementation Plan (LPIP) for the Ranch Plan P.C. originally approved March 14, 2007, 1st Amendment approved in June 2012, 2<sup>nd</sup> Amendment approved on

**Subdivision Committee Draft Report – October 1, 2025**

VTTM 19322 – RMV Subarea 3.5

Page 6 of 9

July 16, 2014, 3<sup>rd</sup> Amendment approved November 7, 2019, 4<sup>th</sup> Amendment approved December 6, 2023, and 5<sup>th</sup> Amendment approved September 17, 2025.

Per the Ranch Plan LPIP, the total parkland acreage requirement for the entire Ranch Plan Planned Community is 94.0 acres, based on 14,000 approved dwelling units and the anticipated proportion of single-family and multi-family units. Of the 94 acres required, 81.6 acres of creditable public parkland are anticipated in Planning Areas 3 and 4. For Subarea 3.5, the Ranch Plan LPIP does not indicate any requirements for public or private parkland. Therefore, there are no parkland dedication requirements applicable to VTTM19322.

- Resources Element - Open Space Component - There are no open space dedication requirements applicable to the subject map.
- OCTA Strategic Plan for Bikeways - There are no County-wide bikeways identified within the area of this map.

Public Services & Utilities

- Schools - This property is within the boundaries of the Capistrano Unified School District. The developer is subject to the provisions of Assembly Bill AB 2926 or other mitigating measures designed to provide for school facilities and/or funding, such as community facilities districts, as outlined by Mitigation Measure 4.15-5 of FEIR 589.
- Facilities Fees Programs - This project area is included within the Ranch Plan Planned Community Development Agreement DA04-01 which phases development commensurate with public services and facilities.
- Water/Sewer - This project is within the boundaries of the Santa Margarita Water District (SMWD). The SMWD stated in their Preliminary Water Sewer Letter, dated July 25, 2025, that SMWD will be capable of providing water and sewage disposal service to this development.
- Water Quality Control - This project will be required to operate in accordance with requirements prescribed by the California Regional Water Quality Control Board, San Diego Region, as outlined by Standard Conditions 4.5-3 thru 4.5-11 of FEIR 589.
- Fire Protection and Safety - Existing and proposed fire protection services will be providing an adequate level of fire protection services to this development. Additionally, this property is within the area covered by the approved Ranch Plan Fire Protection Program, which includes all applicable conditions of approval and regulations. A Fire Master Plan has been prepared for Subarea 3.5, which has been reviewed and approved by the Orange County Fire Authority on May 28, 2025.
- County Service Area (CSA) - This property is within the boundaries of County Service Area No. 26.

Traffic/Circulation

- Scenic Highway Corridors - There are no Scenic Highways applicable to this map.
- Access/Highways/Streets/Roads - Access to the site is via Gavilan Ridge and Radiant Way, proposed public streets. Internal tract access will be provided via in-tract public street Sunlit Way and a private drive.
- Major Thoroughfare and Bridge Fee Program - This project lies within the area of benefit of the Foothill/Eastern Transportation Corridor. The developer is required to pay Foothill/Eastern Major Thoroughfare and Bridge fees in accordance with the adopted program.

**Subdivision Committee Draft Report – October 1, 2025**

VTTM 19322 – RMV Subarea 3.5

Page 7 of 9

- Off-Site Fee Program – The project lies within the area of benefit of the South County Roadway Improvement Road Fee Program (SCRIP). The developer is required to pay SCRIP fees in accordance with the adopted program.

**Fire Master Plan**

The applicant has provided a copy of the Orange County Fire Authority (OCFA) Fire Master Plan, Service Request number 25000828, approved on May 28, 2025. OCFA has reviewed the proposed project and has concurred with the proposal. OCFA and Land Development will continue to coordinate necessary plan check reviews during the permitting and construction process to ensure VTTM 19322 is established in compliance with associated fire safety and fire protection requirements.

**Multiple Final Map Phasing**

As indicated on the Map under Note #22 of the title sheet VTTM 19322, the option of multiple final maps phasing has been requested as part of the approval of this Vesting Tentative Tract Map.

**ALTERNATIVE DEVELOPMENT STANDARDS:**

As allowed by General Regulation #25 of the Ranch Plan Planned Community Program Text, proposed Alternative Development Standards are intended to be incorporated into the development as listed within the “Notes” portion of the cover page of VTTM 19322. The following approved Ranch PC Alternative Development Standards (approved May 22, 2024) are proposed as part of VTTM 19322:

- A-1 36-Foot Double Loaded Streets (Up to 800 ADT)
- A-2a Residential Local Streets 30’ Wide (400 to 1,200 ADT)
- A-11 Curb Returns at Each Residential Driveway
- A-19 Cul-de-sac with Raised Landscape Median
- A-20 Alternative Neighborhood Sidewalk Detail- Curb-Separated Sidewalk
- A-39 Private Curb Core Outlet and Cleanout Detail
- A-40 Private Area Drain Connection to Catch Basin Inlet
- B-2 Intersection Sight Line Standards
- B-8 Corner Ramp Condition Typical Intersection
- B-9 Modified Color of Curb Ramp Detectable Warning Surface
- D-3 Reduced Age Qualified Parking
- D-4b Conventional Single Family Detached Dwellings Setbacks
- D-11 Residential Guest Parking
- G-4 Curb (and Gutter) Options on Private Streets, Private Drives & Alleys
- G-7 Reduced Local Depression on Private Streets
- G-8 Reduced Local Depression on Public Streets
- J-5 Class III NEV Route

**REFERRAL FOR COMMENT AND PUBLIC NOTICE:**

Copies of the vesting tentative tract map submittal package were distributed for review and comment to County staff and consultants, including Land Development, Traffic Engineering, Development Support, Survey, Operations & Maintenance, Building & Safety and the Orange County Fire Authority. Through a collaborative effort with County staff, the applicant adequately addressed all comments. As of the writing of this staff report, no further comments have been received from any County divisions.

**Subdivision Committee Draft Report – October 1, 2025**

VTTM 19322 – RMV Subarea 3.5

Page 8 of 9

A Notice of Public Hearing was mailed to all property owners of record within 300 feet of the subject site on September 19, 2025. Additionally, notices were posted at the project site, at the County Administrations North (CAN) Building, on the Orange County Public Works website and in the local newspaper “OC Reporter,” as required by established public hearing posting procedures. No public comments have been received to date.

**CEQA COMPLIANCE:**

The proposed project is covered by previous CEQA documentation, which includes Final Program EIR 589, certified on November 8, 2004; Addendum 1.0, approved on July 26, 2006; Addendum 1.1, approved on February 24, 2011; the Planning Area 2 Addendum, approved on March 27, 2013; and Addendum 3.1, approved on February 25, 2015. This finding is appropriate and complies with the intent of CEQA, pursuant to the Orange County 2020 Local CEQA Procedures Manual, Section 13.1 for projects where a previous environmental document (i.e., Program EIR 589) is already in place. Further CEQA evaluation and clearances are not required for the proposed VTTM 19322.

**CONCLUSION:**

Based on the review of the subject submittal, staff supports approval of the applicant’s proposed “B” Vesting Tentative Tract Map 19322 (VTTM 19322) pursuant to the Orange County Subdivision Code, Orange County Codified Ordinances (OCCO) Subarticle 5 (Processing Procedures for Tentative Maps).


Submitted by:

Signed by:

  
5920734D9EEE4A4...  
Robert Zegarra, Contract Planner  
Land Development

Concurred by,

DocuSigned by:

  
9EEAFDF5701C43D...  
Bea Bea Jimenez, Division Manager  
Land Development**CERTIFICATION:**

I hereby certify that the Tentative Tract Map 19322 was approved by the Orange County Subdivision Committee on October 1, 2025, per the findings in Appendix A and the conditions in Appendix B.

---

Lily Sandberg,  
Subdivision Committee Chairperson

**APPENDICES:**

- A. Recommended Findings
- B. Recommended Conditions of Approval
- C. Ranch Plan Regulation Compliance Matrix - “B” Map Items



**Subdivision Committee Draft Report – October 1, 2025**

VTTM 19322 – RMV Subarea 3.5

Page 9 of 9

**ATTACHMENTS:**

1. Applicant's Letter of Proposal
2. Will Serve Letter
3. Project Plans and Fire Master Plan

**APPEAL PROCEDURE:**

Any interested person may appeal the decision of the Subdivision Committee on this application to the Orange County Planning Commission within 10 calendar days of the decision upon submittal of required documents and a filing fee of \$500.00 filed at the Development Processing Center, 601 N. Ross St., Santa Ana. If you challenge the action taken on this proposal in court, you may be limited to raising only those issues you or someone else raised in written correspondence delivered to OC Development Services.

# APPENDIX A



## Appendix A Findings

### VTTM 19322

1	<b>EIR AND ADDENDUM</b>	<b>VTTM 19322 (Custom)</b>
That the decision-maker has considered Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 2006; Addendum 1.1 (PA110002-PA110006) approved February 24, 2011; the Planning Area 2 Addendum (PA130001-PA130004 and PA130006) approved on March 27, 2013; Addendum 3.1 (PA140072-81) approved February 25, 2015; and the Planning Area 3 & 4 Amendment and Addendum (PA180030) approved September 11, 2019 prior to project approval. The addendums are approved for the proposed project based upon the following findings:		
a. Together, these documents are adequate to satisfy the requirements of CEQA by the decision-maker;		
b. The additions, clarifications and/or changes to the original document caused by the Addendums, do not raise new significant issues which were not addressed by the EIR and none of the conditions described in CEQA Guidelines Section 15162 applies; and		
c. The consideration of the EIR and approval of the Addendums for the proposed project reflect the independent judgment of the Lead Agency.		
2	<b>ENVIRONMENTAL MONITORING</b>	<b>VTTM 19322 (Custom)</b>
That the monitoring requirements of Public Resources Code Section 21081.6 (AB 3180) will be considered as having been met in that the design of the subject project, the satisfaction of the requirements of the County's building, grading, fire, and other codes and ordinances and the satisfaction of the conditions of approval applied to the project will implement the mitigation measures contained in EIR No. 589, Addendum 1 (PA06-0023), Addendum 1.1 (PA110003-0006), the Planning Area 2 Addendum (PA130001-0004 and PA130006), Addendum 3.1 (PA140072-81), and the Planning Area 3 & 4 Amendment and Addendum (PA180030).		
3	<b>GENERAL PLAN CONSISTENCY</b>	<b>VTTM 19322</b>
That the proposed map is consistent with the Orange County General Plan.		
4	<b>DESIGN &amp; IMPROVEMENT</b>	<b>VTTM 19322</b>
That the design and improvement of the proposed subdivision are consistent with the Orange County General Plan.		
5	<b>DEVELOPMENT TYPE</b>	<b>VTTM 19322</b>
That the proposed site is physically suitable for the proposed type of development.		
6	<b>DEVELOPMENT DENSITY</b>	<b>VTTM 19322</b>
That the proposed site is physically suitable for the proposed density of development.		
7	<b>ENVIRONMENTAL DAMAGE</b>	<b>VTTM 19322</b>
That the design of the subdivision or the proposed improvements are not likely to cause substantial environmental damage or substantial and avoidable injury to fish or wildlife or their habitat.		
8	<b>PUBLIC HEALTH</b>	<b>VTTM 19322</b>
That the design of the subdivision and the type of improvements proposed are not likely to cause serious public health problems.		
9	<b>PUBLIC EASEMENTS</b>	<b>VTTM 19322</b>
That the design of the subdivision and the type of improvements proposed will not conflict with easements of record or established by court judgment acquired by the public-at-large for access through or use of property within the proposed subdivision.		
10	<b>SUBDIVISION / ZONING CODE CONSISTENCY</b>	<b>VTTM 19322</b>
That the proposed subdivision complies with the requirements set forth in the Orange County Subdivision Code and the Orange County Zoning Code.		
11	<b>ZONING CONSISTENCY</b>	<b>VTTM 19322</b>
That the design and improvement of the proposed subdivision are suitable for the uses proposed, and the subdivision can be developed in compliance with applicable zoning regulations pursuant to Section 7-9-254 of the Subdivision Code.		
12	<b>SEWER SYSTEM</b>	<b>VTTM 19322 (Custom)</b>
That the discharge of waste from the proposed subdivision into the existing sewer system of the Water District will not result in violations of existing requirements prescribed by the California Regional Water Quality Control Board, San Diego Region.		
13	<b>NATURAL HEATING AND COOLING</b>	<b>VTTM 19322</b>
That the design of the subdivision and its improvements do provide, to the extent feasible, for future passive or natural heating or cooling opportunities as specified in Section 66473.1 of the Government Code (Subdivision Map Act).		
14	<b>FEE PROGRAMS</b>	<b>VTTM 19322</b>
That the following determinations apply to fees required by Sections 7-9-700 through 713, Codified Ordinances of Orange County:		
A. Purpose of fees: Fire protection, paramedic, law enforcement, library, and general County services.		
B. Use of fees: Construction of new fire station, sheriff substation, library, and general County facilities in newly developing areas which have inadequate service.		
C. Relationship between use of fees and type of development: Dwelling units and commercial/industrial structures and their occupants require fire protection, paramedic, law enforcement, library, and general County services.		
D. Relationship between need for facilities and type of project: Project is located in newly developing area which has inadequate fire protection, paramedic, library services, and sheriff substation and general County facilities.		
E. Relationship between amount of fees and cost of the portion of the facilities attributable to the development: Fees represent project's pro rata share of the cost of the fire station, sheriff substation, library, and general County facilities.		

15	<b>EXPIRATION OF MAPS</b>	<b>VTTM 19322</b>
That because of participation in fee programs for off-site improvements, this project will qualify for consideration under Section 66452.6 of the Subdivision Map Act.		
16	<b>LOCAL PARK CODE</b>	<b>VTTM 19322 (Custom)</b>
That the Local Park Code requirement can be met by an allocation of park lands credit from PM 07-01, the park implementation plan for the Ranch Plan Planned Community.		
17	<b>DEVELOPMENT AGREEMENT</b>	<b>VTTM 19322</b>
That the Development Agreement contains provisions requiring developer participation in fee programs, facility construction and development phasing and is therefore in compliance with the adopted Growth Management Element in terms of public services and facilities being made available to accommodate development.		
18	<b>APPEAL OF EXACTIONS</b>	<b>VTTM 19322</b>
That the applicant is hereby provided notice that the fees, dedications, reservations or other exactions imposed on this project are as described in this approval as well as the reports and actions accompanying this approval and that the 90-day approval period in which the applicant may protest pursuant to Government Code Section 66020 has begun.		



# APPENDIX B



## Appendix B Conditions of Approval VTTM 19322

### 1 RANCH PLAN REGULATION COMPLIANCE MATRIX VTTM 19322 (Custom)

The applicant shall comply with all applicable requirements of the Ranch Plan Regulation Compliance Matrix: to the satisfaction of the appropriate decision maker listed in each applicable Regulation Compliance Matrix item. The applicable requirements are listed below and attached as Appendix C:

#### a. Prior to Recordation:

139: EIR 589 Mitigation Measure 4.9-27 – Invasive Plants CC&R Prohibition  
 524: EIR 589 Stand. Cond. 4.4-3 (G04) – Off-site Letter of Consent (if necessary)  
 527 & 527.1: EIR 589 Standard Condition 4.5-1 (D01a) – Drainage Study  
 528 & 528.1: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements  
 529: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements  
 532: EIR 589 Standard Condition 4.5-4 (D04b) – Master Plan of Drainage  
 533: EIR 589 Standard Condition 4.5-5 (D06b) – Subordination of Easements  
 534: EIR 589 Standard Condition 4.5-5 (D06b) – SMWD Easements  
 535: EIR 589 Standard Condition 4.5-6 (D07b) – Regional Facility Improvements  
 537 & 537.1: EIR 589 St. Cond. 4.5-8 (WQ01) – Water Quality Management Plan (WQMP)  
 538: EIR 589 St. Cond. 4.5-8 (WQ03) – Water Quality Management Plan (WQMP)  
 544: EIR 589 Standard Condition 4.6-2 (T01) – Vehicular Access Rights  
 545: EIR 589 Standard Condition 4.6-3 (T02) – Private Street Improvements  
 546: 546.1: 546.2 & 546.3: SC 4.6-4: (T04) – Street Improvements  
 549: EIR 589 Standard Condition 4.6-7 (T08) – Traffic Signal Conduit  
 550, 550.1, 550.2 & 550.3: EIR 589 Stand. Cond. 4.6-8 (T12) – Internal Circulation  
 551: EIR 589 Standard Condition 4.6-9 (T13b) – Traffic Signal Maintenance Easement  
 552: EIR 589 Standard Condition 4.6-10 (T14b) – Traffic Signal Installation  
 559 & 559.1: EIR 589 Standard Condition 4.8-3 (N01) – Sound Attenuation  
 589.1: EIR 589 Standard Condition 4.15-1 – Water Improvement Plans  
 597: EIR 589 Standard Condition 4.15-9 – Capistrano Unified School District fees  
 619: Ranch Plan Fire Prot. Program Cond. 4 – OCFA Administrative Approval

#### b. Prior to Approval of Site Development Permit

109: EIR 589 Mitigation Measure 4.7-3 – Shade Trees in Parking Lot Design  
 110: EIR 589 Mitigation Measure 4.7-3 – Use of Light-Colored Roof Materials

#### c. Prior to Issuance of Grading Permits

521: EIR 589 Standard Condition 4.4-1 (G01) – Geotechnical report  
 522: EIR 589 Standard Condition 4.4-2 (G02) – Conformance with TT Map  
 523: EIR 589 Standard Condition 4.4-2 (G02) – Revised TT Map (if necessary)  
 524: EIR 589 Stand. Cond. 4.4-3 (G04) – Off-site Letter of Consent (if necessary)  
 525: EIR 589 Standard Condition 4.4-4 (G09) – Consistency with Planning Approval  
 527 & 527.1: EIR 589 Standard Condition 4.5-1 (D01a) – Drainage Study  
 528 & 528.1: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements  
 530 & 530.1: EIR 589 Standard Condition 4.5-3 (D02b) – Drainage Improvements  
 537 & 537.1: EIR 589 St. Cond. 4.5-8 (WQ01) – Water Quality Management Plan (WQMP)  
 538: EIR 589 St. Cond. 4.5-8 (WQ03) – Water Quality Management Plan (WQMP)  
 540: EIR 589 St. Cond. 4.5-10 (WQ04) – Stormwater Pollution Prevention (SWPPP)  
 541: EIR 589 St. Cond. 4.5-11 (WQ05) – Erosion and Sediment Control Plan  
 548: EIR 589 Standard Condition 4.6-6 (T07) – Sight Distance  
 555, 555.1 through 555.5: EIR 589 Standard Condition 4.7-1 – Fugitive Dust  
 556, 556.1, 556.2 & 556.3: EIR 589 Standard Condition 4.7-2 – Emission Control  
 557: EIR 589 Standard Condition 4.8-1 (N10) – Hours of Construction  
 558, 558.1, 558.2, 558.3 & 558.4: EIR 589 St. Condition. 4.8-2 (N10) – Construction Noise  
 559 & 559.1: EIR 589 Standard Condition 4.8-3 (N01) – Sound Attenuation  
 567: EIR 589 Standard Condition 4.10-2 (LA02b) – Private Area Landscaping  
 571: EIR 589 Standard Condition 4.11-1 (A04) – Archaeology Grading Observation and Salvage  
 574: EIR 589 Standard Condition 4.11-2 (A07) – Paleontology Resource Surveillance  
 589: EIR 589 Standard Condition 4.14-2 – Hazardous Materials  
 616: Ranch Plan Fire Prot. Program Cond. 3.d. – Precise Fuel Modification Plan

#### d. Prior to Precise Fuel Modification Plans:

138: EIR 589 Mitigation Measure 4.9-27 – Invasive Plants and Fuel Modification

#### e. Prior to Issuance of Building Permit:

111: EIR 589 Mitigation Measure 4.7-3 – Use of Light-Colored Roof Materials  
 140: EIR 589 Mitigation Measure 4.9-28 – Open Space habitat, light shields  
 206: EIR 589 Mitigation Measure 4.15-5 – Capistrano Unified School District fees  
 526: EIR 589 Standard Condition 4.4-5 – Compliance with Code  
 537 & 537.1: EIR 589 St. Cond. 4.5-8 (WQ01) – Water Quality Management Plan (WQMP)  
 538: EIR 589 St. Cond. 4.5-8 (WQ03) – Water Quality Management Plan (WQMP)  
 540: EIR 589 St. Cond. 4.5-10 (WQ04) – Stormwater Pollution Prevention (SWPPP)  
 541: EIR 589 St. Cond. 4.5-11 (WQ05) – Erosion and Sediment Control Plan  
 547: EIR 589 Standard Condition 4.6-5 (T05) – Major Thoroughfare & Bridge Fees  
 550, 550.1, 550.2 & 550.4: EIR 589 Standard Condition 4.6-8 (T12) – Internal Circulation  
 559.2 & 559.3: EIR 589 Standard Condition 4.8-3 (N01) – Sound Attenuation  
 564 & 564.1: EIR 589 Standard Condition 4.10-1 (LA01b) – Public Area Landscaping  
 570: EIR 589 Standard Condition 4.10-3 (LG01) – Light and Glare

589: EIR 589 Standard Condition 4.14-2 – Hazardous Materials  
617: Ranch Plan Fire Prot. Program Cond. 3.e. – Vegetation Clearance

f. Prior to Combustible Construction:  
609: Ranch Plan Fire Prot. Program Cond. 2.d. – Emergency Access & Water Supply

g. During Construction:  
197: EIR 589 Mitigation Measure 4.14-13 – ESA Remedial Measures

h. Prior to Certificates of Occupancy:  
529: EIR 589 Standard Condition 4.5-2 (D02a) – Drainage Improvements  
531: EIR 589 Standard Condition 4.5-3 (D02b) – Drainage Improvements  
539, 539.1 & 539.2: EIR 589 Standard Condition 4.5-9 (WQ03) – Compliance with Water Quality Management Plan (WQMP)  
563: EIR 589 Standard Condition 4.8-7 (N12) – Transportation Corridor Notification  
565 & 566: EIR 589 Standard Condition 4.10-1 (LA01b) – Public Area Landscaping  
568 & 569: EIR 589 Standard Condition 4.10-2 (LA02b) – Private Area Landscaping  
618: Ranch Plan Fire Prot. Program Cond. 3.f. - Fuel Modification Zones

i. Prior to Release of Grading Bond:  
572 & 573: EIR 589 Standard Condition 4.11-1 (A04) – Archaeology Grading Observation and Salvage  
575 & 576: EIR 589 Standard Condition 4.11-2 (A07) – Paleontology Resource Surveillance

---

**2 WATER QUALITY MANAGEMENT PLAN VTTM 19322**

Prior to the issuance of any grading or building permits, the applicant shall submit for review and approval by the Manager, Permit Services, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. The applicant shall utilize the Orange County Drainage Area Management Plan (DAMP), Model WQMP, and Technical Guidance Manual for reference, and the County's WQMP template for submittal. This WQMP shall include the following:

- Detailed site and project description
- Potential stormwater pollutants
- Post-development drainage characteristics
- Low Impact Development (LID) BMP selection and analysis
- Structural and Non-Structural source control BMPs
- Site design and drainage plan (BMP Exhibit)
- GIS coordinates for all LID and Treatment Control BMPs
- Operation and Maintenance (O&M) Plan that (1) describes the long-term operation and maintenance requirements for BMPs identified in the BMP Exhibit; (2) identifies the entity that will be responsible for long-term operation and maintenance of the referenced BMPs; and (3) describes the mechanism for funding the long-term operation and maintenance of the referenced BMPs

The BMP Exhibit from the approved WQMP shall be included as a sheet in all plan sets submitted for plan check and all BMPs shall be depicted on these plans. Grading and building plans must be consistent with the approved BMP exhibit.

---

**3 BEST MANAGEMENT PRACTICES VTTM 19322 (Custom)**

Prior to issuance of a building permit, the off-site regional Best Management Practices (BMPs) relied upon by this project (e.g., basins, swales, etc.) must be built and/or installed, and operational. The location and operation of these regional BMPs must be in compliance with the Final Project-Specific WQMP for the regional BMP(s). The location and operation of the regional BMP(s) must be demonstrated to the satisfaction of the Manager, Grading and Building Plan Check.

---

**4. COMPLIANCE WITH THE NPDES IMPLEMENTATION VTTM 19322 PROGRAM**

Prior to the issuance of a certificate of use and occupancy, the applicant shall demonstrate compliance with the County's NPDES Implementation Program in a manner meeting the satisfaction of the Manager, OC Inspection, including:

- Demonstrate that all structural Best Management Practices (BMPs) described in the BMP Exhibit from the project's approved WQMP have been implemented, constructed and installed in conformance with approved plans and specifications
- Demonstrate that the applicant has complied with all non-structural BMPs described in the project's WQMP
- Submit for review and approval an Operations and Maintenance (O&M) Plan for all structural BMPs (the O&M Plan shall become an attachment to the WQMP.
- Demonstrate that copies of the project's approved WQMP (with attached O&M Plan) are available for each of the initial occupants.
- Agree to pay for a Special Investigation from the County of Orange for a date twelve (12) months after the issuance of a Certificate of Use and Occupancy for the project to verify compliance with the approved WQMP and O&M Plan
- Demonstrate that the applicant has RECORDED one of the following:
  1. The CC&R's (that must include the approved WQMP and O&M Plan) for the project's Homeowner's Association.
  2. A water quality implementation agreement that has the approved WQMP and O&M Plan attached; or
  3. The final approved Water Quality Management Plan (WQMP) and Operations and Maintenance (O&M) Plan. (Appendix C - Items 539, 539.1, 539.2)

---

**5 INDEMNIFICATION VTTM 19322 (Custom)**

Applicant shall defend with counsel approved by the County of Orange in writing, indemnify and hold harmless the County of Orange, its officers, agents and employees from any claim, action or proceeding against the County, its officers, agents or employees to attack, set aside, void, or annul any approval of the application or related decision, or the adoption of any environmental documents, findings or other environmental determination, by the County of Orange, its Board of Supervisors, Planning Commission, Zoning Administrator, Director of OC Public Works, or Director of Planning concerning this application. The County may, at its sole discretion, participate in the defense of any action, but such participation shall not relieve applicant of his/her obligations under this condition. Applicant shall reimburse the County for any court costs and attorney's fees that the County may be required to pay as a result of such action. The County shall promptly notify the applicant of any such claim, action or proceeding.

---

**6 BUYER NOTIFICATION MAP VTTM 19322 (Custom)**

Prior to the issuance of any building permits for residential construction, the developer RMV Community Development, LLC, shall prepare a map denoting the existing and proposed land uses, arterial highways, and public facilities within the surrounding area for the approval of the Manager, OC Planning. The map content, display, and distribution shall be in accordance with the Buyer Notification Program guidelines listed in Board of Supervisors Resolution 82-1368 and as amended.

# APPENDIX C



RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

Appendix C

PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
<b>a. Prior to Recordation</b>												
139	137-138 (EIR 589, MM 4.9-27)	EIR 589	MM 4.9-27 (cont.)	Prior to the recordation of a map for tract adjacent to the RMV Open Space	Biological Resources	CC&Rs, California Exotic Pest Plant Council	Invasive Plants CC&R Prohibition	b. Prior to the recordation of a map for a tract adjacent to the RMV Open Space, the County of Orange shall verify that the CC&Rs contain language prohibiting the planting of plants identified by the California Exotic Pest Plant Council as an invasive risk in Southern California in private landscaped areas.	<del>Director, PDS</del> <b>Director, OC Planning</b>	Provide letter stating that CC&Rs contain language prohibiting the planting of plants on most current California Invasive Plant Inventory	To be cleared for entire Planned Community, upon providing <a href="#">RMV CC&amp;R summary letter [Hyperlink #13]</a> stating CC&Rs contain language prohibiting the planting of plants on most current <a href="#">California Invasive Plant Inventory (www.cal-ipc.org)</a> in private landscape areas. Only applies to recordation of tract maps that include lots located immediately adjacent to RMV Open Space	Each PA
524		EIR 589	SC 4.4-3	Prior to the recordation of a subdivision map or prior to issuance of a Grading Permit, whichever comes first	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to the recordation of a subdivision map or prior to the issuance of any grading permit, whichever comes first, and if determined necessary by the County of Orange Manager, Subdivision and Grading, the applicant shall record a letter of consent from the affected property owners permitting off-site grading, cross lot drainage, drainage diversions and/or unnatural concentrations. The applicant shall obtain approval of the form of the letter of consent from the Manager, Subdivision and Grading Services before recordation of the letter. (County Standard Condition G04)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Recordation of a letter of consent from affected property owners if determined necessary by County of Orange Director of Planning & Development Services		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
527		EIR 589	SC 4.5-1	Prior to recordation of a Subdivision Map or Issuance of a Grading Permit, whichever comes first	Drainage Study:		Drainage Study:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the following drainage studies shall be submitted to and approved by the Manager, Subdivision and Grading: (County Standard Condition D01a)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory of drainage study		Each PA
527.1		EIR 589	SC 4.5-1 (cont.)	See above	Drainage Study (cont.):		Drainage Study (cont.):	A. A drainage study of the project including diversions, off-site areas that drain onto and/or through the project, and justification of any diversions; and B. When applicable, a drainage study evidencing that proposed drainage patterns will not overload existing storm drains; and C. Detailed drainage studies indicating how the project grading, in conjunction with the drainage conveyance systems including applicable swales, channels, street flows, catch basins, storm drains, and flood water retarding, will allow building pads to be safe from inundation from rainfall runoff which may be expected from all storms up to and including the theoretical 100-year flood. (County Standard Condition D01a)	See above	See above		Each PA
528		EIR 589	SC 4.5-2	Prior to recordation of a Subdivision Map or Issuance of a Grading Permit, whichever comes first	Drainage Improvements:		Drainage Improvements:	A. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the applicant shall in a manner meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition D02a)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Approval of storm drain drainage plans and offer(s) of dedication, if necessary		Each PA
528.1		EIR 589	SC 4.5-2 (cont.)	See above	Drainage Improvements (cont.):		Drainage Improvements (cont.):	1) Design provisions for surface drainage; 2) Design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and 3) Dedicate the associated easements to the County of Orange, if determined necessary. (County Standard Condition D02a)	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
529		EIR 589	SC 4.5-2 (cont.)	Prior to recordation of a Subdivision Map or Issuance of a Certificate of Use and Occupancy, whichever comes first	Drainage Improvements (cont.):		Drainage Improvements (cont.):	B. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any certificates of use and occupancy, whichever occurs first, said improvements shall be constructed in a manner meeting the approval of the Manager, Construction. (County Standard Condition D02a)	<del>County of Orange</del> <del>Manager of Inspection,</del> <b>Manager, OC Inspection Division</b>	Verification of construction of drainage improvement		Each PA
532		EIR 589	SC 4.5-4	Prior to the recordation of a Subdivision Map (except maps for financing and conveyance purposes only)	Master Plan of Drainage:		Master Plan of Drainage:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only), the subdivider shall participate in the applicable Master Plan of Drainage in a manner meeting the approval of the Manager, Subdivision and Grading, including payment of fees and the construction (or provide evidence of financial security, such as bonding) of the necessary facilities. (County Standard Condition D04b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Verification of participation in Master Plan of Drainage (fees and/or improvements)	See guidance above related to Item No. 30.	Each PA
533		EIR 589	SC 4.5-5	Prior to the recordation of a Subdivision Map	Subordination of Easements:		Subordination of Easements:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only), the subdivider shall not grant any easements over any property subject to a requirement of dedication or irrevocable offer to the County of Orange or the Orange County Flood Control District, unless such easements are expressly made subordinate to the easements to be offered for dedication to the County. Prior to granting any of said easements, the subdivider shall furnish a copy of the proposed easement to the Manager, Subdivision and Grading, for review and approval. (County Standard Condition D06b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b> (Orange County Flood Control District and Santa Margarita Water District)	Verification that any granted easements are subordinate to easements offered to County and provision of copy of said easement(s)	Except in those cases where the County of Orange and the public entity grantee have previously mutually agreed upon conditions to coexist within the easement area.	Each PA

RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

Appendix C

PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
534		EIR 589	SC 4.5-5 (cont.)	See above	Subordination of Easements (cont.):		Subordination of Easements (cont.):	The Santa Margarita Water District would restore other improvements or facilities located within the easement, if it has consented to the location of such improvements or facilities to the extent that the exercise of its rights in connecting with the easement impacts other improvements of facilities located within the easement; however, in no event shall Santa Margarita Water District be responsible for the cost of relocating its facilities in event of conflicts with such improvements or facilities. (County Standard Condition D06b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services</del> <b>Director, OC Planning</b> (Orange County Flood Control District and Santa Margarita Water District)	See above	<a href="#">Except in those cases where the County of Orange and the public entity grantee have previously mutually agreed upon conditions to coexist within the easement area.</a>	Each PA
535		EIR 589	SC 4.5-6	Prior to <a href="#">County of Orange acceptance of improvements as identified by separate agreement the recordation of a Subdivision Map</a>	Regional Facility Improvements:		Regional Facility Improvements:	Prior to County of Orange acceptance of improvements as identified by separate agreement the recordation of a subdivision map, the applicant shall improve Regional Facility _____ by the construction (or evidence of financial security, such as bonding) of _____, an IOD shall be recorded offering said improvements and dedicate right-of-way to the Orange County Flood Control District in a manner meeting the approval of the Manager, Subdivision and Grading. County of Orange to accept IOD upon satisfactory completion of improvements. (County Standard Condition D07b, modified)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services</del> <b>Director, OC Planning</b> (Orange County Flood Control District and Santa Margarita Water District)	Verification of construction and/or offer(s) of dedication for flood control improvements		Each PA

RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

Appendix C

PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
537		EIR 589	SC 4.5-8	Prior to the recordation of a Subdivision Map or the issuance of any Grading or Building Permit, whichever comes first	Water Quality Management Plan:		Water Quality Management Plan:	Prior to the recordation of any final subdivision map (except those maps for financing or conveyance purposes only) or the issuance of any grading or building permit (whichever comes first), the applicant shall submit for review and approval by the Manager, Inspection Services Division, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. This WQMP shall identify, at a minimum, the routine structural and non-structural measures specified in the current Drainage Area Management Plan (DAMP). The WQMP may include one or more of the following: (County Standard Condition WQ01)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory Water Quality Management Plan		Each PA
537.1		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	<ul style="list-style-type: none"> <li>• Discuss regional water quality and/or watershed programs (if available for the project);</li> <li>• Address Site Design BMPs (as applicable) such as minimizing impervious areas, maximizing permeability, minimizing directly connected impervious areas, creating reduced or "zero discharge" areas, and conserving natural areas;</li> <li>• Include the applicable Routine Source Control BMPs as defined in the DAMP.</li> </ul> (County Standard Condition WQ01)	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
538		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate how surface runoff and subsurface drainage shall be managed and directed to the nearest acceptable drainage facility (as applicable), via sump pumps if necessary. (Standard Condition of Approval, WQ03)	See above	See above		Each PA
544		EIR 589	SC 4.6-2	Prior to the recordation of a Subdivision Map	Vehicular Access Rights:		Vehicular Access Rights:	Prior to the recordation of a subdivision map, the subdivider shall place notes on the final map which release and relinquish vehicular access rights to all arterial highways to the County of Orange, except for access locations approved by the County of Orange, in a manner meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T01)	<del>County of Orange</del> Director of Planning & Development Services, <b>Director, OC Planning</b>	Verification of notes on the final map which release and relinquish vehicular access rights to all arterial highways to the County of Orange except for access locations approved by the County of Orange	Note shall state: "Rancho Mission Viejo or assigns hereby release and relinquish vehicular access rights to all arterial highways to the County of Orange, except for access locations approved by the County of Orange"	Each PA
545		EIR 589	SC 4.6-3	Prior to the recordation of a Subdivision Map	<u>Private</u> Street Improvements:		<u>Private</u> Street Improvements:	Prior to the recordation of a subdivision map, the subdivider shall place a note on the map, in a manner that meets the approval of the Manager, Subdivision and Grading Services, that states: "The private streets constructed within this map shall be owned, operated and maintained by the developer, successors or assigns. The County of Orange shall have no responsibility therefore unless pursuant to appropriate sections of the Streets and Highways Code of the State of California, the said private streets have been accepted into the County Road System by appropriate resolution of the Orange County Board of Supervisors. (County Standard Condition T02)	<del>County of Orange</del> Director of Planning & Development Services, <b>Director, OC Planning</b>	Verification of a note on the Subdivision Map	Note shall make statement listed in quotations in condition.	Each PA
546		EIR 589	SC 4.6-4	Prior to the recordation of a Subdivision Map	Street Improvements <del>(cont.)</del> :		Street Improvements <del>(cont.)</del> :	Prior to the recordation of a subdivision map, the subdivider shall design and construct <del>(or provide evidence of financial security, such as bonding)</del> the following improvements in accordance with plans and specifications meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition T04)	<del>County of Orange</del> Director of Planning & Development Services, <b>Director, OC Planning</b>	Submittal of satisfactory improvements and utility plans with verification of subsequent construction/in stallation of improvements	If applicable, bonding may substitute for construction of each of the required improvements.	Each PA
546.1		EIR 589	SC 4.6-4 (cont.)	See above	Street Improvements (cont.):		Street Improvements (cont.):	A. Streets, bus stops, on-road bicycle trails, street names, signs, striping and stenciling. (County Standard Condition T04)	See above	See above	See above	Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
546.2		EIR 589	SC 4.6-4 (cont.)	See above	Street Improvements (cont.):		Street Improvements (cont.):	B. The water distribution system and appurtenances shall also conform to the applicable laws and adopted regulations enforced by the County Fire Chief. (County Standard Condition T04)	See above	See above	<a href="#">See above</a>	Each PA
546.3		EIR 589	SC 4.6-4 (cont.)	See above	Street Improvements (cont.):		Street Improvements (cont.):	C. Underground utilities (including gas, cable, electrical and telephone), streetlights, and mailboxes. (County Standard Condition T04)	See above	See above	<a href="#">See above</a>	Each PA
549		EIR 589	SC 4.6-7	Prior to the recordation of a Subdivision Map	Traffic Signal Conduit:		Traffic Signal Conduit:	Prior to the recordation of a subdivision map, the subdivider shall install <a href="#">(or provide evidence of financial security, such as bonding, that)</a> all underground traffic signal conduits (e.g., signals, phones, power, loop detectors, etc.) and other appurtenances (e.g., pull boxes, etc.) needed for future traffic signal construction, and for future interconnection with adjacent intersections, all in accordance with plans and specifications meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T08)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Approved traffic signal plans with verification of subsequent installation	<a href="#">If applicable, bonding may substitute for construction of each of the required improvements.</a>	Each PA
550		EIR 589	SC 4.6-8	Prior to the recordation of a Subdivision Map or prior to the issuance of Building Permits, whichever occurs first	Internal Circulation:		Internal Circulation:	A. Prior to the recordation of a subdivision map or the issuance of any building permits, whichever occurs first, the subdivider shall provide plans and specifications meeting the approval of the Manager, Subdivision and Grading, for the design of the following improvements: (County Standard Condition T12)	<del>County of Orange Director of Planning &amp; Development Services,</del>	Submittal of satisfactory street improvement plans		Each PA
550.1		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation (cont.):		Internal Circulation (cont.):	1) Internal street common private drive system. (County Standard Condition T12)	See above	See above		Each PA
550.2		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation (cont.):		Internal Circulation (cont.):	2) Entrance to the site to emphasize that the development is private by use of signs and other features. (Standard Condition of Approval T12)	See above	See above		Each PA
550.3		EIR 589	SC 4.6-8 (cont.)	Prior to the recordation of Subdivision Map.	Internal Circulation (cont.):		Internal Circulation (cont.):	B. Prior to the recordation of a subdivision map, the applicant shall construct <a href="#">(or provide evidence of financial security, such as bonding)</a> the above improvements in a manner meeting the approval of the Manager, Construction. (County Standard Condition T12)	<del>County of Orange Manager of Inspection,</del> <b>Manager, OC Inspection Division</b>	Verification of improvements' construction in SC 4.6-8A	<a href="#">If applicable, bonding may substitute for construction of each of the required improvements.</a>	Each PA

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
551		EIR 589	SC 4.6-9	Prior to the recordation of a Subdivision Map	Traffic Signal Maintenance Easement:		Traffic Signal Maintenance Easement:	Prior to the recordation of a subdivision map, the subdivider shall dedicate a signal maintenance easement to the County of Orange at the project site access, in a manner meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T13b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of offer(s) of dedication for signal maintenance easement(s)		Each PA



## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
552		EIR 589	SC 4.6-10	Prior to the recordation of a Subdivision Map	Traffic Signal Installation:		Traffic Signal Installation:	Prior to the recordation of a subdivision map, the subdivider shall design and construct/provide a cash deposit of ___ % of the cost of / /enter into an agreement with the County of Orange, accompanied by financial security, for the cost of ___ % of) a traffic signal at the intersection of ___ and ___, in a manner meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T14b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Verification of approved street improvement plans with subsequent installation of improvements or enter into agreement with County for construction (with appropriate financial security)	<u>If applicable, bonding may substitute for construction of each of the required improvements.</u>	Each PA
559		EIR 589	SC 4.8-3	See below	Sound Attenuation:		Sound Attenuation:	The applicant shall sound attenuate all residential lots and dwellings against present and projected noise (which shall be the sum of all noise impacting the project) so that the composite interior standard of 45 dBA CNEL for habitable rooms and a source specific exterior standard of 65 dBA CNEL for outdoor living areas is not exceeded. The applicant shall provide a report prepared by a County-certified acoustical consultant, which demonstrates that these standards will be satisfied in a manner consistent with Zoning Code Section 7-9-137.5, as follows: (County Standard Condition N01)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services and</del> <del>County of Orange</del> <del>Manager of Building Permits Services,</del> <b>Director, OC Planning and Manager, Permit Services</b> (Building Plan Check)	Submittal of satisfactory acoustical analysis	<u>Staff may determine that no attenuation is necessary, and no action is required (as occurred in PA1). In such a case a "not applicable" memo is to be prepared. Applicant and County staff to address AC units in side yards as soon as possible.</u>	Each PA
559.1		EIR 589	SC 4.8-3 (cont.)	Prior to the recordation of a subdivision map or prior to the issuance of grading permits	Sound Attenuation (cont.):		Sound Attenuation (cont.):	a. Prior to the recordation of a subdivision map or prior to the issuance of grading permits, as determined by the Manager, Building Permits Services, the applicant shall submit an acoustical analysis report to the Manager, Building Permits Services, for approval. The report shall describe in detail the exterior noise environment and preliminary mitigation measures. Acoustical design features to achieve interior noise standards may be included in the report in which case it may also satisfy Condition B below. (County Standard Condition N01)	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
589.1		EIR 589	SC 4.15-1	Prior to recordation of <del>final tract a-subdivision</del> maps (alternatively subdivider may enter into a subdivision improvement agreement with the County	Water Improvement Plans:		Water Improvement Plans:	Prior to the recordation of a subdivision map, the subdivider shall design and construct (or provide evidence of financial security, such as bonding) water distribution system and appurtenances that conform to the applicable laws and adopted regulations enforced by the County Fire Chief, in accordance with plans and specifications meeting the approval of the Manager, Subdivision and Grading. (Added per MMRP attached to 11/8/06 CEQA Resolution 04-290)	<del>County of Orange Director of Planning &amp; Development Services</del> <b>Director, OC Planning</b> (OCFA)	Approved water improvement plans with subsequent construction of improvement	<b>Applicant must submit one of the following: (1) approved improvement plan consisted with referenced Plan of Works, (2) letters from both SMWD and OCFA indicating sufficient water supply and pressure for Map area, or (3) subdivision improvement agreement with County.</b>	Each PA
597		EIR 589	SC 4.15-9		CUSD Fees:		CUSD Fees:	Prior to the recordation of final tract map, the project applicant shall provide for the payment of fees pursuant to California Government Code Section 65995, unless other provision are required of the applicant through the agreement with CUSD (see Mitigation Measure 4.15-5).	N/A	Compliance with CUSD agreement	<b>Payment of school fees per CUSD/RMV Agreement</b>	PC-Wide
619		Fire Prot. Prog.	Cond. 4	Prior to recordation of each Tract Map	Administrative Approval of Tract Maps		Administrative Approval of Tract Maps	Prior to recordation of each Tract Map, the applicant shall submit a copy of the proposed Tract map to OCFA for administrative approval (verifying that the map remains consistent with previous approvals), and for OCFA's record keeping purposes.	<del>Director, PDS,</del> <b>Director, OC Planning</b>	Submit a copy of the proposed Tract map to OCFA for administrative approval		
COA #7		Subarea 3.5 Builer "B" Map COAs	Cond. #7	Prior to recordation of the final tract map			MANEUVERABILITY EASEMENT	Prior to recordation of the final tract map, the subdivider shall demonstrate that all necessary ingress/egress easements for vehicle maneuverability within motor courts/alleyways are identified on the final map subject to the satisfaction of the Planning Manager. The easement shall prohibit property owners from installing any improvements within the easement area or interfering with the use or maintenance of the easement.	<del>Director, PDS,</del> <b>Director, OC Planning</b>	Submit a copy of the proposed Tract map to OCFA for administrative approval		

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
<b>b. Prior to Approval of Site Development Permit</b>												
109		EIR 589	MM 4.7-3	Prior to approval of <del>Master Area Plan or Subarea Plan</del> Site Development Permit	Air Quality	Shade trees, evaporative emissions	Incorporate Shade Trees into Parking Lot Design	With the submittal of each Master Area Plan, the project applicant shall identify how shade trees can be incorporated into parking lot designs (to reduce evaporative emissions from parked vehicles); where shade trees can be sited (to reduce summer cooling needs); and how shade trees would be incorporated into bicycle and pedestrian path design. <i>[Note: for the purposes of clarification, the timing of this requirement should be interpreted to read as follows: Prior to approval of each applicable Site Development permit, the project applicant shall ...]</i>	<del>Director, PDS</del> <b>Director, OC Planning</b>	Submittal of satisfactory landscape plans (precise, not general landscape plan at SDP level)		Each PA
110	111 (MM 4.7-3)	EIR 589	MM 4.7-3 (cont.)	Prior to approval of <del>Master Area Plan or Subarea Plan</del> Site Development Permit	Air Quality	Light-colored roof materials	Use Light-Colored Roof Materials to Reflect Heat (Item Nos. 110-111)	As a part of each Master Area Plan, the applicant shall identify how the use of light-colored roof materials and paint to reflect heat to the extent feasible has been incorporated into the design plans. <i>[Note: for the purposes of clarification, the timing of this requirement should be interpreted to read as follows: Prior to approval of each applicable Site Development permit, the project applicant shall ...]</i>	<del>Director, PDS</del> <b>Director, OC Planning</b>	Issuance of Building Permit (Evidence of reflection of materials)		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
<b>c. Prior to Issuance of Grading Permits</b>												
521		EIR 589	SC 4.4-1	Prior to the issuance of a grading permit	Geology and Soils:		Geology and Soils:	Prior to the issuance of a grading permit, the applicant shall submit a geotechnical report to the <del>Manager of Subdivision</del> <b>Manager OC Planned Communities</b> and Grading, for approval. The report shall meet the requirements outlined in the County of Orange Grading Code and Manual. (County Standard Condition G01)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory geotechnical report		Each PA
522		EIR 589	SC 4.4-2	Prior to the issuance of a grading permit	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to the issuance of any grading permits, the Manager of Subdivision and Grading shall review the grading plan for conformance with the grading shown on the approved tentative map. If the applicant submits a grading plan which the <del>Manager of Subdivision and Grading</del> <b>Manager OC Planned Communities</b> determines to show a significant deviation from the grading shown on the approved tentative map, specifically with regard to slope heights, slope ratios, pad elevations or configurations, the Subdivision Committee shall review the plan for a finding of substantial conformance. (County Standard Condition G02)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Approval of grading plan demonstrating submittal conformance with the grading shown on the approved TTM		Each PA
523		EIR 589	SC 4.4-2 (cont.)	Prior to the issuance of a grading permit	Geology and Soils (cont.):		Geology and Soils (cont.):	If the Subdivision Committee fails to make such a finding, the applicant shall process a revised tentative map; or, if a final map has been recorded, the applicant shall process a new tentative map or a site development permit application per Orange County Zoning Code Sections 7-9-139 and 7-9-150. Additionally, the applicant shall process a new environmental assessment for determination by the decision making entity. (County Standard Condition G02)	Subdivision Committee review for substantial conformance, if required	Process new subdivision, if necessary		Each PA
524		EIR 589	SC 4.4-3	Prior to the recordation of a subdivision map or prior to issuance of a Grading Permit, whichever comes first	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to the recordation of a subdivision map or prior to the issuance of any grading permit, whichever comes first, and if determined necessary by the County of Orange Manager, Subdivision and Grading, the applicant shall record a letter of consent from the affected property owners permitting off-site grading, cross lot drainage, drainage diversions and/or unnatural concentrations. The applicant shall obtain approval of the form of the letter of consent from the Manager, Subdivision and Grading Services before recordation of the letter. (County Standard Condition G04)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Recordation of a letter of consent from affected property owners if determined necessary by County of Orange Director of Planning & Development Services		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
525		EIR 589	SC 4.4-4	Prior to the issuance of grading permits	Geology and Soils (cont.):		Geology and Soils (cont.):	Prior to issuance of grading permits, the <del>Manager of Subdivision and Grading-</del> <b>Manager OC Planned Communities</b> shall determine that the proposed grading is consistent with the grading depicted within the approved planning application. (County Standard Condition G09)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Approval of grading plan		Each PA
527		EIR 589	SC 4.5-1	Prior to recordation of a Subdivision Map or issuance of a Grading Permit, whichever comes first	Drainage Study:		Drainage Study:	Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the following drainage studies shall be submitted to and approved by the Manager, Subdivision and Grading: (County Standard Condition D01a)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory of drainage study		Each PA
527.1		EIR 589	SC 4.5-1 (cont.)	See above	Drainage Study (cont.):		Drainage Study (cont.):	A. A drainage study of the project including diversions, off-site areas that drain onto and/or through the project, and justification of any diversions; and B. When applicable, a drainage study evidencing that proposed drainage patterns will not overload existing storm drains; and C. Detailed drainage studies indicating how the project grading, in conjunction with the drainage conveyance systems including applicable swales, channels, street flows, catch basins, storm drains, and flood water retarding, will allow building pads to be safe from inundation from rainfall runoff which may be expected from all storms up to and including the theoretical 100-year flood. (County Standard Condition D01a)	See above	See above		Each PA
528		EIR 589	SC 4.5-2	Prior to recordation of a Subdivision Map or Issuance of a Grading Permit, whichever comes first	Drainage Improvements:		Drainage Improvements:	A. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any grading permits, whichever comes first, the applicant shall in a manner meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition D02a)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Approval of storm drain drainage plans and offer(s) of dedication, if necessary		Each PA
528.1		EIR 589	SC 4.5-2 (cont.)	See above	Drainage Improvements (cont.):		Drainage Improvements (cont.):	1) Design provisions for surface drainage; 2) Design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and 3) Dedicate the associated easements to the County of Orange, if determined necessary. (County Standard Condition D02a)	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
530		EIR 589	SC 4.5-3	Prior to the issuance of Grading Permits	Drainage Improvements (cont.):		Drainage Improvements (cont.):	A. Prior to the issuance of any grading permits, the applicant shall in a manner meeting the approval of the Manager, Subdivision and Grading: (County Standard Condition D02b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory drainage plans		Each PA
530.1		EIR 589	SC 4.5-3 (cont.)	See above	Drainage Improvements (cont.):		Drainage Improvements (cont.):	1) Design provisions for surface drainage; and 2) Design all necessary storm drain facilities extending to a satisfactory point of disposal for the proper control and disposal of storm runoff; and 3) Dedicate the associated easements to the County of Orange, if determined necessary. (County Standard Condition D02b)	See above	See above		Each PA
537		EIR 589	SC 4.5-8	Prior to the recordation of a Subdivision Map or the issuance of any Grading or Building Permit, whichever comes first	Water Quality Management Plan:		Water Quality Management Plan:	Prior to the recordation of any final subdivision map (except those maps for financing or conveyance purposes only) or the issuance of any grading or building permit (whichever comes first), the applicant shall submit for review and approval by the Manager, Inspection Services Division, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. This WQMP shall identify, at a minimum, the routine structural and non-structural measures specified in the current Drainage Area Management Plan (DAMP). The WQMP may include one or more of the following: (County Standard Condition WQ01)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory Water Quality Management Plan		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
537.1		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	<ul style="list-style-type: none"> <li>• Discuss regional water quality and/or watershed programs (if available for the project);</li> <li>• Address Site Design BMPs (as applicable) such as minimizing impervious areas, maximizing permeability, minimizing directly connected impervious areas, creating reduced or "zero discharge" areas, and conserving natural areas;</li> <li>• Include the applicable Routine Source Control BMPs as defined in the DAMP. (County Standard Condition WQ01)</li> </ul>	See above	See above		Each PA
538		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate how surface runoff and subsurface drainage shall be managed and directed to the nearest acceptable drainage facility (as applicable), via sump pumps if necessary. (Standard Condition of Approval, WQ03)	See above	See above		Each PA
540		EIR 589	SC 4.5-10	Prior to the issuance of any Grading or Building Permits	Stormwater Pollution Prevention Plan.		Stormwater Pollution Prevention Plan.	Prior to the issuance of any grading or building permits, the applicant shall demonstrate compliance under California's General Permit for Stormwater Discharges Associated with Construction Activity by providing a copy of the Notice of Intent (NOI) submitted to the State Water Resources Control Board and a copy of the subsequent notification of the issuance of a Waste Discharge Identification (WDID) Number or other proof of filing in a manner meeting the satisfaction of the Manager, Building Permit Services. Projects subject to this requirement shall prepare and implement a Stormwater Pollution Prevention Plan (SWPPP). A copy of the current SWPPP shall be kept at the project site and be available for County review on request. (County Standard Condition WQ04)	<del>County of Orange</del> <del>Manager of Building Inspection</del> <b>Manager, OC Inspection Division</b> (Regional Water Quality Control Board)	Provision of Notice of Intent and verification of a copy of the Storm Water Pollution Prevention Plan (SWPPP); at the project site		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
541		EIR 589	SC 4.5-11	Prior to the issuance of any Grading or Building Permits	Erosion and Sediment Control Plan.		Erosion and Sediment Control Plan.	Prior to the issuance of any grading or building permit, the applicant shall submit a Erosion and Sediment Control Plan (ESCP) in a manner meeting approval of the Manager, Building Permit Services, to demonstrate compliance with local and state water quality regulations for grading and construction activities. The ESCP shall identify how all construction materials, wastes, grading or demolition debris, and stockpiles of soil, aggregates, soil amendments, etc. shall be properly covered, stored, and secured to prevent transport into local drainages or coastal waters by wind, rain, tracking, tidal erosion or dispersion. The ESCP shall also describe how the applicant will ensure that all BMPs will be maintained during construction of any future public right-of-ways. A copy of the current ESCP shall be kept at the project site and be available for County review on request. (County Standard Condition WQ05)	<del>County of Orange</del> <del>Manager of Building Permits,</del> <b>Manager, Permit Services</b> (Building Plan Check)	Submittal of satisfactory Erosion and Sediment Control Plan (ESCP); verification of copy of ESCP at project site		Each PA
548		EIR 589	SC 4.6-6	Prior to the issuance of Grading Permits	Sight Distance:		Sight Distance:	Prior to the issuance of any grading permits, the applicant shall provide adequate sight distance per Standard Plan 1117 at all street intersections, in a manner meeting the approval of the Manager, Subdivision and Grading. The applicant shall make all necessary revisions to the plan to meet the sight distance requirement such as removing slopes or other encroachments from the limited use area in a manner meeting the approval of the Manager, Subdivision and Grading Services. (Standard Condition of Approval T07)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Approved grading plans verifying adequate sight distance		Each PA
555		EIR 589	SC 4.7-1	Prior to the issuance of a grading permit	Fugitive Dust:		Fugitive Dust:	All construction contractors shall comply with South Coast Air Quality Management District (SCAQMD) regulations, including Rule 403, Fugitive Dust, and Rule 402, Nuisance. All grading (regardless of acreage) shall apply best available control measures for fugitive dust in accordance with Rule 403. To ensure that the project is in full compliance with applicable SCAQMD dust regulations and that there is no nuisance impact off the site, the contractor would implement each of the following:	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Verification of compliance with Rule 403 and Rule 402		Each PA



## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
555.1		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	a. Moisten soil not more than 15 minutes prior to moving soil or conduct whatever watering is necessary to prevent visible dust emissions from traveling more than 100 feet in any direction.	See above	See above		Each PA
555.2		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	b. Apply chemical stabilizers to disturbed surface areas (i.e., completed grading areas) within five days of completing grading or apply dust suppressants or vegetation sufficient to maintain a stabilized surface.	See above	See above		Each PA
555.3		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	c. Water excavated soil piles hourly or cover with temporary coverings.	See above	See above		Each PA
555.4		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	d. Water exposed surfaces at least twice a day under calm conditions. Water as often as needed on windy days when winds are less than 25 miles per day or during very dry weather in order to maintain a surface crust and prevent the release of visible emissions from the construction site.	See above	See above		Each PA
555.5		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	e. Wash mud-covered tires and under-carriages of trucks leaving construction sites.	See above	See above		Each PA
555.5		EIR 589	SC 4.7-1 (cont.)	See above	Fugitive Dust (cont.):		Fugitive Dust (cont.):	f. Provide for street sweeping, as needed, on adjacent roadways to remove dirt dropped by construction vehicles or mud, which would otherwise be carried off by trucks departing from project sites.	See above	See above		Each PA
556		EIR 589	SC 4.7-2	Prior to issuance of a grading permit	Construction - ROC and NOX Emissions:		Construction - ROC and NOX Emissions:	The applicant shall comply with the following measures, as feasible, to reduce NO <sub>x</sub> and ROC from heavy equipment.	County of Orange Director of Planning & Development Services, <b>Director, OC Planning</b>	Place as general notes on approved grading plan		Each PA
556.1		EIR 589	SC 4.7-2 (cont.)	See above	Construction Emissions:		Construction Emissions:	a. Turn equipment off when not in use for more than five minutes.	See above	See above		Each PA
556.2		EIR 589	SC 4.7-2 (cont.)	See above	Construction Emissions (cont.):		Construction Emissions (cont.):	b. Maintain equipment engines in good condition and in proper tune as per manufacturers' specifications.	See above	See above		Each PA
556.3		EIR 589	SC 4.7-2 (cont.)	See above	Construction Emissions (cont.):		Construction Emissions (cont.):	c. Lengthen the construction period during smog season (May through October) to minimize the number of vehicles and equipment operating at the same time.	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
557		EIR 589	SC 4.8-1	Prior to the issuance of grading permits	Hours of Construction:		Hours of Construction:	During construction, the project applicant shall ensure that all noise generating activities be limited to the hours of 7 a.m. to 8 p.m. on weekdays and Saturdays. No noise generating activities shall occur on Sundays and holidays in accordance with the County of Orange Noise Ordinance.	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	General note on approved grading plan		Each PA
558		EIR 589	SC 4.8-2	Prior to the issuance of grading permits	Construction Noise:		Construction Noise:	A. Prior to the issuance of any grading permits, the project proponent shall produce evidence acceptable to the Manager, Building Permits Services, that: (County Standard Condition N10)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	General note on approved grading plan		Each PA
558.1		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	(1) All construction vehicles or equipment, fixed or mobile, operated within 1,000' of a dwelling shall be equipped with properly operating and maintained mufflers. (County Standard Condition N10)	See above	See above		Each PA
558.2		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	(2) All operations shall comply with Orange County Codified Ordinance Division 6 (Noise Control). (County Standard Condition N10)	See above	See above		Each PA
558.3		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	(3) Stockpiling and/or vehicle staging areas shall be located as far as practicable from dwellings. (County Standard Condition N10)	See above	See above		Each PA
558.4		EIR 589	SC 4.8-2 (cont.)	See above	Construction Noise (cont.):		Construction Noise (cont.):	B. Notations in the above format, appropriately numbered and included with other notations on the front sheet of the project's permitted grading plans, will be considered as adequate evidence of compliance with this condition. (County Standard Condition N10)	See above	See above		Each PA
559		EIR 589	SC 4.8-3	See below	Sound Attenuation:		Sound Attenuation:	The applicant shall sound attenuate all residential lots and dwellings against present and projected noise (which shall be the sum of all noise impacting the project) so that the composite interior standard of 45 dBA CNEL for habitable rooms and a source specific exterior standard of 65 dBA CNEL for outdoor living areas is not exceeded. The applicant shall provide a report prepared by a County-certified acoustical consultant, which demonstrates that these standards will be satisfied in a manner consistent with Zoning Code Section 7-9-137.5, as follows: (County Standard Condition N01)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services and</del> <del>County of Orange</del> <del>Manager of Building Permits Services,</del> <b>Director, OC Planning and Manager, Permit Services</b> <b>(Building Plan Check)</b>	Submittal of satisfactory acoustical analysis	<b>Staff may determine that no attenuation is necessary, and no action is required (as occurred in PA1). In such a case a "not applicable" memo is to be prepared. Applicant and County staff to address AC units in side yards as soon as possible.</b>	Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
559.1		EIR 589	SC 4.8-3 (cont.)	Prior to the recordation of a subdivision map or prior to the issuance of grading permits	Sound Attenuation (cont.):		Sound Attenuation (cont.):	a. Prior to the recordation of a subdivision map or prior to the issuance of grading permits, as determined by the Manager, Building Permits Services, the applicant shall submit an acoustical analysis report to the Manager, Building Permits Services, for approval. The report shall describe in detail the exterior noise environment and preliminary mitigation measures. Acoustical design features to achieve interior noise standards may be included in the report in which case it may also satisfy Condition B below. (County Standard Condition N01)	See above	See above		Each PA
567		EIR 589	SC 4.10-2	Prior to the issuance of precise grading permits	Private Area Landscaping:		Private Area Landscaping:	a. Prior to the issuance of precise grading permits, the applicant shall prepare a detailed landscape plan for privately maintained common areas which shall be reviewed and approved by the Manager, Subdivision and Grading. The plan shall be certified by a licensed landscape architect or a licensed landscape contractor, as required, as taking into account the approved preliminary landscape plan (if any), County Standard Plans for landscape areas, adopted plant palette guides, applicable scenic and specific plan requirements, Water Conservation Measures contained in Board Resolution 90-487 (Water Conservation Measures), and Board Resolution 90-1341 (Water Conservation Implementation Plan). (County Standard Condition LA02b)	<del>County of Orange</del> Director of Planning & Development Services, <b>Director, OC Planning</b>	Approved detailed landscape plan for privately maintained common areas		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
571	172-176 (MM 4.11-3)	EIR 589	SC 4.11-1	Prior to the issuance of any grading permits	Archaeology Grading Observation and Salvage:		Archaeology Grading Observation and Salvage:	Prior to the issuance of any grading permit, the applicant shall provide written evidence to the County of Orange Manager, Subdivision and Grading, that applicant has retained a County-certified archaeologist to observe grading activities and salvage and catalogue archaeological resources as necessary. The archaeologist shall be present at the pre-grade conference; shall establish procedures for archaeological resource surveillance; and shall establish, in cooperation with the applicant, procedures for temporarily halting or redirecting work to permit the sampling, identification, and evaluation of the artifacts as appropriate. If the archaeological resources are found to be significant, the archaeological observer shall determine appropriate actions, in cooperation with the project applicant, for exploration and/or salvage. (County Standard Condition A04)	<del>County of Orange Manager, Harbors, Beaches &amp; Parks HBP/Coastal and Historical Facilities</del> <b>OC Public Works/OC Planning*</b>	Written evidence that a County-certified archaeologist has been retained to observe grading and salvage, and to catalogue archaeological resources	<b>If prior to rough grade (GA permit) applicant has obtained archaeological clearance, no additional review or clearance required if precise grading (GB) permit is in compliance with GA permit.</b>	Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
574		EIR 589	SC 4.11-2	Prior to the issuance of any grading permits	Paleontology Resource Surveillance:		Paleontology Resource Surveillance:	Prior to the issuance of any grading permit, the project contractor shall provide written evidence to the Manager, Subdivision and Grading, that contractor has retained a County certified paleontologist to observe grading activities and salvage and catalogue fossils as necessary. The paleontologist shall be present at the pre-grade conference, shall establish procedures for paleontological resources surveillance, and shall establish, in cooperation with the contractor, procedures for temporarily halting or redirecting work to permit sampling, identification, and evaluation of the fossils. If the paleontological resources are found to be significant, the paleontologist shall determine appropriate actions, in cooperation with the contractor, which ensure proper exploration and/or salvage. (County Standard Condition A07)	<del>County of Orange Manager, Harbors, Beaches &amp; Parks HBP/Coastal and Historical Facilities</del> <b>OC Public Works/OC Planning*</b>	Written evidence that a County-certified archaeologist has been retained to observe grading and salvage, and to catalogue fossils as necessary		Each PA
589		EIR 589	SC 4.14-2	Prior to issuance of a grading and/or building permit	Hazardous Materials:		Hazardous Materials:	Prior to the issuance of a grading or building permit, the contractor shall submit to the Fire Chief a list of all hazardous, flammable and combustible liquids, solids or gases to be stored, used or handled on site. These materials shall be classified according to the Uniform Fire Code and a document submitted to the Fire Chief with a summary sheet listing the totals for storage and use for each hazard class. (County Standard Condition FPC11A)	<del>County of Orange Director of Planning &amp; Development Services</del> <b>Director, OC Planning (OCFA)</b>	Submission of Hazardous Materials Assessment and Disclosure Statement		Each PA
616		Fire Prot. Prog.	Cond. 3.d.	Prior to the issuance of a GB precise grading permit	Precise Fuel Mod:		Precise Fuel Mod:	d) Prior to the issuance of a GB precise grading permit, the applicant shall provide the <del>Manager, PDS Subdivision and Infrastructure</del> <b>Manager OC Planned Communities</b> , with a clearance from OCFA indicating their review and approval of a Precise Fuel Modification Plan per RPFPP Section C.3.	<del>Director, PDS, Director, OC Planning</del>	Provide the <del>Manager, PDS Subdivision and Infrastructure</del> <b>Manager OC Planned Communities</b> with a clearance from OCFA demonstrating approval of a Conceptual Fuel Modification Plan		

RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

Appendix C

PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
COA# 2		Subarea 3.5 Builder "B" Map COAs		Prior to the issuance of any grading or building permits	WQMP			Prior to the issuance of any grading or building permits, the applicant shall submit for review and approval by the Manager, Permit Services, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. The applicant shall utilize the Orange County Drainage Area Management Plan (DAMP), Model WQMP, and Technical Guidance Manual for reference, and the County's WQMP template for submittal.	<del>County of Orange Manager, Building Inspection Services,</del> <b>Manager, OC Inspection Division</b>			Each PA
COA# 2 (cont.)		Subarea 3.5 Builder "B" Map COAs		See above	WQMP			<p>This WQMP shall include the following:</p> <ul style="list-style-type: none"> <li>- Detailed site and project description</li> <li>- Potential stormwater pollutants</li> <li>- Post-development drainage characteristics</li> <li>- Low Impact Development (LID) BMP selection and analysis</li> <li>- Structural and Non-Structural source control BMPs</li> <li>- Site design and drainage plan (BMP Exhibit)</li> <li>- GIS coordinates for all LID and Treatment Control BMPs</li> <li>- Operation and Maintenance (O&amp;M) Plan that (1) describes the long-term operation and maintenance requirements for BMPs identified in the BMP Exhibit; (2) identifies the entity that will be responsible for long-term operation and maintenance of the referenced BMPs; and (3) describes the mechanism for funding the long-term operation and maintenance of the referenced BMPs</li> </ul> <p>The BMP Exhibit from the approved WQMP shall be included as a sheet in all plan sets submitted for plan check and all BMPs shall be depicted on these plans. Grading and building plans must be consistent with the approved BMP exhibit.</p>	<del>County of Orange Manager, Building Inspection Services,</del> <b>Manager, OC Inspection Division</b>			Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
<b>d. Prior to Precise Fuel Modification Plans</b>												
138	137 and 139 (EIR 589, MM 4.9-27) 514 (ROSA Exhibit G)	EIR 589	MM 4.9-27 (cont.)	Prior to the approval of <a href="#">Precise</a> Fuel Modification Plans	Biological Resources	California Exotic Pest Plant Council, OCFA Fuel Modification Plant List	Invasive Plants and Fuel Modification	a. Prior to issuance of fuel modification plan approvals, the County of Orange shall verify that: 1) plants identified by the California Exotic Pest Plant Council as an invasive risk in Southern California are not included in plans for fuel management zones adjacent to the RMV Open Space and, 2) the plant palette for fuel management zones adjacent to RMV Open Space is limited to those species listed on the Orange County Fire Authority Fuel Modification Plant List.	<del>Director, PDS</del> <b>Director, OC Planning</b> (OCFA)	Verification of authorized plant materials	Signature of <a href="#">Landscape Architect</a> on approved <a href="#">Precise</a> Fuel Modification Plan certifying plant palette: (a) <a href="#">complies with current OCFA plant list</a> , and (b) <a href="#">does not include plants listed on the current invasive species list</a> .	Each PA
<b>e. Prior to Issuance of Building Permit</b>												
111	110 (MM 4.7-3)	EIR 589	MM 4.7-3 (cont.)	Prior to issuance of building permits	Air Quality	Light-colored roof materials	Use Light-Colored Roof Materials to Reflect Heat (Item Nos. 110-111)	Prior to issuance of building permits, the applicant shall identify how the use of light-colored roof materials and paint to reflect heat to the extent feasible has been incorporated into the design plans.	<del>Director, PDS</del> <b>Director, OC Planning</b>	Issuance of Building Permit (Evidence of reflection of heat through home design)	Sustainability Issue	Each PA
140	141 (MM 4.9-28) 515 (ROSA Exhibit G)	EIR 589	MM 4.9-28	Prior to the issuance of Building permits on streets for tracts with public street lighting adjacent to RMV Open Space habitat areas	Biological Resources	Open Space habitat, light shields	Streetlight Shielding Adjacent to Open Space	Lighting shall be shielded or directed away from RMV Open Space habitat areas through the use of low-sodium or similar intensity lights, light shields, native shrubs, berms or other shielding methods.	<del>Director, PDS</del> <b>Director, OC Planning</b>	Preparation of a lighting plan	<a href="#">Preparation of street improvement plans for public streets that detail how street lighting is to be directed away from RMV Open Space areas</a>	Each Applicable PA
206		EIR 589	MM 4.15-5	Prior to issuance of residential building permits (excluding age-qualified units)	Public Services and Facilities	California Government Code Section 65995	CUSD Agreement	Prior to issuance of any residential building permit, excluding senior housing, the applicant shall enter into an agreement with CUSD regarding the development of future facilities and payment of costs. The agreement shall, at a minimum, provide for the payment of fees pursuant to California Government Code Section 65995. If fees are paid, the amount of fees to be paid will be determined based on the established State formula for determining construction costs. Applicable fees shall be paid prior to the issuance of each building permit.	Capistrano Unified School District (CUSD)	Negotiate and execute Mitigation Agreement regarding future school facilities and payment of costs		PC-Wide

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
526		EIR 589	SC 4.4-5	Prior to the issuance of building permits	Geology and Soils (cont.):		Geology and Soils (cont.):	The proposed development shall be designed in compliance with the Uniform Building Code (UBC), accepted industry standards, and the County's earthquake safety Municipal Code requirements.	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Verification of design development compliance with the UBC and Municipal Code requirements		Each PA
537		EIR 589	SC 4.5-8	Prior to the recordation of a Subdivision Map or the issuance of any Grading or Building Permit, whichever comes first	Water Quality Management Plan:		Water Quality Management Plan:	Prior to the recordation of any final subdivision map (except those maps for financing or conveyance purposes only) or the issuance of any grading or building permit (whichever comes first), the applicant shall submit for review and approval by the Manager, Inspection Services Division, a Water Quality Management Plan (WQMP) specifically identifying Best Management Practices (BMPs) that will be used onsite to control predictable pollutant runoff. This WQMP shall identify, at a minimum, the routine structural and non-structural measures specified in the current Drainage Area Management Plan (DAMP). The WQMP may include one or more of the following: (County Standard Condition WQ01)	<del>County of Orange Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory Water Quality Management Plan		Each PA
537.1		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	<ul style="list-style-type: none"> <li>• Discuss regional water quality and/or watershed programs (if available for the project);</li> <li>• Address Site Design BMPs (as applicable) such as minimizing impervious areas, maximizing permeability, minimizing directly connected impervious areas, creating reduced or "zero discharge" areas, and conserving natural areas;</li> <li>• Include the applicable Routine Source Control BMPs as defined in the DAMP.</li> </ul> (County Standard Condition WQ01)	See above	See above		Each PA
538		EIR 589	SC 4.5-8 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	Demonstrate how surface runoff and subsurface drainage shall be managed and directed to the nearest acceptable drainage facility (as applicable), via sump pumps if necessary. (Standard Condition of Approval, WQ03)	See above	See above		Each PA



## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
540		EIR 589	SC 4.5-10	Prior to the issuance of any Grading or Building Permits	Stormwater Pollution Prevention Plan.		Stormwater Pollution Prevention Plan.	Prior to the issuance of any grading or building permits, the applicant shall demonstrate compliance under California's General Permit for Stormwater Discharges Associated with Construction Activity by providing a copy of the Notice of Intent (NOI) submitted to the State Water Resources Control Board and a copy of the subsequent notification of the issuance of a Waste Discharge Identification (WDID) Number or other proof of filing in a manner meeting the satisfaction of the Manager, Building Permit Services. Projects subject to this requirement shall prepare and implement a Stormwater Pollution Prevention Plan (SWPPP). A copy of the current SWPPP shall be kept at the project site and be available for County review on request. (County Standard Condition WQ04)	<del>County of Orange Manager of Building Inspection</del> <b>Manager, OC Inspection Division</b> (Regional Water Quality Control Board)	Provision of Notice of Intent and verification of a copy of the Storm Water Pollution Prevention Plan (SWPPP); at the project site		Each PA
541		EIR 589	SC 4.5-11	Prior to the issuance of any Grading or Building Permits	Erosion and Sediment Control Plan.		Erosion and Sediment Control Plan.	Prior to the issuance of any grading or building permit, the applicant shall submit a Erosion and Sediment Control Plan (ESCP) in a manner meeting approval of the Manager, Building Permit Services, to demonstrate compliance with local and state water quality regulations for grading and construction activities. The ESCP shall identify how all construction materials, wastes, grading or demolition debris, and stockpiles of soil, aggregates, soil amendments, etc. shall be properly covered, stored, and secured to prevent transport into local drainages or coastal waters by wind, rain, tracking, tidal erosion or dispersion. The ESCP shall also describe how the applicant will ensure that all BMPs will be maintained during construction of any future public right-of-ways. A copy of the current ESCP shall be kept at the project site and be available for County review on request. (County Standard Condition WQ05)	<del>County of Orange Manager of Building Permits</del> <b>Manager, Permit Services</b> (Building Plan Check)	Submittal of satisfactory Erosion and Sediment Control Plan (ESCP); verification of copy of ESCP at project site		Each PA
547		EIR 589	SC 4.6-5	Prior to the issuance of Building Permits	Major Thoroughfare and Bridge Fee Programs:		Major Thoroughfare and Bridge Fee Programs:	Prior to the issuance of building permits, the applicant shall pay fees for the Major Thoroughfare and Bridge Fee Program for the Foothill/Eastern Transportation Corridor, in a manner meeting the approval of the Manager, Subdivision and Grading. (County Standard Condition T05)	<del>County of Orange Director of Planning &amp; Development Services</del> <b>Director, OC Planning</b>	Verification of payment of fees for the Major Thoroughfare and Bridge Fee Program		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
550		EIR 589	SC 4.6-8	Prior to the recordation of a Subdivision Map or prior to the issuance of Building Permits, whichever occurs first	Internal Circulation:		Internal Circulation:	A. Prior to the recordation of a subdivision map or the issuance of any building permits, whichever occurs first, the subdivider shall provide plans and specifications meeting the approval of the Manager, Subdivision and Grading, for the design of the following improvements: (County Standard Condition T12)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del>	Submittal of satisfactory street improvement plans		Each PA
550.1		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation (cont.):		Internal Circulation (cont.):	1) Internal street common private drive system. (County Standard Condition T12)	See above	See above		Each PA
550.2		EIR 589	SC 4.6-8 (cont.)	See above	Internal Circulation (cont.):		Internal Circulation (cont.):	2) Entrance to the site to emphasize that the development is private by use of signs and other features. (Standard Condition of Approval T12)	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
550.4		EIR 589	SC 4.6-8 (cont.)	Prior to the issuance of Building Permits	Internal Circulation (cont.):		Internal Circulation (cont.):	C. Prior to the issuance of any building permits, the subdivider shall provide plans meeting the approval of the Manager, Subdivision & Grading, for the design of the internal pedestrian circulation system within the development. (County Standard Condition T12)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Submittal of satisfactory internal pedestrians circulation plans		Each PA
559.2		EIR 589	SC 4.8-3 (cont.)	Prior to the issuance of any building permits for residential construction	Sound Attenuation (cont.):		Sound Attenuation (cont.):	b. Prior to the issuance of any building permits for residential construction, the applicant shall submit an acoustical analysis report describing the acoustical design features of the structures required to satisfy the exterior and interior noise standards to the Manager, Building Permits Services, for approval along with satisfactory evidence which indicates that the sound attenuation measures specified in the approved acoustical report have been incorporated into the design of the project. (County Standard Condition N01)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services and</del> <del>County of Orange</del> <del>Manager of Building Permits Services,</del> <b>Director, OC Planning and Manager, Permit Services</b> (Building Plan Check)	Submittal of satisfactory acoustical analysis		Each PA
559.3		EIR 589	SC 4.8-3 (cont.)	See above	Sound Attenuation (cont.):		Sound Attenuation (cont.):	c. Prior to the issuance of any building permits, the applicant shall show all freestanding acoustical barriers on the project's plot plan illustrating height, location and construction in a manner meeting the approval of the Manager, Building Permits Services. (County Standard Condition N01)	See above	See above		Each PA
564		EIR 589	SC 4.10-1	Prior to the issuance of building permits	Public Area Landscaping:		Public Area Landscaping:	The applicant shall install landscaping, equip for irrigation, and improvements on lots in accordance with an approved plan as stated below: (County Standard Condition LA01b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services in consultation with Manager, HBP,</del> <b>Director, OC Planning</b>	Approved landscaping plan and irrigation plan		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
564.1		EIR 589	SC 4.10-1 (cont.)	See above	Public Area Landscaping:		Public Area Landscaping:	a. Detailed Plan--Prior to the issuance of any building permit(s), the applicant shall submit a detailed landscape plan showing the detailed irrigation and landscaping design to the Manager, Subdivision and Grading for approval, in consultation with the Manager HBP/Program Management. Detailed plans shall show the detailed irrigation and landscaping design and shall take into account the previously approved landscape plan for the Ranch Plan project, the County Standard Plans for landscape areas, adopted plant palette guides, applicable scenic and specific plan requirements, Water Conservation Measures contained in Board Resolution 90-487 (Water Conservation Measures), and Board Resolution 90-1341 (Water Conservation Implementation Plan). (County Standard Condition LA01b)	See above	See above		Each PA
570		EIR 589	SC 4.10-3	Prior to the issuance of building permits	Light and Glare:		Light and Glare:	Prior to issuance of any building permit, the applicant shall demonstrate that all exterior lighting has been designed and located so that all direct rays are confined to the property in a manner meeting the approval of the Manager, Building Permit. (County Standard Condition LG01)	<del>County of Orange</del> <del>Manager of Building Permits,</del> <b>Manager, Permit Services</b> (Building Plan Check)	Approved lighting study/plan	<b>Low voltage lighting:</b> landscape architect is the designer can sign off on the lighting. High voltage lighting: electrical engineer stamp required.	Each PA
589		EIR 589	SC 4.14-2	Prior to issuance of a grading and/or building permit	Hazardous Materials:		Hazardous Materials:	Prior to the issuance of a grading or building permit, the contractor shall submit to the Fire Chief a list of all hazardous, flammable and combustible liquids, solids or gases to be stored, used or handled on site. These materials shall be classified according to the Uniform Fire Code and a document submitted to the Fire Chief with a summary sheet listing the totals for storage and use for each hazard class. (County Standard Condition FPC11A)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services</del> <b>Director, OC Planning</b> (OCFA)	Submittal of Hazardous Materials Assessment and Disclosure Statement		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
617		Fire Prot. Prog.	Cond. 3.e.	Prior to the issuance of a building permit for construction phases of Vesting Tentative Tract Maps adjoining fuel modification areas, and prior to the County of Orange allowing fuel tanks, generators and/or Lumber Drops	Vegetation Clearance:		Vegetation Clearance:	e) Prior to the issuance of a building permit for construction phases of Vesting Tentative Tract Maps adjoining fuel modification areas, and prior to the County of Orange allowing fuel tanks, generators and/or Lumber Drops (see Section E, Definitions) within the project site, the applicant shall provide the Manager, Building & Safety, with a clearance from OCFA indicating that vegetation has been cleared and maintained at a height of 8 inches or less, or that the appropriate fuel modification thinning and removal of plants from the OCFA Undesirable Plant List has been implemented.	Director, PDS, Director, OC Planning	Provide the Manager, Building & Safety, with a clearance from OCFA indicating that vegetation has been cleared and maintained		
COA# 3		Subarea 3.5 Builer "B" Map COAs	Cond. #3	Prior to the issuance of a building permit			BEST MANAGEMENT PRACTICES	Prior to issuance of a building permit, the off-site regional Best Management Practices (BMPs) relied upon by this project (e.g., basins, swales, etc.) must be built and/or installed, and operational. The location and operation of these regional BMPs must be in compliance with the Final Project-Specific WQMP for the regional BMP(s). The location and operation of the regional BMP(s) must be demonstrated to the satisfaction of the Manager, Grading and Building Plan Check.	Director, PDS, Manager, Permit Services (Building Plan Check)			
COA# 6		Subarea 3.5 Builer "B" Map COAs	Cond. #6	Prior to the issuance of a building permit			BUYER NOTIFICATION MAP	Prior to the issuance of any building permits for residential construction, the developer RMV Community Development, LLC, shall prepare a map denoting the existing and proposed land uses, arterial highways, and public facilities within the surrounding area for the approval of the Manager, OC Planning. The map content, display, and distribution shall be in accordance with the Buyer Notification Program guidelines listed in Board of Supervisors Resolution 82-1368 and as amended.	Director, PDS, Director, OC Planning			

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
<b>f. Prior to Combustible Construction</b>												
609			Cond. 2.d.	Prior to initiation of combustible construction	A Map Fire Master Plan (cont.):		A Map Fire Master Plan (cont.):	d) Prior to initiation of combustible construction the following fire master plan improvements shall be verified by site inspection: • Emergency access • Water Supply	Director, PDS, <b>Director, OC Planning</b>	Site inspection		
<b>g. During Construction</b>												
197	196 (EIR 589, MM 4.14-13)	EIR 589	MM 4.14-13 (cont.)	During construction	Hazards and Hazardous Materials	Remedial measures	ESA Remedial Measures	If soil is encountered during site development that is suspected of being impacted by hazardous materials, work will be halted and site conditions will be evaluated by a qualified environmental professional. If requested by the qualified environmental professional, the results of the evaluation will be submitted to OCHCA and/or RWQCB, and the appropriate remedial measures will be implemented, as directed by OCHCA, RWQCB, or other applicable oversight agency, until all specified requirements of the oversight agencies are satisfied and a no-further-action status is attained.	Director, PDS, <b>Director, OC Planning</b> (Orange County Health Care Agency)	Stop work upon encountering condition; prepare evaluation and submit to OCHCA and/or RWQCB (as directed)		Each PA
<b>h. Prior to Issuance of Certificates of Occupancy</b>												
529		EIR 589	SC 4.5-2 (cont.)	Prior to recordation of a Subdivision Map or Issuance of a Certificate of Use and Occupancy, whichever comes first	Drainage Improvements (cont.):		Drainage Improvements (cont.):	B. Prior to the recordation of a subdivision map (except maps for financing and conveyance purposes only) or prior to the issuance of any certificates of use and occupancy, whichever occurs first, said improvements shall be constructed in a manner meeting the approval of the Manager, Construction. (County Standard Condition D02a)	<del>County of Orange Manager of Inspection,</del> <b>Manager, OC Inspection Division</b>	Verification of construction of drainage improvement		Each PA
531		EIR 589	SC 4.5-3 (cont.)	Prior to the issuance of Certificates of Use and Occupancy	Drainage Improvements (cont.):		Drainage Improvements (cont.):	B. Prior to the issuance of any certificates of use and occupancy, said improvements shall be constructed in a manner meeting the approval of the Manager, Construction. (County Standard Condition D02b)	<del>County of Orange Manager of Inspection,</del> <b>Manager, OC Inspection Division</b>	Verification of installation of drainage improvement		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
539		EIR 589	SC 4.5-9	Prior to the issuance of a Certificate of Use and Occupancy	Compliance with the WQMP:		Compliance with the WQMP:	Prior to the issuance of a certificate of use and occupancy, the applicant shall demonstrate compliance with the WQMP in a manner meeting the satisfaction of the Manager, Inspection Services Division, including: • Demonstrate that all structural Best Management Practices (BMPs) described in the project's WQMP have been implemented, constructed and installed in conformance with approved plans and specifications; • Demonstrate that the applicant has complied with all non-structural BMPs described in the project's WQMP; • Submit for review and approval an Operations and Maintenance (O&M) Plan for all structural BMPs for attachment to the WQMP;	<del>County of Orange</del> <del>Manager of Building Inspection,</del> <b>Manager, OC Inspection Division</b>	Verification of compliance with Water Quality Management Plan		Each PA
539.1		EIR 589	SC 4.5-9 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	• Demonstrate that copies of the project's approved WQMP (with attached O&M Plan) are available for each of the incoming occupants; • Agree to pay for a Special Investigation from the County of Orange for a date (12) twelve months after the issuance of a Certificate of Use and Occupancy for the project to verify compliance with the approved WQMP and O&M Plan; and (County Standard Condition WQ03)	See above	See above		Each PA
539.2		EIR 589	SC 4.5-9 (cont.)	See above	Water Quality Management Plan (cont.):		Water Quality Management Plan (cont.):	• Demonstrate that the applicant has agreed to and recorded one of the following: 1) the CC&R's (that must include the approved WQMP and O&M Plan) for the project Home Owner's Association; 2) a water quality implementation agreement that has the approved WQMP and O&M Plan attached; or 3) the final approved Water Quality Management Plan (WQMP) and Operations and Maintenance (O&M) Plan. (County Standard Condition WQ03)	See above	See above		Each PA

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
560		EIR 589	SC 4.8-4	Prior to the issuance of certificates of use and occupancy	Multi-Family Residential Development:		Multi-Family Residential Development:	Prior to the issuance of any certificates of use and occupancy, the applicant shall perform field testing in accordance with Title 24 Regulations to verify compliance with FSTC and FIIC standards if determined necessary by the Manager, Building Inspection Services. In the event such a test was previously performed, the applicant shall provide satisfactory evidence and a copy of the report to the Manager, Building Inspection Services, as a supplement to the previously required acoustical analysis report. (County Standard Condition N09)	<del>County of Orange</del> <del>Manager of Building Inspection Services,</del> <b>Manager, OC Inspection Division</b>	Verification of field testing in accordance with Title 24 Regulations to verify compliance with FSTC and FIIC standards or a copy of a previous test		Each PA
563		EIR 589	SC 4.8-7	Prior to the issuance of certificates of use and occupancy	Transportation Corridor Notification:		Transportation Corridor Notification:	Prior to the issuance of certificates of use and occupancy, the developer shall produce evidence to the Manager, Building Inspection Services, that the Department of Real Estate has been notified that the project area is adjacent to a regional transportation corridor. The corridor is expected to be a high capacity, high-speed, limited-access facility for motor vehicles, and will have provisions for bus lanes and other mass transit type facilities. (County Standard Condition N12)	<del>County of Orange</del> <del>Manager of Building Inspection Services,</del> <b>Manager, OC Inspection Division</b>	Submission of evidence that County of Orange Dept. of Real Estate has been notified the project area is adjacent to a regional transportation corridor		Each PA
565		EIR 589	SC 4.10-1 (cont.)	Prior to the issuance of final certificates of use and occupancy and the release of financial security	Public Area Landscaping (cont.):		Public Area Landscaping (cont.):	b. Installation Certification: Prior to the issuance of final certificates of use and occupancy and the release of financial security, if any, guaranteeing the landscape improvements, said improvements shall be installed and shall be certified by a licensed landscape architect or licensed landscape contractor, as having been installed in accordance with the approved detailed plans. (County Standard Condition LA01b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services &amp; Manager-HBP,</del> <b>Director, OC Planning</b>	Landscaping and irrigation plan certification from landscape architect		Each PA
566		EIR 589	SC 4.10-1 (cont.)	Prior to the issuance of final certificates of use and occupancy and the release of financial security	Public Area Landscaping (cont.):		Public Area Landscaping (cont.):	b. Installation Certification (cont): The applicant shall furnish said certification, including an irrigation management report for each landscape irrigation system, and any other required implementation report determined applicable, to the Manager, Construction, and the Manager, Building Inspection Services, prior to the issuance of any certificates of use and occupancy. (County Standard Condition LA01b)	<del>County of Orange</del> <del>Manager, Construction and Manager, Building Inspection Services,</del> <b>Manager, OC Inspection Division</b>	Approved irrigation management report		Each PA



## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
568		EIR 589	SC 4.10-2 (cont.)	Prior to the issuance of certificates of use and occupancy	Private Area Landscaping (cont.):		Private Area Landscaping (cont.):	b. Prior to the issuance of certificates of use and occupancy, applicant shall install said landscaping and irrigation system and shall have a licensed landscape architect or licensed landscape contractor, certify that it was installed in accordance with the approved plan. (County Standard Condition LA02b)	<del>County of Orange</del> <del>Director of Planning &amp; Development Services,</del> <b>Director, OC Planning</b>	Certification from landscape architect that landscaping and irrigation system in accordance with the approved plan		Each PA
569		EIR 589	SC 4.10-2 (cont.)	Prior to the issuance of certificates of use and occupancy	Private Area Landscaping (cont.):		Private Area Landscaping (cont.):	c. Prior to the issuance of any certificates of use and occupancy, the applicant shall furnish said installation certification, including an irrigation management report for each landscape irrigation system, and any other implementation report determined applicable, to the Manager, Building Inspection Services. (County Standard Condition LA02b)	<del>County of Orange</del> <del>Manager, Building Inspection Services,</del> <b>Manager, OC Inspection Division</b>	Approved irrigation management report for each landscape irrigation system		Each PA
618		Fire Prot. Prog.	Cond. 3.f.	Prior to the issuance of any certificate of use and occupancy adjoining fuel modification areas	Occupancy Requirements:		Occupancy Requirements:	f) Prior to the issuance of any certificate of use and occupancy, the applicant shall provide the Manager, Building & Safety, with a clearance from OCFA indicating that: 1. Approved "A" Zone planting has been installed and approved irrigation has been activated. 2. Approved fuel modification zone markers have been installed. 3. Accessways every 500 feet (or as approved) have been installed. 4. Approved thinning of the "B" and "C" Zones and removal of plants from the OCFA Undesirable Plant List have been completed. 5. CC&Rs or other approved documents contain provisions for maintaining the fuel modification zones.	<del>Director, PDS,</del> <b>Director, OC Planning</b>	Provide the Manager, Building & Safety, with a clearance from OCFA indicating installation and thinning		

## RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

## Appendix C

## PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
<b>i. Prior to Release of Grading Bond</b>												
572		EIR 589	SC 4.11-1 (cont.)	Prior to the release of the grading bond	Archaeology Grading Observation and Salvage (cont.):		Archaeology Grading Observation and Salvage (cont.):	Prior to the release of the grading bond, the applicant shall obtain approval of the archaeologist's follow-up report from the Manager, Harbors, Beaches & Parks HBP/Coastal and Historical Facilities. The report shall include the period of inspection, an analysis of any artifacts found and the present repository of the artifacts. Applicant shall prepare excavated material to the point of identification. Applicant shall offer excavated finds for curatorial purposes to the County of Orange, or its designee, on a first refusal basis. (County Standard Condition A04)	<del>County of Orange Manager, Harbors, Beaches &amp; Parks HBP/Coastal and Historical Facilities</del> OC Public Works/OC Planning*	Approval of the archaeologist's follow-up report		Each PA
573		EIR 589	SC 4.11-1 (cont.)	Prior to the release of the grading bond	Archaeology Grading Observation and Salvage (cont.):		Archaeology Grading Observation and Salvage (cont.):	These actions, as well as final mitigation and disposition of the resources shall be subject to the approval of the Manager, HBP/Coastal and Historical Facilities. Applicant shall pay curatorial fees if an applicable fee program has been adopted by the Board of Supervisor, and such fee program is in effect at the time of presentation of the materials to the County of Orange or its designee, all in a manner meeting the approval of the Manager, HBP/Coastal and Historical Facilities. (County Standard Condition A04)	<del>County of Orange Manager, Harbors, Beaches &amp; Parks HBP/Coastal and Historical Facilities</del> OC Public Works/OC Planning*	Verification of payment of curatorial fee if an applicable fee program has been adopted by the Board of Supervisor at the time of presentation		Each PA
575		EIR 589	SC 4.11-2 (cont.)	Prior to the release of the grading bond	Paleontology Resource Surveillance (cont.):		Paleontology Resource Surveillance (cont.):	Prior to the release of any grading bond, the contractor shall submit the paleontologist's follow up report for approval by the County Manager, HBP/Coastal and Historical Facilities. The report shall include the period of inspection, a catalogue and analysis of the fossils found, and the present repository of the fossils. The contractor shall prepare excavated material to the point of identification. The contractor shall offer excavated finds for curatorial purposes to the County of Orange, or its designee, on a first-refusal basis. (County Standard Condition A07)	<del>County of Orange Manager, Harbors, Beaches &amp; Parks HBP/Coastal and Historical Facilities</del> OC Public Works/OC Planning*	Approval of the paleontologist's follow-up report		Each PA

RANCH PLAN REGULATION COMPLIANCE MATRIX GUIDANCE DOCUMENT

Appendix C

PA 3.5 BUILDER "B" MAP REQUIREMENTS SORTED BY MILESTONE

Item No.	Cross Reference Column	Source	Condition, Mitigation, Public Benefit or Entitlement Provision	Timing	Subject	Keywords	Title	Requirements or Entitlement Provisions	Reviewing / Approving Authority (Advisory Agency in Parentheses)	Form of Compliance	Guidance for Compliance	Area Application
576		EIR 589	SC 4.11-2 (cont.)	Prior to the release of the grading bond	Paleontology Resource Surveillance (cont.):		Paleontology Resource Surveillance (cont.):	These actions, as well as final mitigation and disposition of the resources, shall be subject to approval by the HBP/Coastal and Historical Facilities. The contractor shall pay curatorial fees if an applicable fee program has been adopted by the Board of Supervisors, and such fee program is in effect at the time of presentation of the materials to the County of Orange or its designee, all in a manner meeting the approval of the County Manager, HBP/Coastal and Historical Facilities. (County Standard Condition A07)	<del>County of Orange Manager, Harbors, Beaches &amp; Parks HBP/Coastal and Historical Facilities</del> <b>OC Public Works/OC Planning*</b>	Verification of payment of curatorial fee if an applicable fee program has been adopted by the Board of Supervisor at the time of presentation		Each PA

# ATTACHMENT 1



April 29, 2025

Bea Bea Jiménez  
Division Manager  
Land Development  
OC Public Works  
601 North Ross Street  
Santa Ana, CA 92701

**SUBJECT:**

Application for "B" Vesting Tentative Tract Map 19322 within Rancho Mission Viejo (Ranch Plan) Planning Area 3, Subarea 3.5 for the AQ43 Lennar project

Dear Ms. Jiménez,

**PROPOSAL:**

Rancho Mission Viejo requests Subdivision Committee approval of Vesting Tentative Tract Map 19322 within Rancho Mission Viejo (Ranch Plan) Planning Area 3, Subarea 3.5 for the AQ43 project to allow 49 Conventional Single Family Detached Dwellings on 49 numbered residential / park lots and 14 lettered lots for landscaped open space purposes.

**ZONING:**

Ranch Plan Planned Community (PC) – Subarea Plan 3.5 Conventional Single Family Detached Dwellings (PC Text Section III.A.1)

**LOCATION:**

The AQ43 project site is located within the Ranch Plan Planned Community - Planning Area 3 (PA3), Subarea 3.5 and Vesting Tentative Tract Map 17935, Lots 26-32, and Lots U, W, Y, Z, CC, DD, EE, FF, HH, and II in unincorporated Orange County, California.

**LANDOWNER/SUBDIVIDER:**

The specific land ownership entity for the proposed project site is RMV PA3 Development LLC (referred to as Rancho Mission Viejo, or "RMV"). The site will eventually be owned by, and homes built by, a neighborhood builder company (Lennar).

**BACKGROUND AND EXISTING CONDITIONS:**

In November 2004, the County of Orange approved the Ranch Plan Planned Community, which encompasses approximately 22,815 acres located east of I-5, north and south of Ortega Highway, within the Fifth Supervisorial District. As approved, the Ranch Plan Planned Community encompasses 75 percent permanent open space, with development of 14,000 dwelling units and 5,200,000 square feet (SF) of non-residential uses allowed within the remaining 25 percent. It is regulated by the Ranch Plan PC Program Text which addresses the

unique characteristics of the property and a development plan for the transition to suburban/urban uses occurring over a 25- to 30-year period.

The Master Area Plan and Subarea Plans for Planning Area 3 were approved on October 27, 2022 including Subarea Plan 3.5 (PA22-0067) and again in October 2024 (PA24-0104). VTTM 17935 for Subarea Plan 3.5 was approved by the OC Subdivision Committee on October 16, 2024. Grading for Subarea 3.5 is approved and currently under construction.

### **PROPOSED PROJECT:**

The applicant (RMV) requests approval of Vesting Tentative Tract Map 19322 to allow 49 Conventional Single-Family Detached Dwellings on 49 numbered residential/park lots and 14 lettered lots for landscaped open space purposes, all within the 12.81-acre project site. Subsequent model sales complex and construction level building applications will be submitted by Lennar. The project will also include street and infrastructure improvements, landscaping, and minor precise grading.

The 49 numbered lots range in size from 5,967 square feet up to 8,556 square feet. The site has a net residential acreage of 9.20 acres (excluding streets, motorcourts, alleys and HOA slopes) for a net residential density of 5.32 dwelling units per acre.

### **SURROUNDING LAND USE:**

Land uses immediately surrounding the project site include the following:

- Westerly: Chaquita Canyon – Open Space
- Southerly: Subarea 3.5 – future residential
- Easterly: Subarea 3.5 - future residential
- Northerly: Subarea 3.8 – future residential

### **REFERRAL FOR COMMENT AND PUBLIC NOTICE:**

The applicant understands that the tentative map application submittal will be distributed for review and comment to County staff and consultants, including Land Development, OC Infrastructure Programs, Inspection Services, Building & Safety, OC Survey, and Orange County Fire Authority. We also understand that the VTTM must be approved by the OC Subdivision Committee at a Public Meeting with a public notice mailed to all property owners of record within 300 feet of the subject, and posted at the site, at the Orange County Hall of Administration, and at 601 N. Ross Street, as required by established public meeting posting procedures.

### **CONSISTENCY ANALYSIS:**

The proposed SDP and VTTM are consistent with the Ranch Plan PC Program Text Use Regulations & Development Standards (PC Program Text, Section III), as described below:

- a. General Plan – The OC General Plan Land Use Element designates Subarea 3.4 of Ranch Plan as “1B, Suburban Residential (0.5 to 18 du/ac)”, per GPA 01-01. The proposed SDP and VTTM are consistent with the 1B “Suburban Residential designation.
- b. Zoning – The proposed SDP and VTTM are consistent with the Ranch Plan Planned Community zoning, including all applicable requirements of the PC Program Text Use Regulations & Development Standards (PC Section III).
- c. State Subdivision Map Act and County of Orange Subdivision Code and Manual – In Compliance.

- d. Area Plans – The proposed SDP and VTTM are consistent with land uses and other details of PA3&4 Master Area Plan and Subarea Plan 3.5 (PA22-0067 & PA24-0104)
- e. CEQA – The proposed SDP and VTTM are consistent with Final EIR 589, previously certified on November 8, 2004; Addendum 1.0 (PA060023) approved July 26, 2006; Addendum 1.1 (PA110003-06) approved February 24, 2011; the Planning Area 2 Addendum (PA130001-06) approved March 27, 2013; and Addendum 3.1 (PA140072-81) approved February 25, 2015.
- f. Alternative Development Standards – All Alternative Development Standards incorporated into this project have been previously approved by the appropriate decision maker per the Ranch Plan Planned Community Program Text, General Regulation 25.
- g. Regulation Compliance Matrix – Clearance of all applicable conditions of approval have been confirmed per the Ranch Plan Regulation Compliance Matrix.

#### Estimated Earthwork

The proposed estimated grading quantities for this map are substantially consistent with or less than the earthwork quantities described under previous approvals (i.e. Master Area Plan (PA3&4), Subarea Plan 3.5, VTTM 17935 and Subarea 3.5 Rough Grading Permit GRD24-0045 currently in process. The proposed grading on this map has been addressed per CEQA document FEIR 589, together with Addendum 3.1 (PA140072-81) approved February 25, 2015.

#### Drainage:

The subject property is in the Ranch Plan Planned Community Runoff Management Plan Area. No Master Plan of Drainage (MPD) facilities have been identified or approved within the site and no MPD fees are required.

#### Recreation and Open Space:

The proposed map is not required to provide any improvements or dedications associated with the County Master Plan of Regional Recreation Facilities; Master Plan of Regional Riding and Hiking Trails; Resources Element (Open Space Component); or OCTA Strategic Plan for Bikeways.

- Master Plan of Regional Recreation Facilities - There are no regional park dedication requirements of the subject map.
- Master Plan of Regional Riding and Hiking Trails - There are no riding and hiking trail requirements of the subject map.
- Master Plan of Local Parks (Local Park Code) - The proposed map is required to provide park land in accordance with the Master Plan of Local Parks (Local Park Code). The Local Park Code requirement for the subject map VTTM 19322 is 0.392 net usable acres of park land based upon a proposal to build 49 dwelling units at a gross residential density of 3.83/ac (49 du x .008 ac/du). Said requirement can be satisfied by an allocation of parkland credit from Park Modification PM07-01, the Local Park Implementation Plan (LPIP) for the Ranch Plan P.C. originally approved March 14, 2007, 1st Amendment approved in June 2012, 2<sup>nd</sup> Amendment approved on July 16, 2014, 3<sup>rd</sup> Amendment approved November 7, 2019, and 4<sup>th</sup> Amendment approved December 6, 2023. Per the Ranch Plan LPIP, the total parkland acreage requirement for the entire Ranch Plan Planned Community is 94.0 acres, based on 14,000 approved dwelling units and the anticipated proportion of single-family and multi-family units. The Ranch Plan LPIP (PM07-01) indicates that far more acres of total community-wide parkland will be implemented in Planning Area 3&4 than would be required per County standards, based on the 7,500 dwelling units entitled by the PA3&4 Master Area Plan PA180030, per the parkland generation factor for each unit (greater than 6.5 du/ac requires 0.006 acres and less than 6.5 du/ac requires 0.008 acres).

- Resources Element - Open Space Component - There are no open space dedication requirements of the subject map.
- OCTA Strategic Plan for Bikeways - There are no County-wide bikeways identified within the area of this map.

#### Public Services & Utilities

- Schools - This property is within the boundaries of the Capistrano Unified School District. The developer is subject to the provisions of Assembly Bill AB 2926, or other mitigating measures designed to provide for school facilities and/or funding, such as community facilities districts. No school site is proposed for Subarea 3.4.
- Facilities Fees Programs - This project area is included within the Ranch Plan Planned Community Development Facility Agreement area which phases development commensurate with public services and facilities.
- Water/Sewer - This project is within the boundaries of the Santa Margarita Water District. The District stated in their "will-serve" letter dated ###/###/2024, that the District will be capable of providing water and sewage disposal service to this development.
- Water Quality Control - This project will be required to operate in accordance with requirements prescribed by the California Regional Water Quality Control Board, San Diego Region.
- Fire Protection and Safety - Existing and proposed fire protection services will be providing an adequate level of fire protection services to this development, per the TT19322 Fire Master Plan approved by OCFA ###/###/2024. Additionally, this property is within the area covered by the approved Ranch Plan Fire Protection Program, which includes all applicable conditions of approval and regulations.
- County Service Area (CSA) - This property is within the boundaries of County Service Area No. 26.

#### Traffic/Circulation

- Scenic Highway Corridors - There are no Scenic Highways applicable to this map
- Access/Highways/Streets/Roads - Access to the site is Laster Lane. Internal tract access will be provided by internal private alleys and motor courts.
- Major Thoroughfare and Bridge Fee Program - This project lies within the area of benefit of the Foothill/Eastern Transportation Corridor. The developer is required to pay Foothill/Eastern Major Thoroughfare and Bridge fees in accordance with the adopted program.
- Off-Site Fee Program – The project lies within the area of benefit of the South County Roadway Improvement Road Fee Program (SCRIP). The developer is required to pay SCRIP fees in accordance with the adopted program.

#### Multiple Final Map Phasing

As indicated by Note 22 on this TT19322, the option of multiple final maps phasing has been requested as part of the approval of this Vesting Tentative Tract Map.

#### **DEVIATIONS FROM STANDARDS OF DESIGN:**

The developer may request deviations from County standard design criteria in accordance with Subdivision Code section 7-9-291. In the absence of any specifically approved deviation request, the County-approved standard design criteria will prevail. No deviations are requested with this map.



**ALTERNATIVE DEVELOPMENT STANDARDS:**

As indicated by Note 30 on this TT19309, as allowed by General Regulation #25 of the Ranch Plan Planned Community Program Text, proposed Alternative Development Standards are intended to be incorporated into the development.

Upon review of this application our hope is that staff supports OC Subdivision Committee approval of the "B" tentative tract map. Please contact me with any questions, or if you or your staff need any further information.

Sincerely,


Richard Vuong  
Project Director, Planning and Entitlement  
Rancho Mission Viejo

# ATTACHMENT 2

**BOARD OF DIRECTORS**

LAURA FREESE  
MARGARET NOVAK  
SAUNDRA F. JACOBS  
BETTY H. OLSON, PH.D  
FRANK URY

ROBERT S. GRANTHAM  
GENERAL MANAGER



# Santa Margarita Water District

July 25, 2025

County of Orange  
OC Public Works  
OC Development Services  
601 N. Ross Street  
Santa Ana, California 92703

Subject: **Preliminary Water and Sewer Letter for Lennar, VTTM 19322, Rancho Mission Viejo, in Improvement District No. 5**

Greetings:

This letter is in response to a request by Lennar (Developer) for a preliminary water and sewer letter for the subject tract.

The Santa Margarita Water District (District) supplies all of its current customers with domestic water purchased from the Metropolitan Water District of Southern California (Metropolitan) through the Municipal Water District of Orange County (MWDOC), which acts as a wholesaler to its member agencies. It is anticipated the subject tract would also be supplied with available domestic water purchased from Metropolitan through MWDOC. Supplemental water for this development, if required, will be provided per the approved The Ranch Plan Planning Area 3 and 4 Water Supply Verification, dated October 2017. Subject to the Developer's successful completion of the in-tract water and recycled water and the District's construction of the off-site water and recycled water facilities, the District can and will provide domestic and recycled water service to each and every building parcel in the subject tract without exception.

Furthermore, and subject to the Developer's successful completion of the in-tract sewer facilities and the District's construction of off-site sewer facilities, the District can and will provide sewer service to each and every building lot within the subject tract without exception.

At this time, the Developer has not provided surety to guarantee the construction of the in-tract water, recycled water and sewer facilities. A final will-serve will be issued upon your request when (1) the Developer has guaranteed the construction of the in-tract facilities and (2) construction of the District's water and sewer facilities is assured.

Should you have any questions or desire additional information, please call Karla Houlihan at (949) 459-6581.

Sincerely,  
SANTA MARGARITA WATER DISTRICT

*Patricia Butler*


Patricia A Butler  
Chief Engineer

S:\ENGINEERING\PRELIMINARY WILL SERVE\2025\Will Serve VTTM 19322.doc

# ATTACHMENT 3



# VICINITY MAP



# VESTING TENTATIVE TRACT MAP 19322 PA 3, SUBAREA 3.5 AQ43

REVIEWED FOR CODE COMPLIANCE


THESE PLANS AND DOCUMENTS HAVE BEEN REVIEWED AND FOUND TO BE IN COMPLIANCE WITH THE CALIFORNIA SUBDIVISION MAP ACT, AS AMENDED, AND THE CALIFORNIA BUILDING CODE. THE REVIEWER'S REVIEW IS LIMITED TO THE TECHNICAL ASPECTS OF THE PLANS AND DOES NOT CONSTITUTE A GUARANTEE OF THE ACCURACY OF THE INFORMATION PROVIDED HEREON. THE REVIEWER'S REVIEW IS LIMITED TO THE TECHNICAL ASPECTS OF THE PLANS AND DOES NOT CONSTITUTE A GUARANTEE OF THE ACCURACY OF THE INFORMATION PROVIDED HEREON.

08/19/2025

SALEM GARAWI, P.E.  
CSG CONSULTANTS, INC.

## LEGAL DESCRIPTION

LOTS 26 THROUGH 32, LOTS U, W, Y, Z, CC, DD, EE, FF, AND II IN THE UNINCORPORATED TERRITORY OF THE COUNTY OF ORANGE, STATE OF CALIFORNIA, AS SHOWN ON "A" TRACT 17935



## LOCATION MAP

## NOTES

- EXISTING LAND USE: VACANT LAND, PREVIOUSLY MASS GRADED PER GR022-0016 & ROUGH GRADED PER GR024-0045 TO ALLOW FOR FUTURE DEVELOPMENT.
- PROPOSED LAND USE: CONVENTIONAL SINGLE FAMILY DETACHED RESIDENTIAL - 49 DWELLING UNITS.
- EXISTING ZONING: LOCATED WITHIN RANCH PLAN PLANNED COMMUNITY PLANNING AREA 3 AND SUBAREA PLAN PA 3.5, IS ZONED AS A DEVELOPMENT AREA BY THE RANCH PLAN PC TEXT, AND SHALL BE PROCESSED PER THE IMPLEMENTATION PROCEDURES DETAILED IN SECTION 11.C OF THE PC TEXT.
- THE PLANNING AREA 3 MASTER AREA PLAN AND SUBAREA PLAN 3.5 (PA24-0181) DESIGNATE THE PROJECT SITE AS RESIDENTIAL.
- GRADING PLANS MAY BE PROCESSED CONCURRENTLY WITH A TENTATIVE TRACT MAP, PER A CONCURRENT PROCESSING REQUEST LETTER. PLAN CHECKING OF ROUGH GRADE PLANS OR PRECISE GRADE PLANS MAY PROCEED, BUT APPROVAL OF THE GRADING PLAN MUST FOLLOW VTM APPROVAL.
- CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) IMPACTS HAVE BEEN ADDRESSED BY THE RANCH PLAN FINAL PROGRAM EIR 589 AND ADDENDUM 3.1.
- ADJACENT LAND USE ZONING

NORTH: OPEN SPACE  
SOUTH: EXISTING RESIDENTIAL, SUBAREA 3.2A MR41 TR19152  
EAST: FUTURE RESIDENTIAL, SUBAREA 3.5 AQ24 (VTM19321) AND AQ13 (VTM19324)  
WEST: OPEN SPACE / PUBLIC STREET (RANCH CANYON AND LAMKIN LANE)

8. SANITARY SEWER SERVICES PROVIDED BY: SANTA MARGARITA WATER DISTRICT.  
9. DOMESTIC WATER SERVICE PROVIDED BY: SANTA MARGARITA WATER DISTRICT.  
10. NON-DOMESTIC RECYCLED WATER SERVICE PROVIDED BY: SANTA MARGARITA WATER DISTRICT.

11. ALL PROPOSED UTILITIES ARE TO BE UNDERGROUND WITH THE EXCEPTION OF ELECTRICAL TRANSMISSION LINES GREATER THAN 66KV. PROPOSED UTILITY LOCATIONS SHOWN ON THE MAP ARE APPROXIMATE. ACTUAL LOCATIONS AND EASEMENT WIDTHS WILL BE REFLECTED ON FINAL TRACT MAP(S).


GAS: SOUTHERN CALIFORNIA GAS COMPANY  
ELECTRIC: SAN DIEGO GAS AND ELECTRIC  
TELEPHONE: AT&T AND COX COMMUNICATIONS  
CABLE TELEVISION: COX COMMUNICATIONS

- PROJECT SITE IS WITHIN THE CAPISTRANO UNIFIED SCHOOL DISTRICT.
- DRAINAGE SYSTEM WILL BE DEVELOPED IN ACCORDANCE WITH THE G.C. PUBLIC WORKS AND COUNTY OF ORANGE FLOOD CONTROL DISTRICT STANDARDS AND THE "TENTATIVE TRACT MAP 17935 SUBAREA 3.5 MASTER PLAN OF DRAINAGE" PREPARED BY HUNSAKER AND ASSOCIATES AND THE RUN OFF MANAGEMENT PLAN (ROMP), PA 3 & 4 ROMP REVISION 1 APPROVED 11/17/23.
- STREET IMPROVEMENTS SHOWN HEREON SHALL MEET THE REQUIREMENTS OF THE COUNTY OF ORANGE AND THE RANCH PLAN ALTERNATIVE DEVELOPMENT STANDARDS.
- ALL SLOPES SHALL BE CONSTRUCTED AT A MAXIMUM SLOPE RATIO OF 2:1 UNLESS OTHERWISE NOTED.
- GRADING FOR VESTING TENTATIVE TRACT MAP NO. 19322 MAY BE ACCOMPLISHED IN MULTIPLE PHASES.
- STORM FLOW TRIBUTARIES TO THE SITE SHALL BE INTERCEPTED AND CONVEYED AROUND AND THROUGH THE SITE VIA THE PROPOSED STORM DRAIN SYSTEMS SHOWN HEREON.
- ALL PROPOSED STORM DRAINS SHOWN HEREON ARE PRELIMINARY. STORM DRAIN PLANS WILL BE PREPARED PRIOR TO RECODIFICATION OF THE FINAL MAP.
- BACKSLOPE AND OFFSITE FACILITIES FOR VESTING TENTATIVE TRACT NO. 19322 MAY BE PHASED AND COORDINATED WITH THE INITIAL GRADING AND DEVELOPMENT.
- ACCESS TO THE SITE IS PROPOSED VIA GAVILAN RIDGE AND STOOK STREET. STREETS ARE PUBLIC AND ALLEYS ARE PRIVATE.
- PUBLIC EASEMENTS (IF NECESSARY) FOR SIDEWALK PURPOSES WILL BE REFLECTED ON THE FINAL MAPS.
- THE APPLICANT REQUESTS THE OPTION OF RECORDING MULTIPLE FINAL MAPS FROM THIS VESTING TENTATIVE TRACT MAP PER SECTION 66456.1 OF THE STATE OF CALIFORNIA GOVERNMENT CODE (SUBDIVISION MAP ACT), AS AMENDED MARCH 1982.
- LANDSCAPING WITHIN MEDIAN AREAS, STREET ISLANDS, AND PARKWAYS WILL BE MAINTAINED BY A MASTER MAINTENANCE CORPORATION ESTABLISHED FOR THE BENEFIT OF THE PROPERTY OWNERS.
- THIS MAP IS AN APPLICATION FOR A DEVELOPMENT PERMIT PURSUANT TO SECTION 65943 OF THE CALIFORNIA GOVERNMENT CODE.
- PROPOSED UTILITIES, AND EASEMENTS, INCLUDING BUT NOT LIMITED TO PUBLIC UTILITIES, FIRE ACCESS, PRIVATE ACCESS, PRIVATE UTILITY AND ACCESS ARE APPROXIMATE. ACTUAL UTILITY AND TRAIL LOCATIONS AND EASEMENT WIDTHS WILL BE REFLECTED ON THE FINAL MAPS, OR BY SEPARATE EASEMENT DOCUMENTS SUBSEQUENT TO FINAL MAP RECODIFICATION.
- STREET CENTERLINE RATES OF GRADE WILL BE BETWEEN 1% AND 10% UNLESS SHOWN OTHERWISE.

- THE SUBDIVIDED PROPERTY SHOWN HEREON IS CONSIDERED "CONTIGUOUS UNITS" OF LAND PURSUANT TO SECTION 66424 OF THE CALIFORNIA SUBDIVISION MAP ACT, AS AMENDED.
- EASEMENTS FOR PUBLIC USE MAY BE CREATED ON THE FINAL MAPS OR BY SEPARATE INSTRUMENTS SUBSEQUENT TO FINAL MAP RECODIFICATION FOR PUBLIC USE OVER FACILITIES SUCH AS, BUT NOT LIMITED TO, WATER QUALITY ELEMENTS, NEIGHBORHOOD ELECTRICAL VEHICLE PATHS AND OTHER FACILITIES AS MAY BE DETERMINED.
- ACCESS TO STORM DRAINS AND BASINS FOR MAINTENANCE PURPOSES SHALL BE PROVIDED TO THE COUNTY OF ORANGE OR OCFO AS APPROPRIATE.
- PER THE RANCH PLAN PLANNED COMMUNITY-WIDE ALTERNATIVE DEVELOPMENT STANDARDS (APPROVED MAY 22, 2024), SUBSEQUENT REVISIONS OR ADDITIONS MAY ALSO BE APPROVED, AND AS ALLOWED BY RANCH PLAN PC TEXT (GENERAL REGULATION 25) THE FOLLOWING ALTERNATIVE DEVELOPMENT STANDARDS (ADS) ARE PROPOSED AS PART OF THIS "A" TENTATIVE TRACT MAP, OR MAY BE PROPOSED AS PART OF SUBSEQUENT "B" TENTATIVE TRACT MAPS:

- 36-FOOT DOUBLE LOADED STREETS (UP TO 800 ADT)
- RESIDENTIAL LOCAL STREETS 30' WIDE (400 TO 1,200 ADT)
- CURB RETURNS AT EACH RESIDENTIAL DRIVEWAY
- CUL-DE-SACS WITH RAISED LANDSCAPE MEDIAN
- ALTERNATIVE NEIGHBORHOOD SIDEWALK DETAIL CURB-SEPARATED WALKWAY
- PRIVATE CURB CORE OUTLET AND CLEANOUT DETAIL
- PRIVATE AREA DRAIN CONNECTION TO CATCH BASIN INLET
- INTERSECTION SIGHT LINE STANDARDS
- CORNER RAMP CONDITION TYPICAL INTERSECTION
- MODIFIED COLOR OF CURB RAMP DETECTABLE WARNING SURFACE
- REDUCED AGE QUALIFIED PARKING
- CONVENTIONAL SINGLE FAMILY DETACHED DWELLINGS SETBACKS
- CURB (AND GUTTER) OPTIONS ON PRIVATE STREETS
- REDUCED LOCAL DEPRESSIONS ON PRIVATE STREETS
- REDUCED LOCAL DEPRESSION ON PUBLIC STREET
- CLASS III NEW ROUTE

- DEVELOPMENT OF VTM 19322 SHALL COMPLY WITH SITE ACCESSIBILITY REQUIREMENTS PER THE CALIFORNIA BUILDING CODE AND PER THE ORANGE COUNTY HIGHWAY DESIGN MANUAL SECTION 105.1 (2b) FOR SIDEWALKS THAT ARE LESS THAN 5 FEET IN WIDTH.
- ALL PUBLIC STREETS SHALL BE COUNTY MAINTAINED.
- ALL PRIVATE STREETS/EASEMENTS WILL NOT BE ACCEPTED BY THE COUNTY FOR MAINTENANCE. COUNTY WILL ONLY ACCEPT THE NECESSARY PUBLIC STREETS AND PUBLIC EASEMENTS.
- ALL LOT AND PAD GRADIENTS TO BE 1% MINIMUM, UNLESS OTHERWISE NOTED. MASS GRADED PADS CAN BE GRADED AT 1% MINIMUM PER GEOTECHNICAL ENGINEER'S LETTER ON FILE AT RANCHO MISSION VIEJO, LLC (DEVIATION TO COUNTY GRADING CODE AND MANUAL).
- ALL CROSS LOT DRAINAGE TO BE ACCEPTED BY DOWNSTREAM PROPERTY OWNER.
- ALL PRIVATE COURTS SHALL HAVE A RECIPROCAL INGRESS/EGRESS EASEMENT, MINIMUM 30 FOOT WIDE FOR THE BENEFIT OF ALL LOTS IN TRACT NO. 19322.
- PER RANCH PLAN COMPLIANCE MATRIX ITEM 544, "PRIOR TO THE RECODIFICATION OF A SUBDIVISION MAP, THE SUBDIVIDER SHALL PLACE NOTES ON THE FINAL MAP WHICH RELEASE AND RELINQUISH VEHICULAR ACCESS RIGHTS TO ALL ARTERIAL HIGHWAYS TO THE COUNTY OF ORANGE, IN A MANNER MEETING THE APPROVAL OF THE MANAGER, SUBDIVISION AND GRADING."
- PROJECT WILL BE SHARING BMP FACILITIES WITH ROUGH GRADE "A" TTM WOMP FOR PLANNING AREA 3 SUBAREA 3.5 (W024-0058), APPROVED 10/17/24, CONSISTENT WITH WATERSHED'S DECEMBER 16, 2024 MEMO REGARDING UPDATED GUIDELINES FOR THE PREPARATION OF WOMP FOR THE RANCH PLAN PLANNED COMMUNITY. PROJECT IS LOCATED IN THE SAN DIEGO REGION OF THE CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD AND WILL OPERATE IN ACCORDANCE WITH THE APPLICABLE BOARD'S REQUIREMENTS.
- THIS PLAN IS LOCATED WITHIN AN AREA COVERED BY THE RANCH PLAN FIRE PROTECTION PROGRAM.
- THE RESIDENTIAL DEVELOPMENT IS WITHIN A STATE RESPONSIBILITY AREA (SRA) - VERY HIGH FIRE HAZARD SEVERITY ZONE.
- ALL UNITS TO BE SPRINKLERED PER RANCH FIRE PROTECTION PROGRAM AND OCFA REQUIREMENTS.
- DEVELOPMENT OF TRACT 19322 WILL COMPLY WITH ALL APPLICABLE REQUIREMENTS OF THE MODEL WATER EFFICIENT LANDSCAPE ORDINANCE.
- IN THE DESIGN OF THIS MAP, THE GUIDELINES AND REQUIREMENTS WITHIN THE CALIFORNIA SOLAR PERMITTING GUIDEBOOK ADOPTED BY THE STATE OF CALIFORNIA WERE CONSIDERED.



## LEGEND

- |                                 |                       |
|---------------------------------|-----------------------|
| PROJECT BOUNDARY                | EXISTING CONTOUR      |
| PROPOSED LOT LINE               | EXISTING STORM DRAIN  |
| PROPOSED CONTOUR LINE           | EXISTING WATER        |
| RIGHT OF WAY                    | EXISTING SEWER        |
| TOP OF SLOPE                    | PROPOSED STORM DRAIN  |
| TOE OF SLOPE                    | PROPOSED WATER        |
| DAYLIGHT LINE                   | PROPOSED SEWER        |
| PROPOSED EASEMENT               | PROPOSED FIRE HYDRANT |
| PROPOSED RETAINING WALL         | LOT NUMBER            |
| EXISTING EASEMENT PER VTM 17935 | PAD ELEVATION         |

## EASEMENT NOTES

- INDICATES AN EASEMENT FOR SEWER, WATER AND ACCESS PURPOSES DEDICATED PER FINAL MAP 19322 TO THE SANTA MARGARITA WATER DISTRICT.
- INDICATES A RECIPROCAL INGRESS/EGRESS EASEMENT, MINIMUM 30 FOOT WIDE FOR THE BENEFIT OF ALL LOTS IN TRACT NO. 19322.
- INDICATES AN EXISTING EASEMENT FOR SEWER AND ACCESS PURPOSES DEDICATED PER FINAL MAP 17935 TO THE SANTA MARGARITA WATER DISTRICT.
- INDICATES AN EXISTING EASEMENT FOR STORM DRAIN AND ACCESS PURPOSES DEDICATED PER FINAL MAP 17935 TO THE COUNTY OF ORANGE.

## SLOPE DESIGNATIONS:

- ALL MANUFACTURED SLOPES TO HAVE TERRACE AND DOWN DRAINS AS REQUIRED BY THE COUNTY OF ORANGE GRADING CODE REQUIREMENTS, BUT ARE NOT SHOWN HEREON FOR CLARITY.
- (A) MAINTAINED BY MASTER HOA  
(B) MAINTAINED BY INDIVIDUAL LOT OWNER

## STATEMENT OF OWNERSHIP

RMV PA3 DEVELOPMENT, LLC IS THE OWNER OF THAT PORTION OF PA3 COVERED BY TT19322 AND AUTHORIZED TO EXECUTE AND DELIVER ALL DOCUMENTS THAT ARE NECESSARY AND APPROPRIATE FOR PROCESSING AND IMPLEMENTING THE PA3 DEVELOPMENT PROGRAM. SAID AUTHORITY INCLUDES, BUT IS NOT LIMITED TO, THE EXECUTION AND DELIVERY OF SUCH APPLICATIONS, AGREEMENTS AND OTHER DOCUMENTS AS ARE REQUIRED BY THE COUNTY OF ORANGE IN CONNECTION WITH THE PROCESSING AND DEVELOPMENT OF PA3 BY RANCHO MISSION VIEJO, LLC, A DELAWARE LIMITED LIABILITY COMPANY, ITS AUTHORIZED AGENT AND MANAGER.

DATED THIS: 8/12/2025

BY: *Nicholas A. Streeter*  
PRINTED NAME: Nicholas A. Streeter  
TITLE: President

BY: *Elise L. Millington*  
PRINTED NAME: Elise L. Millington  
TITLE: CEO


## BENCHMARK

OCS BM "AP-02-00" (NAVD88) ELEVATION: 238.11' FOUND 3-3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "AP-02-99", SET IN THE NORTHEASTLY CORNER OF A CONCRETE BRIDGE DECK. MONUMENT IS LOCATED IN THE NORTHEASTLY CORNER OF ANTONIO PARKWAY AND ITS OVERCROSSING OF SAN JUAN CREEK.

## ENGINEERS STATEMENT

I HEREBY STATE THAT THIS MAP WAS PREPARED UNDER MY SUPERVISION AND THAT THE OWNER OF RECORD HAS KNOWLEDGE OF AND CONSENTS TO THE FILING OF THIS MAP.

*N.S. Streeter*  
NICHOLAS A. STREETER  
DATE: 8/12/2025




REVISION	DESCRIPTION
DATE	

<b>OWNER:</b> RMV PA3 DEVELOPMENT, LLC 28811 ORTEGA HIGHWAY SAN JUAN CAPISTRANO, CA 92694 (949) 240-3363 ATTN: JAY BULLOCK jbullock@ranchomv.com	<b>APPLICANT:</b> <b>LENNAR</b> 15131 ALTON PARKWAY, SUITE 365 IRVINE, CA 92618 (949) 349-8000 ATTN: BRIAN GEORGE brian.george@lennar.com	<b>PREPARED BY:</b> <b>PROACTIVE</b> ENGINEERING CONSULTANTS 27081 Towne Centre Drive, Suite 270 Foothill Ranch, CA 92611 (949) 316-7480 ATTN: NICHOLAS STREETER, PE, PLS nstreeter@proactive.net
<b>COUNTY OF ORANGE</b> <b>VESTING TENTATIVE TRACT MAP 19322</b> <b>RANCH PLAN - PLANNING SUBAREA 3.5</b> <b>RMV PA3 DEVELOPMENT - AQ43</b> <b>NORTHWEST SIDE OF LEGADO ROAD AND LAMKIN LANE</b>		
<b>DESIGNED BY:</b> _____ <b>DRAFTED BY:</b> _____ <b>CHECKED BY:</b> _____	<b>DATE:</b> 8/12/2025	<b>COUNTY FILE NO.:</b> VTTM 19322 <b>SHEET:</b> VTTM-1




## TYPICAL STREET SECTIONS & DETAILS



**TYPICAL 24' PRIVATE COURT**

(ADS G-4)  
ADT-19  
NOT TO SCALE


NOT TO SCALE



SECTION A-A

**SUNLIT WAY**

PARKING BOTH SIDES - 25 MPH (ADS A-20 & J-5)  
ADT-260  
(PUBLIC)


 $\mathbb{Q}$ 

SECTION B-B  
CLIMITE MAX

**SUNLIT WAY**  
ONE SIDE - 25 MPH (ADS A-1)

ADT-260  
(PUBLIC)

£



SECTION C-C  
CLINITE WAY

**SUNLIT WAY**  
ONE SIDE - 25 MPH (ADS A-1)

ADT-260  
(PUBLIC)

### NUMBERED LOT AREA SUMMARY

LOT NUMBER	LOT SIZE S.F.	LOT SIZE ACRES	LOT NUMBER	LOT SIZE S.F.	LOT NUMBER
1	7,018	0.16	26	6,572	0.11
2	6,946	0.16	27	6,570	0.11
3	6,751	0.15	28	6,572	0.11
4	6,556	0.15	29	6,579	0.11
5	6,361	0.15	30	6,806	0.11
6	6,165	0.14	31	7,472	0.11
7	5,991	0.14	32	6,601	0.11
8	6,722	0.15	33	6,587	0.11
9	6,949	0.16	34	6,469	0.11
10	6,547	0.15	35	6,536	0.11
11	6,288	0.14	36	6,190	0.11
12	6,448	0.15	37	6,610	0.11
13	7,161	0.16	38	6,175	0.11
14	7,436	0.17	39	6,284	0.11
15	7,511	0.17	40	6,354	0.11
16	7,471	0.17	41	6,263	0.11
17	7,404	0.17	42	6,214	0.11
18	6,531	0.15	43	6,195	0.11
19	6,513	0.15	44	6,203	0.11
20	6,494	0.15	45	6,229	0.11
21	6,663	0.15	46	6,217	0.11
22	6,463	0.15	47	6,718	0.11
23	6,256	0.14	48	8,034	0.11
24	6,264	0.14	49	8,643	0.22
25	6,325	0.15			
TOTAL				325,788	7.4

### LETTERED LOT AREA SUMMARY

LOT NUMBER	LOT SIZE		USE
	SQ. FT.	ACRES	
A	3001	0.07	PRIVATE DRIVE
B	16891	0.39	LANDSCAPE LOT
C	3556	0.08	LANDSCAPE LOT
D	4343	0.10	SLOPE/LANDSCAPE
E	4755	0.11	SLOPE/LANDSCAPE
F	6283	0.14	SLOPE/LANDSCAPE
G	3527	0.08	SLOPE/LANDSCAPE
H	1409	0.03	SLOPE/LANDSCAPE
I	2843	0.07	SLOPE/LANDSCAPE
J	5661	0.13	SLOPE/LANDSCAPE
K	4791	0.11	SLOPE/LANDSCAPE
L	9679	0.22	SLOPE/LANDSCAPE
M	13544	0.31	SLOPE/LANDSCAPE
N	3752	0.09	SLOPE/LANDSCAPE
	<b>84035</b>	<b>1.93</b>	

## PROJECT SUMMARY

PROJECT SUMMARY						
LOT NUMBERS	TOTAL LOTS	ACRES	GROSS %	NET %	PROPOSED LAND USE	
1-49	49	7.48	57.81%	94.09%	RESIDENTIAL SFD	
A	1	0.07	0.53%	0.87%	PRIVATE DRIVE	
B-C	2	0.47	3.63%	5.91%	LANDSCAPE LOT	
D-N	11	1.39	10.75%	17.50%	SLOPE/ LANDSCAPE	
STREET		3.53	27.28%	44.41%	PUBLIC STREET R.O.W.	
TOTALS	63					
GROSS DEVELOPMENT AREA		12.94	ALL LOTS 1-49, A-N		3.79	DU/AC GROSS DENSITY
NET DEVELOPMENT AREA		7.95	LESS R.O.W./P.V. DR., SLOPE/LANDSCAPE, LESS R.O.W./P.V. DR., LANDSCAPE LOTS, SLOPE/ LANDSCAPE		6.16	DU/AC NET DENSITY
NET RESIDENTIAL AREA		7.48			6.55	DU/AC NET RESIDENTIAL DENSITY

## PROJECT SUMMARY NOTES

**Density:**

- Gross Density: The number of dwelling units per gross acre (see definition of "gross acres")
- Net Density: The number of dwelling units per net acre (see definition of "net acres")

**Gross Acres:** The total acreage of the building site including, but not limited to, building site areas, streets, driveways, private recreation areas, ordinance required local park land, open space area, easement areas and slopes.

**Net Acres:** The number of acres remaining after subtracting other land uses such as parks, other peripheral open space, schools and collector and arterial roads and after subtracting slopes greater than ten (10) feet in height from the total gross acreage.

**Net Residential Area:** The area of land remaining in a project, measured in acres or square feet, after deduction of the area contained in the public and private street (OC Planned Communities interprets this definition to include alleys and motor courts) and highway rights-of-way, schools, parks, flood control works, off-street parking areas, and any other use, easement or encumbrance which prevents the surface use of the property for a building site or construction of structures (i.e. lettered lots).

**OWNER:**  
RMV PA3 DEVELOPMENT, LLC  
28811 ORTEGA HIGHWAY  
SAN JUAN CAPISTRANO, CA 92694  
(949) 240-3363  
ATTN: JAY BULLOCK  
jbullocc@ranchomv.com

**APPLICANT:**

**LENNAR**  
15131 ALTON PARKWAY, SUITE 360  
IRVINE, CA 92618  
(949) 349-8000  
ATTN: BRIAN GEORGE  
brian.george1@lennar.com

**PREPARED BY:**  
**PROACTIVE**  
ENGINEERING CONSULTANTS  
27051 Towne Centre Drive, Suite 270  
Foothill Ranch, CA 92610 (949) 716-7480  
ATTN: NICHOLAS STREETER, PE, PLS  
NSTREETER@PROENG.NET


**COUNTY OF ORANGE**

**VESTING TENTATIVE TRACT MAP 19322  
RANCH PLAN - PLANNING SUBAREA 3.5  
RMV PA3 DEVELOPMENT - AQ43  
NORTHWEST SIDE OF LEGADO ROAD AND LAMKIN LANE**

DESIGNED BY: --	DATE: 8/12/2025	COUNTY FILE NO.: VTTM 19322	SHEET VTTM-2
-----------------	-----------------	-----------------------------	--------------

PLOTTED BY: Nick Streeter DATE: Aug. 12, 2025 11:31:55 AM FILE: N:\25.041.000\TTM\25.041-AQ43-TTM 19322.dwg

### LEGEND




## EASEMENT NOTES

- ① INDICATES AN EASEMENT FOR SEWER, WATER AND ACCESS PURPOSES DEDICATED PER FINAL MAP 19322 TO THE SANTA MARGARITA WATER DISTRICT.
- ② INDICATES A RECIPROCAL INGRESS/EGRESS EASEMENT, MINIMUM 30' WIDE FOR THE BENEFIT OF ALL LOTS IN TRACT NO. 19322.
- ③ INDICATES AN EXISTING EASEMENT FOR SEWER AND ACCESS PURPOSES DEDICATED PER FINAL MAP 17935 TO THE SANTA MARGARITA WATER DISTRICT.
- ④ INDICATES AN EXISTING EASEMENT FOR STORM DRAIN AND ACCESS PURPOSES DEDICATED PER FINAL MAP 17935 TO THE COUNTY OF ORANGE.


## SLOPE DESIGNATIONS

ALL MANUFACTURED SLOPES TO HAVE TERRACE AND DOWN DRAIN  
AS REQUIRED BY THE COUNTY OF ORANGE GRADING CODE  
REQUIREMENTS, BUT ARE NOT SHOWN HEREON FOR CLARITY.

☐ (A) MAINTAINED BY MASTER HOA  
☐ (B) MAINTAINED BY INDIVIDUAL LOT OWNER







VICINITY MAP

# ORANGE COUNTY FIRE AUTHORITY



## FIRE MASTER PLAN

ORANGE COUNTY FIRE AUTHORITY  
Reviewed by Planning & Development  
Service Request Expires After 6 Months of Inactivity

Approval subject to field inspection and required test, notations hereon, conditions in correspondence and conformance with applicable regulations. The stamping of these plans shall not be held to permit or approve the violation of any law.

OCFA SR #: 25000828 PR145 OCFA Approved  
Fee Codes: PR 145  
Plan Type: Fire Master Plan  
By: brianslegers  
Date: 05/28/2025

ONLY STAMPED SHEETS REVIEWED BY ORANGE COUNTY FIRE AUTHORITY  
Call at least 72 hours in advance to schedule inspections: (714) 573-6150

Notes:

OCFA STAMP

### PROJECT INFORMATION REQUIREMENTS

PROJECT LOCATION: RIENDA PLANNING AREA 3.5, RANCHO MISSION VIEJO

PARCEL MAP NUMBER:  
TRACT NUMBER: 19322  
LOT NUMBERS: 1-49

EMERGENCY ACCESS EASEMENTS

#### DETAILED SCOPE OF WORK

NOTE: OCFA WILL ONLY REVIEW WORK OUTLINED IN SCOPE OF WORK  
AQ43 IS A NEW PROPOSED PROJECT WITHIN THE RANCHO MISSION VIEJO PLANNING AREA 3.5. THE PROJECT CONSISTS 49 UNITS TOTAL, WITH THE LARGEST BUILDING BEING 2,941 GROSS SQ.FT.

#### NUMBER OF UNITS OR HOMES IN DEVELOPMENT

49 SINGLE FAMILY DETACHED BUILDINGS

#### SPECIAL CONDITIONS

- ☒ FIRE HAZARD SEVERITY ZONE  
☐ STATE LICENSED FACILITY  
☐ AM&M  
☐ METHANE MITIGATION
- ☒ STATE RESPONSE AREA  
☐ COMPLETE SR:
- ☐ LOCAL RESPONSE AREA

#### NUMBER OF STORIES

1 AND 2 STORIES

#### BUILDING HEIGHT

#### OCCUPANCY TYPE (CHECK ALL THAT APPLY)

\* INDICATES SFM REGULATED OCCUPANCY. OCFA PLAN SUBMITTAL REQUIRED

- # GROUP S MOTOR VEHICLE REPAIR AND AIRCRAFT REPAIR REQUIRE OCFA PLAN SUBMITTAL
- ☐ GROUP A1\*  
☐ GROUP B  
☐ GROUP H2\*  
☐ GROUP I2\*  
☐ GROUP R2\*  
☐ GROUP R4\*

☐ GROUP A2\*  
☐ GROUP E\*  
☐ GROUP H3\*  
☐ GROUP I3\*  
☐ GROUP R2.1  
☐ GROUP S1#

☐ GROUP A3\*  
☐ GROUP F1  
☐ GROUP H4\*  
☐ GROUP I4\*  
☐ GROUP R2.2  
☐ GROUP S2#

☐ GROUP A4\*  
☐ GROUP F2  
☐ GROUP H5\*  
☐ GROUP M  
☒ GROUP R3  
☐ GROUP U

☐ GROUP A5\*  
☐ GROUP H1\*  
☐ GROUP I1\*  
☐ GROUP R1\*  
☐ GROUP R3.1

#### TYPE OF CONSTRUCTION

- ☐ TYPE IA  
☐ TYPE IIA  
☐ TYPE IIIA  
☐ TYPE IVA  
☐ TYPE VA
- ☐ TYPE IB  
☐ TYPE IIB  
☐ TYPE IIIB  
☐ TYPE IV-B  
☒ TYPE VB
- ☐ TYPE IV-C

#### MIXED USE AND OCCUPANCY (PER CBC 508 & 509)

- ☐ ACCESSORY OCCUPANCIES (CBC 508.2)  
(ACCESSORY OCCUPANCY < 10% OF STORY)
- ☐ INCIDENTAL USES (CBC 509)
- ☐ NONSEPARATED OCCUPANCIES (CBC 508.3)
- ☐ SEPARATED OCCUPANCIES (CBC 508.4)

#### SPECIAL DETAILED REQUIREMENTS

- ☐ HIGH RISE (CBC 403)
- ☐ ATRIUM (CBC 404)
- ☐ OPEN PARKING GARAGE (CBC 406.5)
- ☐ GROUP I2 (CBC 407) SMOKE COMPARTMENTS REFUGE AREAS
- ☐ HAZARDOUS MATERIALS (CBC 414, CFC CHAPTER 50)

#### SPRINKLERS

- ☒ NEW  
☐ IMPROVEMENT
- ☒ MANDATORY  
☐ VOLUNTARY

#### TYPE

- ☐ NFPA 13  
☒ NFPA 13D  
☐ NFPA 13R
- ☐ FIRE PUMP  
☐ STANDPIPES

#### FIRE ALARM

- ☐ NEW  
☐ IMPROVEMENT  
☐ VOICE EVACUATION
- ☐ MANDATORY  
☐ VOLUNTARY

#### FIRE FLOW REQUIREMENT PER OCFA GUIDELINE B-09 ATTACHMENT 23

FLOW (IN GPM @ 20 PSI): 1,000 GPM DURATION: 1 HR

#### WATER AVAILABILITY

\*PROVIDE COPY OF OCFA WATER AVAILABILITY FORM COMPLETED BY WATER DISTRICT ON FIRE MASTER PLAN\*

FLOW:  
PRESSURE:

- ☒ ON SITE FIRE HYDRANTS  
TOTAL NUMBER: 6

#### EMERGENCY RESPONDER RADIO COVERAGR (BDA)

- ☐ THIS BUILDING SHALL BE EQUIPPED WITH AN EMERGENCY RESPONDER DIGITAL RADIO SYSTEM PER THE REQUIREMENTS OF THE ORANGE COUNTY SHERIFF'S DEPARTMENT-COMMUNICATIONS & TECHNOLOGY DIVISION. FOR THE INITIAL SUBMITTAL, OCCSD/COMM REQUIRES THE ERRCS/BDA/DAS SYSTEM DESIGNER TO PROVIDE THE FOLLOWING FOR PRE-EVALUATION: A. PROJECT NAME; B. SITE ADDRESS; C. PROJECT DESCRIPTION; D. CONTRACTOR CONTACT INFORMATION; E. BDA MODEL (SIN IF AVAILABLE); F. PROPOSED MODE OF OPERATION (CLASS A/B); G. PROPOSED PROJECT TIMELINE. THIS INFORMATION IS TO BE SUBMITTED BY THE DESIGNER VIA EMAIL TO ERRCS@OCCSD.ORG AND BDACERT@OCFA.ORG. CFC 510

### OCFA STANDARD FIRE MASTER PLAN NOTES

#### INSPECTION REQUIREMENTS

- 1.OCFA SITE INSPECTIONS ARE REQUIRED FOR THIS PROJECT. PLEASE SCHEDULE ALL FIELD INSPECTIONS AT LEAST 48 HOURS IN ADVANCE. INSPECTIONS CANCELED AFTER 1 P.M. ON THE DAY BEFORE THE SCHEDULED DATE WILL BE SUBJECT TO A RE-INSPECTION FEE. CALL OCFA INSPECTION SCHEDULING AT (714) 573-6150.
- 2.A LUMBER DROP INSPECTION SHALL BE PERFORMED PRIOR TO BRINGING COMBUSTIBLE MATERIALS (OR COMBUSTIBLE FIXTURES AND FINISHES FOR STRUCTURES OF NON-COMBUSTIBLE CONSTRUCTION). ALL-WEATHER ACCESS ROADS CAPABLE OF SUPPORTING 94,000 LBS., TOPPED WITH ASPHALT, CONCRETE, OR EQUIVALENT SHALL BE IN PLACE AND HYDRANTS OPERATIONAL AT TIME OF LUMBER DROP INSPECTION.
- 3.FOR PROJECTS WITH FUEL MODIFICATION, A VEGETATION CLEARANCE INSPECTION IS REQUIRED PRIOR TO A LUMBER DROP INSPECTION. USE THE FUEL MODIFICATION PLAN SERVICE REQUEST NUMBER TO SCHEDULE THE VEGETATION CLEARANCE INSPECTION.
- 4.PHASED INSTALLATION OF FIRE ACCESS ROADS REQUIRES ADDITIONAL INSPECTIONS NOT COVERED BY THE FEES PAID AT PLAN SUBMITTAL. CONTACT INSPECTION SCHEDULING TO ARRANGE FOR ADDITIONAL INSPECTIONS THAT MAY BE NEEDED AND ANY FEES THAT MAY BE DUE.
- 5.AN ORIGINAL APPROVED, SIGNED, WET-STAMPED OCFA FIRE MASTER PLAN SHALL BE AVAILABLE ON-SITE AT TIME OF INSPECTION.
- 6.ACCESS ROADS AND HYDRANTS SHALL BE MAINTAINED AND REMAIN CLEAR OF OBSTRUCTIONS AT ALL TIMES DURING AND AFTER CONSTRUCTION. AREAS WHERE PARKING IS NOT PERMITTED SHALL BE CLEARLY IDENTIFIED AT ALL TIMES. OBSTRUCTION OF FIRE LANES AND HYDRANTS MAY RESULT IN CANCELLATION OR SUSPENSION OF INSPECTIONS.
- 7.TEMPORARY FUEL TANKS OF 60 OR MORE GALLONS SHALL BE REVIEWED, INSPECTED, AND PERMITTED BY THE OCFA PRIOR TO USE.
- 8.THE PROJECT ADDRESS SHALL BE CLEARLY POSTED AND VISIBLE FROM THE PUBLIC ROAD DURING CONSTRUCTION.
- 9.ALL GATES IN CONSTRUCTION FENCING SHALL BE EQUIPPED WITH EITHER A KNOX OR BREAKAWAY PADLOCK.
10. BUILDINGS OF FOUR OR MORE STORIES SHALL BE PROVIDED WITH STAIRS AND A STANDPIPE BEFORE REACHING 40 FEET IN HEIGHT.

#### GENERAL REQUIREMENTS

11. FIRE LANE WIDTHS SHALL BE MEASURED FROM TOP FACE OF THE CURB TO TOP FACE OF THE CURB FOR FIRE LANES WITH STANDARD CURBS AND GUTTERS AND FROM FLOW-LINE TO FLOW-LINE FOR FIRE LANES WITH MODIFIED CURB DESIGNS (E.G., ROLLED, RAMPED, ETC.). THE DEVELOPER IS RESPONSIBLE TO VERIFY THAT ALL APPROVED PUBLIC WORKS OR GRADING DEPARTMENT STREET IMPROVEMENT PLANS OR PRECISE GRADING PLANS CONFORM TO THE MINIMUM STREET WIDTH MEASUREMENTS PER THE APPROVED OCFA FIRE MASTER PLAN AND STANDARDS IDENTIFIED IN OCFA GUIDELINE B-09 FOR ALL PORTIONS OF THE FIRE ACCESS ROADS.
12. PERMANENT, TEMPORARY, AND PHASED EMERGENCY ACCESS ROADS SHALL BE DESIGNED AND MAINTAINED TO SUPPORT AN IMPOSED LOAD OF 94,000 LBS. AND SURFACED TO PROVIDE ALL-WEATHER DRIVING CAPABILITIES.
13. FIRE LANE SIGNS AND RED CURBS SHALL MEET THE SPECIFICATIONS SHOWN IN OCFA GUIDELINE B-09 AND SHALL BE INSTALLED AS DESCRIBED THEREIN. ADDITIONAL FIRE LANE MARKINGS MAY BE REQUIRED AT THE TIME OF INSPECTION DEPENDING ON FIELD CONDITIONS.
14. ALL FIRE HYDRANTS SHALL HAVE A "BLUE REFLECTIVE PAVEMENT MARKER" INDICATING THEIR LOCATION PER THE OCFA STANDARD. ON PRIVATE PROPERTY MARKERS ARE TO BE MAINTAINED IN GOOD CONDITION BY THE PROPERTY OWNER.
15. ADDRESS NUMBERS SHALL BE LOCATED AND BE OF A COLOR AND SIZE SO AS TO BE PLAINLY VISIBLE AND LEGIBLE FROM THE ROADWAY FROM WHICH THE BUILDING IS ADDRESSED IN ACCORDANCE WITH OCFA GUIDELINE B-09. WAYFINDING SIGNS, WHEN REQUIRED BY THE LOCAL AHJ, SHALL COMPLY WITH THE STANDARDS OF THAT AGENCY. WHEN WAYFINDING SIGNS ARE ALSO REQUIRED BY THE OCFA, THEY MAY BE DESIGNED TO LOCAL AHJ REQUIREMENTS PROVIDED THAT SUCH STANDARDS FACILITATE LOCATION OF STRUCTURES, SUITES, AND DWELLING UNITS BY EMERGENCY PERSONNEL.
16. ACCESS GATES SHALL BE APPROVED PRIOR TO INSTALLATION AND SHALL BE IN COMPLIANCE WITH CHAPTER 5 OF THE CFC AND OCFA GUIDELINES.
17. APPROVED ACCESS WALKWAYS SHALL BE PROVIDED TO ALL REQUIRED OPENINGS AND ALL RESCUE WINDOWS.
18. VEGETATION SHALL BE SELECTED AND MAINTAINED IN SUCH A MANNER AS TO ALLOW IMMEDIATE ACCESS TO ALL HYDRANTS, VALVES, FIRE DEPARTMENT CONNECTIONS, PULL STATIONS, EXTINGUISHERS, SPRINKLER RISERS, ALARM CONTROL PANELS, RESCUE WINDOWS, AND OTHER DEVICES OR AREAS USED FOR FIREFIGHTING PURPOSES. VEGETATION OR BUILDING FEATURES SHALL NOT OBSTRUCT ADDRESS NUMBERS OR INHIBIT THE FUNCTIONING OF ALARM BELLS, HORNS, OR STROBES.
19. DUMPSTERS AND TRASH CONTAINERS LARGER THAN 1.5 CUBIC YARDS SHALL NOT BE STORED IN BUILDINGS OR PLACED WITHIN 5 FEET OF COMBUSTIBLE WALLS, OPENINGS OR COMBUSTIBLE ROOF EAVE LINES UNLESS PROTECTED BY AN APPROVED SPRINKLER SYSTEM.
20. ANY FUTURE MODIFICATION TO THE APPROVED FIRE MASTER PLAN OR APPROVED SITE PLAN, INCLUDING BUT NOT LIMITED TO ROAD WIDTH, GRADE, SPEED HUMPS, TURNING RADII, GATES OR OTHER OBSTRUCTIONS, SHALL REQUIRE REVIEW, INSPECTION, AND APPROVAL BY THE OCFA.
21. APPROVAL OF THIS PLAN SHALL NOT BE CONSTRUED AS APPROVAL OF ANY INFORMATION OR PROJECT CONDITIONS OTHER THAN THOSE ITEMS AND REQUIREMENTS IDENTIFIED IN OCFA GUIDELINE B-09 AND RELATED PORTIONS OF THE 2022 CFC AND CBC. THIS PROJECT MAY BE SUBJECT TO ADDITIONAL REQUIREMENTS NOT STATED HEREIN UPON EXAMINATION OF ACTUAL SITE AND PROJECT CONDITIONS OR DISCLOSURE OF ADDITIONAL INFORMATION.

#### PROJECT-SPECIFIC REQUIREMENTS

22. AN AUTOMATIC FIRE SPRINKLER SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH APPLICABLE CODES AND LOCAL ORDINANCES, AMENDMENTS, AND GUIDELINES. SPRINKLER SYSTEMS, OTHER THAN THOSE LISTED IN CFC 903.4, SHALL BE MONITORED BY AN APPROVED CENTRAL STATION. SEPARATE PLAN SUBMITTALS FOR THE SPRINKLER AND MONITORING SYSTEMS ARE REQUIRED.
23. STRUCTURES LOCATED IN A FIRE HAZARD SEVERITY ZONE OR WILDLAND-URBAN INTERFACE AREA ARE SUBJECT TO THE CONSTRUCTION REQUIREMENTS PRESCRIBED IN CHAPTER 7A OF THE 2022 CBC AND/OR SECTION 337 OF THE 2022 CRC. CONSTRUCTION MATERIALS/METHODS ARE REVIEWED AND INSPECTED BY THE BUILDING DEPARTMENT.
24. ONE OR MORE STRUCTURES SHOWN ON THIS PLAN ARE LOCATED ADJACENT TO A FUEL MODIFICATION AREA. CHANGES TO THE FUEL MODIFICATION ZONE LANDSCAPING, NEW STRUCTURES, OR ADDITIONALTERATION TO EXISTING STRUCTURES REQUIRES REVIEW AND APPROVAL BY THE OCFA.
25. PROJECTS LOCATED IN STATE RESPONSIBILITY AREAS AND IN LOCAL RESPONSIBILITY AREA VHFHSZ SHALL ALSO COMPLY WITH ALL APPLICABLE REQUIREMENTS FROM TITLE 14, DIV. 1.5, CH. 7, SUBCH. 2 "SRA FIRE SAFE REGULATIONS" AND GUIDELINE B-09A.

#### GATES

- ☐ MANUAL  
☐ ELECTRIC

#### OCFA NOTES FOR ELECTRIC VEHICLE GATES

1. A REMOTE OPENING DEVICE IS REQUIRED. THE REMOTE GATE OPENING DEVICE THAT WILL BE INSTALLED IS (CHECK ONE):  

☐ 3M OPTICOM  
☐ CLICKCENTER\* (SINGLE-PULSE MODE WITH 1.5 SECOND TRANSMISSION WINDOW)  
☐ FIRE STROBE ACCESS PRODUCTS, INC.  
☐ TOWAR
2. IN THE EVENT OF LOSS OF NORMAL POWER TO THE GATE OPERATING MECHANISM, IT SHALL BE AUTOMATICALLY TRANSFERRED TO A FAIL-SAFE MODE ALLOWING THE GATE TO BE PUSHED OPEN BY A SINGLE FIREFIGHTER WITHOUT ANY OTHER ACTIONS, KNOWLEDGE, OR MANIPULATION OF THE OPERATING MECHANISM BEING NECESSARY.  

A) A BATTERY MAY ONLY BE USED IN PLACE OF FAIL-SAFE MANUAL OPERATION WHEN THE GATE OPERATOR HAS A FAIL-OPEN MODE THAT WILL AUTOMATICALLY, IMMEDIATELY, AND COMPLETELY OPEN THE GATE AND KEEP IT OPEN UPON REACHING A LOW POWER THRESHOLD, REGARDLESS OF THE PRESENCE OF NORMAL POWER.

B) SHOULD THE GATE BE TOO LARGE OR HEAVY FOR A SINGLE FIREFIGHTER TO OPEN MANUALLY, A SECONDARY SOURCE OF RELIABLE POWER BY MEANS OF AN EMERGENCY GENERATOR OR A CAPACITOR WITH ENOUGH RESERVE TO AUTOMATICALLY, IMMEDIATELY, AND COMPLETELY OPEN THE GATE UPON LOSS OF PRIMARY POWER SHALL BE PROVIDED FOR FAIL-OPEN OPERATION.
3. IN ADDITION TO THE REMOTE OPERATOR, THE GATE CONTROL SHALL BE OPERABLE BY A KNOX EMERGENCY OVERRIDE KEY SWITCH EQUIPPED WITH A DUST COVER. UPON ACTIVATION OF THE KEY SWITCH, THE GATE SHALL OPEN AND REMAIN OPEN UNTIL RETURNED TO NORMAL OPERATION BY MEANS OF THE KEY SWITCH. WHERE A GATE CONSISTS OF TWO LEAVES, THE KEY SWITCH SHALL OPEN BOTH SIMULTANEOUSLY IF OPERATION OF A SINGLE LEAF ON THE INGRESS SIDE DOES NOT PROVIDE FOR THE WIDTH, TURNING RADII, OR SETBACKS NECESSARY FOR FIRE APPARATUS TO NAVIGATE THE VEHICLE ENTRY POINT.
4. THE KEY SWITCH SHALL BE PLACED BETWEEN 42" AND 48" ABOVE THE ROADWAY SURFACE AT THE RIGHT SIDE OF THE ACCESS GATE WITHIN TWO FEET OF THE EDGE OF THE ROADWAY. IN IRVINE, THE SWITCH SHALL BE ON THE LEFT SIDE IN ACCORDANCE WITH IRVINE'S UNIFORM SECURITY ORDINANCE.
5. THE KEY SWITCH SHALL BE READILY VISIBLE AND UNOBSTRUCTED FROM THE FIRE LANE LEADING TO THE GATE.
6. THE KEY SWITCH SHALL BE LABELED WITH A PERMANENT RED SIGN WITH NOT LESS THAN 1/2" CONTRASTING LETTERS READING "FIRE DEPT" OR WITH A "KNOX" DECAL.

### APPLICABLE CODES

- ☒ 2022 CALIFORNIA FIRE CODE  
☐ 2022 CALIFORNIA BUILDING CODE  
☒ 2022 CALIFORNIA RESIDENTIAL CODE  
☐ 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE  
☐ 2022 CALIFORNIA MECHANICAL CODE  
☐ 2022 CALIFORNIA ELECTRICAL CODE  
☐ 2022 CALIFORNIA PLUMBING CODE  
☐ 2022 CALIFORNIA BUILDING ENERGY EFFICIENCY STANDARDS  
☐ APPLICABLE NFPA STANDARDS  
☒ LOCALLY ADOPTED ORDINANCES: RANCH PLAN FIRE PROTECTION PROGRAM  
☒ CONDITIONS OF APPROVAL: COUNTY OF ORANGE  
☒ OCFA GUIDELINES

### DEFERRED SUBMITTALS

THIS PROJECT HAS BEEN PERMITTED WITHOUT REVIEW AND/OR APPROVAL OF THE FOLLOWING DEFERRED SUBMITTALS. PLANS APPROVED BY OCFA SHALL BE OBTAINED FOR EACH DEFERRED ITEM LISTED BELOW PRIOR TO COMMENCING ANY WORK WITHIN THE SCOPE OF SUCH DEFERRAL. DEFERRALS MUST BE REVIEWED AND ACCEPTED BY THE ARCHITECT OR ENGINEER OF RECORD PRIOR TO SUBMITTING FOR REVIEW WITH OCFA. PORTIONS OF THE PROJECT THAT ARE DEFERRED SHALL BE SUBJECT TO THE CODES, STANDARDS, AND OTHER APPLICABLE REQUIREMENTS IN FORCE ON THE DATE THAT THE DEFERRED PLAN IS SUBMITTED TO OCFA.

- ☐ ARCHITECTURAL PLAN  
☐ HIGH PILED COMBUSTIBLE STORAGE  
☐ CHEMICAL USE AND/OR STORAGE  
☐ FUEL TANK (FOR GENERATOR, IF OVER 60 GALLONS)  
☐ BATTERY/ENERGY STORAGE SYSTEM

- ☐ UNDERGROUND SYSTEM SERVING SPRINKLERS, STANDPIPES, AND/OR PRIVATE HYDRANTS

- ☒ SPRINKLER SYSTEM  
☐ STANDPIPE SYSTEM

- ☐ FIRE PUMP  
☐ HOOD AND DUCT EXTINGUISHING SYSTEM  
☐ ALARM SYSTEM

#### PREREQUISITE PLANS

- ☒ PLANNING APPLICATION SR: 546033  
OVERALL FIRE MASTER PLAN SR: 24002015  
☐ METHANE MITIGATION SR:
- ☒ FUEL MODIFICATION PLAN SR: CONCEPTUAL FUEL MODIFICATION REVISION SR24001976

#### REVISION

#### REVISION SCOPE OF WORK

### PROJECT DIRECTORY

#### ARCHITECT/ENGINEER

BUSINESS NAME: HUNSAKER & ASSOCIATES IRVINE, INC  
CONTACT NAME:  
ADDRESS: 3 HUGHES  
CITY: IRVINE STATE: CA ZIP: 92618  
PHONE: (949) 583-1010  
EMAIL:

#### PROPERTY OWNER/HOA

BUSINESS NAME: RMV PA3 DEVELOPMENT, LLC  
CONTACT NAME:  
ADDRESS: 28811 ORTEGA HIGHWAY  
CITY: SAN JUAN CAPISTRANO STATE: CA ZIP: 92675  
PHONE: (949) 240-3363  
EMAIL:

#### TENANT

BUSINESS NAME:  
CONTACT NAME:  
ADDRESS:  
CITY: STATE: ZIP:  
PHONE:  
EMAIL:

DESIGNED	6	NO.	DATE
DAVID OATIS	5		
DRAWN	4		
FSP	3		
CHECKED	2		
FSP	1		
DATE			
SCALE			
SPECIFIED ON SHEET			

OCFA REVIEW AND INSPECTIONS (OCFA USE ONLY)	
NO OCFA REVIEW REQUIRED	<input type="checkbox"/>
PLAN REVIEW ONLY	<input type="checkbox"/>
PLAN REVIEW AND INSPECTION	<input type="checkbox"/>

PLANS PREPARED BY:  
**firesafe** PLANNING, INC.  
29506 AIRCROSS STREET  
RANCHO MISSION VIEJO, CA 92684  
(949) 240-5911

RIENDA AQ43 AT RANCHO MISSION VIEJO PLANNING SUB-AREA 3.5  
VESTING TENTATIVE TRACT NO. 19322  
FIRE MASTER PLAN  
ORANGE COUNTY FIRE AUTHORITY  
COMMUNITY RISK REDUCTION - PLANNING AND DEVELOPMENT SECTION





REVISION 02/2023 JAH

SERVICE REQUEST NUMBER  
25000828

SHEET  
F-1

1 OF 4





**PARKING ENFORCEMENT LETTER**

MAY 6, 2025

PLANNING AND DEVELOPMENT SERVICES SECTION  
ORANGE COUNTY FIRE AUTHORITY  
1 FIRE AUTHORITY ROAD  
IRVINE, CA 92602

REUDA PLANNING AREA 3.5    0434 FIRE MASTER PLAN, TENTATIVE TRACT NO. 19322, RANCHO MISSION VIEJO, COUNTY OF ORANGE, CA, OCCA PARKING ENFORCEMENT PLAN

THE FIRE LANE PARKING ENFORCEMENT PLAN FOR THE ABOVE REFERENCED PROJECT IS STATED AS FOLLOWS:

ALL FIRE LANES WITHIN PA 3.5 SHALL BE MAINTAINED AND IN NO EVENT SHALL PARKING BE PERMITTED ALONG ANY PORTION OF A STREET OR DRIVE THAT REQUIRED FIRE LANES OR ANY AREA DESIGNATED AS A FIRE LANE FOR TURN-AROUND OR DRIVE THROUGH PURPOSES.

PA 3.5 HOMEOWNER'S ASSOCIATION SHALL ADOPT REASONABLE RULES AND REGULATIONS REGARDING THE PARKING OF VEHICLES ALONG THE STREETS, ROADS AND OR DRIVES WITHIN THE PROJECT THAT ARE NOT IN CONFLICT WITH APPLICABLE LAW.

IN FURTHERANCE THEREOF, PA 3.5 HOMEOWNER'S ASSOCIATION, THROUGH ITS OFFICERS, COMMITTEES AND AGENTS WILL ESTABLISH THE "PARKING" AND "NO PARKING" AREAS WITHIN THE PROPERTY IN ACCORDANCE WITH SECTION 22659.2 OF THE CALIFORNIA VEHICLE CODE AND THE RANCH FIRE PROTECTION PROGRAM. THE LAW SHALL BE ENFORCED BY THE CALIFORNIA DEPARTMENT OF TRANSPORTATION BY ALL LAWFUL MEANS, INCLUDING, WRITTEN WARNINGS, CITING, LEVYING FINES AND TOWING VEHICLES IN VIOLATION.

PA 3.5 HOMEOWNER'S ASSOCIATION WILL CONTRACT WITH A CERTIFIED PATROL AND TOWING COMPANY TO REMOVE VEHICLES THAT VIOLATE NO PARKING RESTRICTIONS. FIRST TIME VIOLATORS WILL RECEIVE A WRITTEN WARNING AND WITH SUBSEQUENT VIOLATIONS, THE VEHICLE SHALL BE SUBJECT TO TOWING. THE VEHICLE OWNER SHALL BE RESPONSIBLE FOR ALL COSTS INCURRED IN REMEDYING SUCH VIOLATION, INCLUDING WITHOUT LIMITATION TOWING COST, CITATIONS AND LEGAL FEES.


COMBUSTIBLE CONSTRUCTION LETTER

MAY 6, 2025

ORANGE COUNTY FIRE AUTHORITY  
1 FIRE AUTHORITY ROAD  
IRVINE, CA 92602



SUBJECT: COMBUSTIBLE CONSTRUCTION LETTER: RMV RIENDA PA3.5 AQ43 FIRE MASTER PLAN - OCFA S.R. 25000828  
RANCHO MISSION VIEJO, COUNTY OF ORANGE

THE PURPOSE OF THIS LETTER IS TO NOTIFY YOU THAT THIS PROJECT SHALL INSTALL ALL REQUIRED PAVED FIRE ACCESS  
ROADS THAT MEET O.C.F.A. GUIDELINES PER THE APPROVED PLANS. ALL FIRE HYDRANTS AND WATER SUPPLY FOR  
FIREFIGHTING PURPOSES SHALL BE INSTALLED PER THE APPROVED PLANS AND SHALL MEET ALL FIRE FLOWS  
REQUIREMENTS, PRIOR TO ANY COMBUSTIBLE CONSTRUCTION MATERIALS BEING DELIVERED FOR CONSTRUCTION.



			CIVIL ENGINEER:	ARCHITECTURE/PLANNING:	PREPARED BY:	PREPARED FOR:	PREPARED FOR:	TITLE:	DATE:
			 <b>PROACTIVE</b> ENGINEERING CONSULTANTS 27051 Towne Centre Drive, Suite 270 Foothill Ranch, CA 92610 (949) 716-7460	 <b>WHA.</b> ARCHITECTS . PLANNERS . DESIGNERS 680 NEWPORT CENTER DRIVE, SUITE 300 NEWPORT BEACH, CA 92660	 <b>firesafe</b> PLANNING, INC. 28506 AIROSO STREET RANCHO MISSION VIEJO, CA 92694 (949) 240-5911	 <b>LENNAR</b> 2000 FIVEPOINT, SUITE 3RD FLOOR IRVINE, CA 92618 (949) 240-8000	 <b>RMV PA3</b> DEVELOPMENT, LLC 28811 ORTEGA HIGHWAY SAN JUAN CAPISTRANO, CA 92675 (949) 240-5363	<b>FIRE MASTER PLAN</b> <b>RANCHO MISSION VIEJO RIENDA PA 3.5</b> <b>NOTES AND DETAILS</b> VTTM 19322 - AQ43 OCFA SR 25000828  ORANGE COUNTY FIRE AUTHORITY	05/06/2025
2									SHEET:
3									
4									





**LEGEND**

- EXISTING FIRE HYDRANT PER PREVIOUSLY APPROVED BACKBONE FIRE MASTER PLAN SR542339.
- PROPOSED PUBLIC FIRE HYDRANT WITH BLUE REFLECTIVE FIRE HYDRANT MARKER. MARKER SHALL BE PLACED 6" FROM CENTERLINE OF STREET (SEE ARCHITECTURAL PLAN FOR FINAL DESIGN AND LOCATIONS)
- 4" MIN. UNIT ADDRESSING (SEE ARCHITECTURAL PLAN FOR FINAL DESIGN AND LOCATIONS)
- 300' HOSE PULL DISTANCE - FOR SINGLE FAMILY BUILDING TO THE FRONT DOOR
- PROPOSED FIRE LANE SIGNAGE AS INDICATED ON PLAN AND DETAILS HEREON
- PROPOSED FIRE ACCESS ROAD WITH ALL-WEATHER PAVED SURFACE DESIGNED, AT A MINIMUM, TO THE AASHTO H-20 STANDARD PER THE RPFFP.
- EXISTING FIRE ACCESS ROAD
- INDICATES PROPOSED STRUCTURES MEETING THE 2022 CALIFORNIA RESIDENTIAL CODE SECTION R337
- INDICATES TURNING RADIUS PER 2022 OCFI GUIDELINE B-01: 20' WIDE PATH WITH 20' RADIUS INSIDE AND 40' RADIUS OUTSIDE.
- LOT  
PLAN TYP. -
- INDICATES LOT NUMBER, UNIT NUMBER AND PLAN TYPE.

**CONSTRUCTION NOTES**

- EXISTING FIRE LANE ENTRANCE SIGN PER PREVIOUSLY APPROVED OVERALL FIRE MASTER PLAN
- INSTALL FIRE LANE 'NO PARKING' SIGN PER DETAIL SHEET FM-2 AND OCFI GUIDELINE B-01
- INSTALL FIRE LANE 'BEGIN NO PARKING' SIGN PER DETAIL SHEET F-2 AND OCFI GUIDELINE B-01
- INSTALL FIRE LANE 'END NO PARKING' SIGN PER DETAIL SHEET F-2 AND OCFI GUIDELINE B-01
- INSTALL BLUE FIRE HYDRANT MARKER THAT SHALL BE PLACED 4" FROM CENTERLINE OF HYDRANT SIDE OF STREET

**RANCH FIRE PROTECTION PROGRAM ATTACHMENTS**

RANCH PLAN FIRE PROTECTION PROGRAM WAS APPROVED BY ORANGE COUNTY FIRE AUTHORITY AND ORANGE COUNTY BOARD OF SUPERVISORS DATED: JULY 31, 2007 AND AMENDMENT NO. 1, DATED: MARCH 25, 2013; AMENDMENT NO. 2, DATED: AUGUST 14, 2014 AND AMENDMENT NO. 3, DATED: MARCH 31, 2022.

ATTACHMENTS USED WITH THIS SUBMITTAL:

- 1. FIRE LANE NO PARKING SIGN LOCATIONS
- 2. FIRE LANE NO PARKING SIGN
- 3. FIRE LANE BEGINNING NO PARKING SIGN
- 4. MOUNTING SPECIFICATION FOR FIRE LANE SIGNS AND NO PARKING SIGNS
- 5. STREET WIDTHS
- 6. HYDRANT DISTRIBUTION TABLE
- 7. FIRE FLOW REQUIREMENT TABLE
- 8. HYDRANT DISTRIBUTION TABLE
- 9. FIRE HYDRANT LOCATIONS
- 10. BLUE DOT HYDRANT MARKER LOCATION
- 11. ADS-A19...CUL DE SAC WITH RAISED LANDSCAPE MEDIAN

BUILDING INFORMATION AND DATA					
PLAN DESCRIPTION	STORIES	OCCUPANCY TYPE	CONSTRUCTION TYPE	AUTOMATIC FIRE SPRINKLERS	SQUARE FOOTAGE
PLAN #1	1	R-3	V-B	NFPA 13D	2,254 SF
PLAN #1X	2	R-3	V-B	NFPA 13D	2,941SF
PLAN #2	1	R-3	V-B	NFPA 13D	2,303 SF
PLAN #2X	2	R-3	V-B	NFPA 13D	2,900 SF

**MIN. FIRE FLOW AND FIRE HYDRANT SPACING REQUIREMENTS**

MINIMUM FIRE FLOW OF 1,000 GPM AT 20PSI FOR 1 HOUR REQUIRED PER THE LARGEST BUILDING OF APPROXIMATELY 2,941 SQ.FT. AND TYPE V-B CONSTRUCTION. A MINIMUM OF ONE (1) FIRE HYDRANTS ARE REQUIRED SPACED NO MORE THAN 600- FEET FROM HYDRANT TO HYDRANT, NO MORE THAN 300- FEET FROM ANY BUILDING, AND NO MORE THAN 250- FEET FROM THE END OF A DEAD-END FIRE ACCESS ROAD.

**FIRE FLOW TEST REQUIREMENT**

NOTE: A FIRE FLOW MODELING CALCULATION AND FIRE FLOW TEST SHALL BE COMPLETED AND OBTAINED FROM THE SANTA MARGARITA WATER DISTRICT PRIOR TO LUMBER DROP INSPECTION. THE FIRE FLOW TEST SHALL INDICATE THE FLOW AT 20 PSI, AND SHALL BE PROVIDE TO OCFI PRIOR TO SCHEDULING THE LUMBER DROP INSPECTION.

NO.	DATE	REVISIONS	CIVIL ENGINEER:	ARCHITECTURE/PLANNING:	PREPARED BY:	PREPARED FOR:	PREPARED FOR:	TITLE:	DATE:
1								FIRE MASTER PLAN	05/06/2025
2								RANCHO MISSION VIEJO RIENDA PA 3.5	
3								FIRE MASTER LAYOUT	
4								VTTM 19322 - AQ43	
								OCFA SR 25000828	
								ORANGE COUNTY FIRE AUTHORITY	

GRAPHIC SCALE  
1 inch = 40 ft.

PROACTIVE  
ENGINEERING CONSULTANTS  
27051 Towne Centre Drive, Suite 270  
Foothill Ranch, CA 92610 (949) 716-7460

WHA  
680 NEWPORT CENTER DRIVE, SUITE 300  
NEWPORT BEACH, CA 92660

firesafe  
PLANNING, INC.  
28506 AIROSO STREET  
SAN JUAN CAPISTRANO, CA 92694  
(949) 240-5911



LENNAR  
2000 FIVEPOINT, SUITE 3RD FLOOR  
IRVINE, CA 92618  
(949) 439-8000

RMV PA3  
DEVELOPMENT, LLC  
28811 ORTEGA HIGHWAY  
SAN JUAN CAPISTRANO, CA 92675  
(949) 240-3363

OCFA 25000828 - RIENDA AQ43 - FIRE MASTER PLAN

DATE: 05/06/2025  
SHEET: 13 OF 14  
F-3  
OCFA 25000828 - RIENDA AQ43 - FIRE MASTER PLAN





- LEGEND**
- EXISTING FIRE HYDRANT PER PREVIOUSLY APPROVED BACKBONE FIRE MASTER PLAN SR542339.
  - PROPOSED PUBLIC FIRE HYDRANT WITH BLUE REFLECTIVE FIRE HYDRANT MARKER. MARKER SHALL BE PLACED 6" FROM CENTERLINE OF STREET
  - 4" MIN. UNIT ADDRESSING (SEE ARCHITECTURAL PLAN FOR FINAL DESIGN AND LOCATIONS)
  - 300' HOSE PULL DISTANCE - FOR SINGLE FAMILY BUILDING TO THE FRONT DOOR
  - PROPOSED FIRE LANE SIGNAGE AS INDICATED ON PLAN AND DETAILS HEREON
  - PROPOSED FIRE ACCESS ROAD WITH ALL-WEATHER PAVED SURFACE DESIGNED, AT A MINIMUM, TO THE AASHTO H-20 STANDARD PER THE RPFFPP.
  - EXISTING FIRE ACCESS ROAD
  - INDICATES PROPOSED STRUCTURES MEETING THE 2022 CALIFORNIA RESIDENTIAL CODE SECTION R307
  - INDICATES TURNING RADIUS PER 2022 OCFI GUIDELINE B-01: 20' WIDE PATH WITH 20' RADIUS INSIDE AND 40' RADIUS OUTSIDE.
  - LOT PLAN TYP. INDICATES LOT NUMBER, UNIT NUMBER AND PLAN TYPE.

- CONSTRUCTION NOTES**
- EXISTING FIRE LANE ENTRANCE SIGN PER PREVIOUSLY APPROVED OVERALL FIRE MASTER PLAN
  - INSTALL FIRE LANE 'NO PARKING' SIGN PER DETAIL SHEET FM-2 AND OCFI GUIDELINE B-01
  - INSTALL FIRE LANE 'BEGIN NO PARKING' SIGN PER DETAIL SHEET F-2 AND OCFI GUIDELINE B-01
  - INSTALL FIRE LANE 'END NO PARKING' SIGN PER DETAIL SHEET F-2 AND OCFI GUIDELINE B-01
  - INSTALL BLUE FIRE HYDRANT MARKER THAT SHALL BE PLACED 4" FROM CENTERLINE OF HYDRANT SIDE OF STREET

- RANCH FIRE PROTECTION PROGRAM ATTACHMENTS**
- RANCH FIRE PROTECTION PROGRAM WAS APPROVED BY ORANGE COUNTY FIRE AUTHORITY AND ORANGE COUNTY BOARD OF SUPERVISORS DATED: JULY 31, 2007 AND AMENDMENT NO. 1, DATED: MARCH 25, 2013; AMENDMENT NO. 2, DATED: AUGUST 14, 2014 AND AMENDMENT NO. 3, DATED: MARCH 31, 2022.
- ATTACHMENTS USED WITH THIS SUBMITTAL:
- 1. 24/28 FIRE LANE NO PARKING SIGN LOCATIONS
  - 2. FIRE LANE NO PARKING SIGN
  - 3. FIRE LANE BEGIN/END NO PARKING SIGN
  - 4. MOUNTING SPECIFICATION FOR FIRE LANE SIGNS AND NO PARKING SIGNS
  - 5. STREET WIDTHS
  - 6. HYDRANT DISTRIBUTION TABLE
  - 7. FIRE FLOW REQUIREMENT TABLE
  - 8. HYDRANT DISTRIBUTION TABLE
  - 9. FIRE HYDRANT LOCATIONS
  - 10. BLUE DOT HYDRANT MARKER LOCATION
  - 11. ADS-A19 - CUL DE SAC WITH RAISED LANDSCAPE MEDIAN

BUILDING INFORMATION AND DATA					
PLAN DESCRIPTION	STORIES	OCCUPANCY TYPE	CONSTRUCTION TYPE	AUTOMATIC FIRE SPRINKLERS	SQUARE FOOTAGE
PLAN #1	1	R-3	V-B	NFPA 13D	2,254 SF
PLAN #1X	2	R-3	V-B	NFPA 13D	2,941 SF
PLAN #2	1	R-3	V-B	NFPA 13D	2,303 SF
PLAN #2X	2	R-3	V-B	NFPA 13D	2,900 SF

**MIN. FIRE FLOW AND FIRE HYDRANT SPACING REQUIREMENTS**



MINIMUM FIRE FLOW OF 1,000 GPM AT 20PSI FOR 1 HOUR REQUIRED PER THE LARGEST BUILDING OF APPROXIMATELY 2,941 SQ. FT. AND TYPE V-B CONSTRUCTION. A MINIMUM OF ONE (1) FIRE HYDRANTS ARE REQUIRED SPACED NO MORE THAN 600- FEET FROM HYDRANT TO HYDRANT, NO MORE THAN 300- FEET FROM ANY BUILDING, AND NO MORE THAN 250- FEET FROM THE END OF A DEAD-END FIRE ACCESS ROAD.

**FIRE FLOW TEST REQUIREMENT**

NOTE: A FIRE FLOW MODELING CALCULATION AND FIRE FLOW TEST SHALL BE COMPLETED AND OBTAINED FROM THE SANTA MARGARITA WATER DISTRICT PRIOR TO LUMBER DROP INSPECTION. THE FIRE FLOW TEST SHALL INDICATE THE FLOW AT 20 PSI, AND SHALL BE PROVIDED TO OCFI PRIOR TO SCHEDULING THE LUMBER DROP INSPECTION.

<table><tr><th>NO.</th><th>DATE</th><th>REVISIONS</th></tr><tr><td>1</td><td></td><td></td></tr><tr><td>2</td><td></td><td></td></tr><tr><td>3</td><td></td><td></td></tr><tr><td>4</td><td></td><td></td></tr></table>		NO.	DATE	REVISIONS	1			2			3			4			<p>CIVIL ENGINEER:</p> <p><b>PROACTIVE</b> ENGINEERING CONSULTANTS 27051 Towne Centre Drive, Suite 270 Foothill Ranch, CA 92610 (949) 716-7460</p>		<p>ARCHITECTURE/PLANNING: ARCHITECTS - PLANNERS - DESIGNERS</p> <p><b>WHA</b> 680 NEWPORT CENTER DRIVE, SUITE 300 NEWPORT BEACH, CA 92660</p>		<p>PREPARED BY:</p> <p><b>firesafe</b> PLANNING, INC. 28506 AIROSO STREET RANCHO MISSION VIEJO, CA 92694 (949) 240-5911</p>		<p>PREPARED FOR:</p> <p><b>LENNAR</b> 2000 FIVEPOINT, SUITE 3RD FLOOR IRVINE, CA 92618 (949) 349-8000</p>		<p>PREPARED FOR:</p> <p><b>RMV PA3 DEVELOPMENT, LLC</b> 28811 ORTEGA HIGHWAY SAN JUAN CAPISTRANO, CA 92675 (949) 240-3363</p>		<p>TITLE:</p> <p><b>FIRE MASTER PLAN RANCHO MISSION VIEJO RIENDA PA 3.5 FIRE MASTER LAYOUT VTM 19322 - AQ43 OCFA SR 25000828</b></p> <p>ORANGE COUNTY FIRE AUTHORITY</p>		<p>DATE:</p> <p>05/06/2025</p> <p>SHEET:</p> <p>112 OF 112 <b>F-4</b> FIRE MASTER PLAN</p>
NO.	DATE	REVISIONS																											
1																													
2																													
3																													
4																													





### 2022 CRC SECTION R337 SCREENING FORM

CRC Section 337 Code	Yes	No
R337.3.1 General	X	
R337.3.2 Qualifications by Testing	X	
R337.3.3 Approved Agency	X	
R337.3.4 Labeling	X	
R337.3.5 R337.3.5.1 & R337.3.5.2 Weathering and surface treatment protection	X	
R337.3.5.2.1 Fire-retardant-treated wood	X	
R337.3.5.2.2 Fire-retardant-treated wood shingles and shakes	X	
R337.3.5.3 Surface treatment protection	X	
R337.3.6 Alternates for materials, design, tests methods of construction	X	
R337.3.7 Standards of Quality	X	
R337.4.1 Ignition-Resistant Construction & General	X	
R337.4.2 Ignition-Resistant Material	X	
R337.4.3 Conditions of acceptance for ignition-resistant material	X	
R337.4.3.1 Fire Testing of wood structural panels	X	
R337.4.4 Alternate methods for determining ignition-resistant material	X	
R337.5 & R337.5.1 Roofing & Roofing General	X	
R337.5.2 Roof Coverings	X	
R337.5.3 Roof Valleys	X	
R337.5.4 Roof Gutters	X	
R337.6 & R337.6.1 Vents & Vents General	X	
R337.6.2 Vents Requirements	X	
R337.6.2.1 Off ridge and ridge vents	X	
R337.7, R337.7.1 & R337.7.2 Exterior Covering, Scope & General	X	
R337.7.3 Exterior Wall Coverings	X	
R337.7.3.1 Extent of Exterior Wall Coverings	X	
R337.7.4 & R337.7.4.1 Exterior Wall Assemblies & Conditions of Acceptance	X	
R337.7.5 Open Roof Eaves	X	
R337.7.6 Enclosed Roof Eaves and Roof Eave Soffits	X	
R337.7.7 Exterior Porch Ceilings	X	
R337.7.8 Floor Projections	X	
R337.7.9 Underfloor Protection	X	
R337.7.10 Underside of Appendages	X	
R337.7.11 Conditions of acceptance when treated in accordance with ASTM E2957	X	
R337.8 & R337.8.1 Exterior Windows, Skylights and Doors & General	X	
R337.8.2 Exterior glazing	X	
R337.8.2.1 Exterior Windows, Skylights and exterior glazed door assembly requirements	X	
R337.8.2.2 Operable Skylights	X	
R337.8.2.3 Structural glass veneer	X	
R337.8.3 Exterior Doors	X	
R337.8.3.1 Exterior Door Glazing	X	
R337.8.4 Garage Door Perimeter Gap	X	
R337.9, R337.9.1 & R337.9.1.1 Decking, General & Flashing	X	
R337.9.2 Where required	X	
R337.9.3 Decking Surfaces	X	
R337.9.4 Requirements of type of ignition-resistant material in Section R337.9.3, Item 1	X	
R337.9.4.1 Conditions of acceptance for ASTM E2632	X	
R337.9.4.2 Conditions of acceptance for ASTM E2728	X	
R337.9.5 Requirements for type of material in Section R337.9.3, Item 7	X	
R337.10 & R337.10.1 Accessory Buildings and Miscellaneous Structures & General	X	
R337.10.2 Accessibility	X	
R337.10.3 Where required	X	
R337.10.3.1 Structures and Accessory Buildings within 3 feet	X	
R337.10.3.2 Accessory Buildings greater than 120 sq. ft., located 3 feet or more but less than 50 feet	X	
R337.10.3.3 Accessory Buildings 120 sq. ft. or less, located 3 feet or more but less than 50 feet	X	
R337.10.3.4 Miscellaneous Structures located 3 feet or more but less than 50 feet	X	
R337.10.4 Roof Construction	X	

If separate buildings within the same Tract have different responses above, then you must submit additional Screening Form(s) for each portion of the development that has different designs.

Name of Community: RMV RIENDA - SUB AREA 3.5 - AQ43

List the final tract and lot numbers on the lines below that this form is associated to:  
VTTM 19322 - LOTS 1 THROUGH 49

David Otis David Otis as Agent of LENNAR - 949-240-5911, MAY 6, 2025

### OCFA APPROVAL

<b>ORANGE COUNTY FIRE AUTHORITY</b>	
Reviewed by Planning & Development	
Service Request Expires After 6 Months of Inactivity	
Approval subject to field inspection and required test, notations hereon, conditions in correspondence and conformance with applicable regulations. The stamping of these plans shall not be held to permit or approve the violation of any law.	
OCFA SR #: <b>25000827 PR146 OCFA Approved</b>	
Fee Codes: <b>PR146</b>	
Plan Type: <b>Fire Protection Plan</b>	
By: <b>branslegers</b>	
Date: <b>05/28/2025</b>	
ONLY STAMPED SHEETS REVIEWED BY ORANGE COUNTY FIRE AUTHORITY	
Call at least 72 hours in advance to schedule inspections: (714) 573-6150	
Notes:	

NO.	DATE	REVISIONS	CIVIL ENGINEER:	ARCHITECTURE/PLANNING:	PREPARED BY:	PREPARED FOR:	PREPARED FOR:	TITLE:	DATE:
1								FIRE PROTECTION PLAN	05/06/2025
2								RANCHO MISSION VIEJO RIENDA PA 3.5	
3								VTTM 19322 - AQ43	
4								OCFA SR 25000827	
ORANGE COUNTY FIRE AUTHORITY									

GRAPHIC SCALE

1 inch = 60 ft.

**PROACTIVE**  
ENGINEERING CONSULTANTS  
27051 Towne Centre Drive, Suite 270  
Foothill Ranch, CA 92610 (949) 716-7460

**WHA**  
ARCHITECTS, PLANNERS, DESIGNERS  
680 NEWPORT CENTER DRIVE, SUITE 300  
NEWPORT BEACH, CA 92660

**firesafe**  
PLANNING, INC.  
28506 AIROSO STREET  
SAN JUAN CAPISTRANO, CA 92694  
(949) 240-5911

**LENNAR**  
2000 FIVEPOINT, SUITE 3RD FLOOR  
IRVINE, CA 92618  
(949) 349-8000

**RMV PA3**  
DEVELOPMENT, LLC  
28811 ORTEGA HIGHWAY  
SAN JUAN CAPISTRANO, CA 92675  
(949) 240-3363